


DO NOT SCALE FROM THIS DRAWING  
ALL DIMENSIONS TO BE VERIFIED BY THE CONTRACTOR ON SITE



Where original skirting boards are present - to be carefully removed and reinstalled above new acoustic floor.

Flanking strips to be installed as part of acoustic flooring system.

Suspended ceiling depth increased to preserve depth of any original cornice profiles.

Flexible intumescent sealant around perimeter junction of plasterboard.

New acoustic flooring system laid over existing floor boards.

Floors stripped back to existing floor boards. Existing boards to remain.

Original 'pugging' to remain where present - removed locally to enable service penetrations.

Original 'lath & plaster' ceiling to remain where present.

New suspended ceiling system to be installed below original ceiling.  
150mm standard drop, increased to preserve depth of any original cornice profiles.

1No. layer of 19mm Gyproc SoundBloc F  
1No. layer of 15mm Gypsum-based plasterboard.

60MIN. FIRE COMPARTMENT AREA.

Suspended Ceiling Detail  
below Original Ceiling scale 1:5

| REV | DESCRIPTION | DATE | BY | CHKD |
|-----|-------------|------|----|------|
|-----|-------------|------|----|------|

TURNER  
JACKSON+DAY  
ASSOCIATES

125 John Wilson Business Park  
Whitstable  
Kent CT15 3QT  
t: 01227 261453  
e: enquiries@tjda.co.uk  
www.turner-jacksonday.co.uk

client details  
Mile Property Group Ltd

project details  
Custom House  
The Terrace, Gravesend, DA12 2DE

drawing title  
DETAIL 05  
Suspended Ceiling Detail

date scale drawn by checked by  
Apr'21 1:5 @ A3 AR

|             |             |          |
|-------------|-------------|----------|
| project no: | drawing no. | revision |
| 1735        | 104         |          |