



Stone around pond
showing similar
look and style



Dryopteris filix



Campanula
Portenschlagiana



Acer palmatum dissectum
'Garnet'



Ligularia dentata
'Desdemona'

- Luctec Gemeni XF LED Bollard lights

All trees must be planted into a pit twice the width and depth of the root ball with an appropriate compost (recommended by the supplier) and top dressed with a multi-purpose fertiliser when first planted. Make sure the newly planted trees are well heeled in for stability and keep well watered.

Lavandula stoechas must be trimmed back in August removing dead flowers and approximately 1" of foliage.

Darmera peltata. keep soil well moist.
Remove dead leaves.

- Excavate pond, remove surplus material
- Install a 100mm deep x 200mm wide level concrete outer rim shelf around the rim of

- Excavate pond, remove surplus material
- Install a 100mm deep x 200mm wide level concrete outer rim shelf around the rim of the pool
- Install a 25mm layer of soft sand to the pool shell.
- Install a Geotextile liner cushion fleece
- Install a 1mm thick Firestone Butyl liner
- Install a single layer of engineering bricks around the entire rim.
- Install a 25mm overflow.
- Install a mixed layer of 10-50mm diameter rounded Scottish pebbles/cobbles and 20mm flint gravel.

All fences to be painted black using exterior fence paint.

All levels shown are indicative only and are to be confirmed on site before any construction commences. Levels under existing trees to be retained.



Project: 23 ELM ROAD

Site address: 23 ELM ROAD, GRAVESEND,
KENT DA12 5LE

Designed by:
VG Oakleigh Manor Ltd.
victor@oakleighmanor.co.uk

Scale:	1:50 @ A2
--------	-----------

Drawing	03
---------	----

Date:	24/07/2023
-------	------------

Rev. 00

DO NOT SCALE from this drawing.


© Oakleigh Manor Landscape Design and Build Ltd.



Wall light



Luctec Gemeni XF LED Bollard lights



Setts transition points
along pathway.



Setts edging to lawn.



Setts transition points
along pathway.

SCALE: 1:50 @ A1



SCALE: 1:50 @ A1