

Hardscape Schedule Update_CHERRY DENE

Hardscape Name	Main Area	Main Perimeter	Main Components	Specification	Approx. Price	Comments
Decorative Aggregate w/3.0mm Cor-ten Steel	14.51sq m	28lm		Gravel surface on compacted sub-base with	£ 87.90	
Hedge (Evergreen 2-2.5m RB)	19.66sq m	39lm		Planted in trench 450x300mm min with BS	£ 516.00	
Hedge (Mixed Native)	130.85sq m	224lm		Planted in trench 450x300mm min with BS	£ -	
Hedge (Single Species Native)	10.42sq m	28lm		Planted in trench 450x300mm min with BS	£ 91.70	
Long Grass (set aside area)	68.08sq m	87lm		Sown with meadow or long-grass seed mix	£ -	
Permeable Concrete Block Paving with Edging	334.67sq m	184lm		Permeable concrete blocks laid in 45° or 90°	£ 127.71	
Planted Area	80.11sq m	74lm		Prepared to 300–450mm depth with BS 386	£ 137.54	
Planted Area (Dense)	215.85sq m	310lm		Prepared to 300–450mm depth with BS 386	£ 137.54	
Planted Area (Mixed)	44.65sq m	72lm		Prepared to 300–450mm depth with BS 386	£ 137.54	
Porcelain Paving 900X600mm	189.43sq m	183lm		External-grade vitrified porcelain slabs laid	£ 270.61	
Turfed Lawn Areas	743.37sq m	306lm		Fine-grade cultivated turf laid in stretcher b	£ 40.05	