



Tree Data Schedule

| Reference | Age & Species                                                    | Height (m) | Crown H (m) | Crown Spread (m) |   |     | Scaled Tree Diagram (m) | Notes                                                                                                                                                                                                                                                                                                      | Recommendations                          |                    | Vigour   | Ancestry Value          |                       |
|-----------|------------------------------------------------------------------|------------|-------------|------------------|---|-----|-------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|--------------------|----------|-------------------------|-----------------------|
|           |                                                                  |            |             | W                | N | E   |                         |                                                                                                                                                                                                                                                                                                            | Independent of any development proposals |                    |          | Physiological Condition | Life Expectancy (yrs) |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            | Priority                                 | Inspect (Free (m)) |          |                         |                       |
| T1        | Semi-Mature<br>Lawson Cypress<br><i>Chamaecyparis lawsoniana</i> | 6.5        | 2           | 17               | 3 | 3   |                         | Position: Situated within the rear garden.<br>Form: Single stemmed and vertical with a narrow, upright habit.<br>History: No evidence of significant pruning.<br>Defects: No significant defects observed.                                                                                                 | No action required.                      |                    | Moderate | Low                     |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            | n/a                                      | 3                  | Good     | 40+                     |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            |                                          |                    |          |                         |                       |
| T2        | Semi-Mature<br>Californian Lilac<br><i>Ceanothus</i> sp.         | 5          | 2           | 14               | 2 | 3.5 |                         | Position: Situated within the rear garden.<br>Form: Twin-stemmed at 1m with a slightly unbalanced crown.<br>History: No evidence of significant pruning.<br>Defects: Significant bark wound to stem (acceptable condition at present).<br>Other: Recorded stem diameter is equivalent for 2 stems at 10cm. | No action required.                      |                    | Moderate | Low                     |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            | n/a                                      | 3                  | Good     | 20-40                   |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            |                                          |                    |          |                         |                       |
| T3        | Early-Mature<br>Buddleia<br><i>Buddleia</i> sp.                  | 4.5        | 1.5         | 16               | 3 | 2   |                         | Position: Situated within the rear garden.<br>Form: Multi-stemmed at 1m with an unbalanced crown.<br>History: No evidence of significant pruning.<br>Defects: No significant defects observed.<br>Other: Recorded stem diameter is equivalent for 2 stems (10cm & 12cm).                                   | No action required.                      |                    | Moderate | Low                     |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            | n/a                                      | 3                  | Good     | 40+                     |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            |                                          |                    |          |                         |                       |
| T4        | Young<br>Elder<br><i>Sambucus nigra</i>                          | 3.5        | 1.5         | 10               | 1 | 1.5 |                         | Form: Twin-stemmed at ground level with a slightly unbalanced crown.<br>History: No evidence of significant pruning.<br>Defects: No significant defects observed.                                                                                                                                          | No action required.                      |                    | Moderate | Low                     |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            | n/a                                      | 3                  | Good     | 40+                     |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            |                                          |                    |          |                         |                       |
| T5        | Early-Mature<br>Cherry<br><i>Prunus</i> sp.                      | 6.5        | 2.5         | 38               | 4 | 4.5 |                         | Position: Situated within the front garden.<br>Form: Multi-stemmed at 3m with a balanced crown.<br>History: Reduced.<br>Defects: No significant defects observed.<br>Other: Vegetation prevented detailed inspection.                                                                                      | No action required.                      |                    | Moderate | High                    |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            | n/a                                      | 3                  | Good     | 20-40                   |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            |                                          |                    | Fair     | C +                     |                       |
| T6        | Early-Mature<br>Elder<br><i>Sambucus nigra</i>                   | 6          | 3           | 23               | 2 | 2   |                         | Position: Situated on third party land.<br>Form: Multi-stemmed at ground level with a poorly formed crown.<br>History: No evidence of significant pruning.<br>Defects: No significant defects observed.<br>Other: Limited inspection, dimensions estimated for 3 x stems (15cm, 15cm and 8cm).             | No action required.                      |                    | Moderate | Moderate                |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            | n/a                                      | 3                  | Good     | 40+                     |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            |                                          |                    | Fair     | C                       |                       |
| T7        | Mature<br>Black Locust<br><i>Robinia pseudoacacia</i>            | 14         | 2.5         | 71               | 5 | 5   |                         | Position: Situated on third party land.<br>Form: Twin-stemmed at 1m with a balanced crown.<br>History: No evidence of significant pruning.<br>Defects: Ivy clad.<br>Other: Limited inspection, dimensions estimated for 2 stems at 50cm.                                                                   | No action required.                      |                    | Moderate | High                    |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            | n/a                                      | 3                  | Good     | 40+                     |                       |
|           |                                                                  |            |             |                  |   |     |                         |                                                                                                                                                                                                                                                                                                            |                                          |                    | Fair     | B +                     |                       |

Photographs



Statutory Protection

We were informed by Sharon Bickerstaff of Gravesham Borough Council on the 21<sup>st</sup> August 2023 that:

- The site is within the Darnley Road Conservation Area.
- There are no tree preservation orders affecting trees within the site.
- There are no tree preservation orders immediately adjacent to the site.





**CROWN**  
Tree Consultancy  
08000 14 13 30

|         |                                                                                |
|---------|--------------------------------------------------------------------------------|
| Author: | Emma Hoyle<br>FDSc (Arboriculture), ED (Forestry & Arboriculture), M. Arbor. A |
| Client: | Matthew Lenton-Magor                                                           |

### Notices

Suitable weather-proof notices are to be displayed to identify tree protection zones. They must state the purpose of the fencing and that it will not be moved, or traversed, other than by authorised personnel.

In this zone it is proposed to excavate for the basement extension. The methodology of installation will be confirmed with the engineers and agreed with the local authority prior to commencement. The specific method adopted will vary between contractors; However, the following restrictions apply and must be adhered to:

- No excavation or ground disturbance will occur beyond the basement footprint.
- Any excavator or piling rig shall be marshalled to ensure no contact is made with any tree canopy.
- If piling mats are required, they shall be installed entirely above ground. If it requires additional stabilisation, using screw piles for example, trial excavation shall be undertaken in the presence of the project architect to determine where such piles may be located to avoid all significant roots (i.e. roots over 25mm in diameter).

|       |                         |                                                                                                                                                                                                                   |
|-------|-------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 6th.  | Construction Phase      | Demolish existing structures and remove existing surfaces where applicable.                                                                                                                                       |
| 7th.  |                         | Install new buildings, hard surfaces and services taking into account restricted activities as specified in this Arboricultural Method Statement.                                                                 |
| 8th.  |                         | Site meeting with project arboret. Landscaping restrictions to be agreed. Condition of retained trees to be assessed and mitigation agreed. Ground conditions to be assessed and ground remediation to be agreed. |
| 9th.  | Post-Construction Phase | Remove protective barriers (fencing and ground protection measures as applicable).                                                                                                                                |
| 10th. |                         | Undertake restricted landscaping operations within Root Protection Areas, including (where applicable) boundary treatments, pedestrian surfaces and any proposed tree planting.                                   |

| Tree Reference                    | Action Required                                | Notes                                                                                                               |
|-----------------------------------|------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|
| T5<br>young Holly & a Cotoneaster | Remove                                         | Stumps of trees within the RPAs of retained trees shall be removed with a stump grinder NOT a mechanical excavator. |
| Y4<br>new Ash, Bay Laurel & T5    | Trim foliage back to the edge of the footpath. | Only light trimming to be undertaken to increase clearance for access.                                              |
| T5                                | Crown trim and reshape canopy.                 | Tree pruning works to be undertaken in accordance with BS 3998.                                                     |

Trees to be removed are indicated by a thin, dashed line.

is to be mixed at considerable distances from trees and water run-off cannot enter Root Protection Areas, then no further special measures are required. Otherwise, provision will be made to ensure that the mixing area is contained so that no water run-off enters the Root Protection Area of any trees (see diagram for example). Mixers and barrows will be cleaned within this area.

## Fence Posts or Decking Posts


If permanent fencing or decking is to be installed within Post Protection Areas, the following restrictions will apply:

- All post holes will be excavated by hand and kept as narrow as possible (maximum diameter 300mm).
- Exploratory post holes will be dug before commencing to post / panel positions. If any roots in excess of 25mm are encountered they are to remain intact and the post hole will be relocated to a new position. The fencing system will be installed with flexibility (i.e. where fixed panel widths are used, all post holes must be excavated before commencing to the final location).
- Any roots in excess of 10mm which are severed will be neatly pruned back with secateurs. This will help to encourage regrowth and reduce the likelihood of infection.

Walls will be avoided over Post Protection Areas, unless their foundations are spanned over roots using a beam system.

# Tree Protection Plan

Existing Layout (Black)  
Proposed Basement Layout (Blue)  
Proposed Ground Floor Layout (Pink)



| Position           | Name                      | Contact Phone & email                                    | Roles                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|--------------------|---------------------------|----------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Project Manager    | Insert Details            | Insert Details                                           | <p>Liaising with site manager &amp; project arborist regarding any potential issues relating to trees (including pre-start clarification of the Arboricultural Method Statement).</p> <p>Scheduling of meetings, excavations and inspections (including project arborist and local authority tree officer where applicable).</p> <p>Overseeing this monitoring schedule.</p> <p>Instructing the project arborist and arranging access.</p> <p>Liaising with local authority regarding discharge of planning conditions and variances to the Arboricultural Method Statement.</p> <p>Reporting to the local authority following site inspections and any variation or incidents.</p> |
| Site Manager       | Insert Details            | Insert Details                                           | <p>Day to day monitoring of tree protection measures.</p> <p>Induction of all contractors.</p> <p>Reporting to the Project Manager and the Appointed Arborist of any incidents or potential variances to the agreed tree protection measures.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| Project Arborist   | Crown Tree Consultancy    | 08000 14 13 30<br>0203 797 7449<br>info@crowntrees.co.uk | <p>Liaising with LPA Tree Officer over technical arboricultural matters.</p> <p>Upon instruction the arborist shall inspect the tree protection barriers including ground protection measures and produce a short report for the project manager to submit.</p> <p>Upon instruction the arborist shall attend any specified site visits and inspections and produce a short report for the project manager to submit.</p>                                                                                                                                                                                                                                                           |
| Local Authority    | Gravesham Borough Council | Insert Details                                           | <p>Approval of the Arboricultural Method Statement and site monitoring reports.</p> <p>Liaising with the appointed arborist on all technical arboricultural matters.</p> <p>Liaising with the Project Manager to agree suitability of tree protection measures and any variations.</p> <p>Enforcement.</p> <p>Discharge of planning conditions relating to trees.</p>                                                                                                                                                                                                                                                                                                               |
| Additional Contact | Insert Details            | Insert Details                                           | Insert Details                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |

| Reference<br>ID | Age & Species             | Height (m) | Crown (m)   |               | Crown Spread (m) |     |     | Scaled Tree Diagram (m)                                                               | Notes                                                | Recommendations<br><small>(dependent on site assessment and management proposals)</small>                                                                                                                                                                               |                           | Vigour   | Anxiety Value           |                       |                    |
|-----------------|---------------------------|------------|-------------|---------------|------------------|-----|-----|---------------------------------------------------------------------------------------|------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|----------|-------------------------|-----------------------|--------------------|
|                 |                           |            | Crown H (m) | Diameter (cm) | W                | S   | E   |                                                                                       |                                                      | Priority                                                                                                                                                                                                                                                                | Inspect<br>Interval (yrs) |          | Physiological Condition | Life Expectancy (yrs) | Retention Category |
|                 |                           |            |             |               |                  |     |     |                                                                                       |                                                      |                                                                                                                                                                                                                                                                         |                           |          |                         |                       |                    |
| T1              | Semi-Mature               |            |             |               |                  |     |     |                                                                                       |                                                      |                                                                                                                                                                                                                                                                         | Moderate                  | Low      |                         |                       |                    |
|                 | Lawn Cypress              | 6-5        | 2           | 17            | 3                | 3   | 3   |  | Position:<br>Form:<br>History:<br>Defects:           | Situated within the rear garden.<br>Single stemmed and vertical with a narrow, upright habit.<br>No evidence of significant pruning.<br><b>No significant defects observed.</b>                                                                                         | No action required.       | Good     | 40+                     |                       |                    |
|                 | Chamaecyparis lawsoniana. |            |             |               |                  |     |     |                                                                                       | n/a                                                  | 3                                                                                                                                                                                                                                                                       | Good                      |          | C                       |                       |                    |
| T2              | Semi-Mature               |            |             |               |                  |     |     |                                                                                       |                                                      |                                                                                                                                                                                                                                                                         | Moderate                  | Low      |                         |                       |                    |
|                 | Californian Lilac         | 5          | 2           | 14            | 2                | 2.5 | 2   |  | Position:<br>Form:<br>History:<br>Defects:           | Situated within the rear garden.<br>Tree-stemmed at 1m with a slightly unbalanced crown.<br>No evidence of significant pruning.<br><b>Significant bark wound to stem (acceptable condition at present).</b><br>Recorded stem diameter is equivalent to 3 stems at 10cm. | No action required.       | Good     | 20-40                   |                       |                    |
|                 | Ceanothus sp.             |            |             |               |                  |     |     |                                                                                       | n/a                                                  | 3                                                                                                                                                                                                                                                                       | Good                      |          | C                       |                       |                    |
| T4              | Young                     |            |             |               |                  |     |     |                                                                                       |                                                      |                                                                                                                                                                                                                                                                         | Moderate                  | Low      |                         |                       |                    |
|                 | Elder                     | 3-5        | 1.5         | 10            | 1                | 1.5 | 1   |  | Form:<br>History:<br>Defects:                        | Two-stemmed at ground level with a slightly unbalanced crown.<br>No evidence of significant pruning.<br><b>No significant defects observed.</b>                                                                                                                         | No action required.       | Good     | 40+                     |                       |                    |
|                 | Sambucus nigra.           |            |             |               |                  |     |     |                                                                                       | n/a                                                  | 3                                                                                                                                                                                                                                                                       | Good                      |          | C                       |                       |                    |
| T5              | Early-Mature              |            |             |               |                  |     |     |                                                                                       |                                                      |                                                                                                                                                                                                                                                                         | Moderate                  | High     |                         |                       |                    |
|                 | Cherry                    | 6-5        | 2.5         | 38            | 4                | 4.5 | 5.5 |  | Position:<br>Form:<br>History:<br>Defects:<br>Other: | Situated within the front garden.<br>Multi-stemmed at 3m with a balanced crown.<br>Reduced.<br><b>No significant defects observed.</b><br>Vegetation prevented detailed inspection.                                                                                     | No action required.       | Good     | 20-40                   |                       |                    |
|                 | Prunus sp.                |            |             |               |                  |     |     |                                                                                       | n/a                                                  | 3                                                                                                                                                                                                                                                                       | Fair                      |          | C +                     |                       |                    |
| T6              | Early-Mature              |            |             |               |                  |     |     |                                                                                       |                                                      |                                                                                                                                                                                                                                                                         | Moderate                  | Moderate |                         |                       |                    |
|                 | Elder                     | 6          | 3           | 33            | 2                | 2   | 2   |  | Position:<br>Form:<br>History:<br>Defects:<br>Other: | Situated on third party land.<br>Multi-stemmed at ground level with a poorly formed crown.<br>Evidence of significant pruning.<br><b>No significant defects observed.</b><br>Limited inspection, dimensions estimated for 3 x stems (50cm, 50cm and 8cm).               | No action required.       | Good     | 40+                     |                       |                    |
|                 | Sambucus nigra.           |            |             |               |                  |     |     |                                                                                       | n/a                                                  | 3                                                                                                                                                                                                                                                                       | Fair                      |          | C                       |                       |                    |
| T7              | Mature                    |            |             |               |                  |     |     |                                                                                       |                                                      |                                                                                                                                                                                                                                                                         | Moderate                  | High     |                         |                       |                    |
|                 | Black Locust              | 14         | 2.5         | 71            | 5                | 5   | 5   |  | Position:<br>Form:<br>History:<br>Defects:<br>Other: | Situated on third party land.<br>Tree-stemmed at 3m with a balanced crown.<br>No evidence of significant pruning.<br><b>Hybridised.</b><br>Limited inspection, dimensions estimated for 2 stems at 50cm.                                                                | No action required.       | Good     | 40+                     |                       |                    |
|                 | Rubia pseudocaccid.       |            |             |               |                  |     |     |                                                                                       | n/a                                                  | 3                                                                                                                                                                                                                                                                       | Fair                      |          | B +                     |                       |                    |

| Inspection                                                                                                                                                                                                                     | Site Attendees                                                                                    | Comments                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Pre-Start Desk-top</b><br>To occur prior to any works taking place on the site.                                                                                                                                             | N/A.                                                                                              | Project Manager and Site Manager to study this Method Statement & contact the Project Arborist to clarify all protection measures.                                                                                                                                                                                                                                                                                                                   |
| <b>Pre-Start Meeting</b><br>After all work is completed & 3 tree protection barriers / ground protection measures installed and prior to any other activity, i.e. demolition & soil stripping.                                 | Site Manager, Site Arborist, Project Arborist, relevant contractors.<br><br>Tree Officer invited. | Tree protection fencing locations & specification checked.<br>Ground protection measures checked.<br>Contractors to be inducted to all relevant aspects of the Arboricultural Method Statement. Responsibilities checked and acknowledged.<br>Adherence to the Arboricultural Method Statement to be discussed and agreed.<br>Report on findings to be provided by the arborist and sent to the local authority tree officer by the project manager. |
| <b>Monthly Inspection and Reporting</b><br>To occur once per calendar month throughout the entirety of the project until the local authority agree that tree protection measures may be removed.                               | Site Manager and Project Arborist.                                                                | Tree protection fencing locations & specification checked.<br>Ground protection measures checked.<br>Past month, present and future month – activities and adherence to Arboricultural Method Statement discussed and checked.<br>Report on findings to be provided by the Project Arborist and sent to the local authority by the project manager.                                                                                                  |
| <b>Any other ground disturbance in Restricted Zones &amp; Construction Exclusion Zones</b><br>Including demolition, soil stripping, removal of hard surfaces, excavation for new surfacing, foundations, service trenches etc. | Site Manager, Project Arborist.                                                                   | Two week's notice to be given prior to commencement.<br>Excavation to be as specified in this Method Statement.<br>Excavations to be recorded and photographed.<br>Mitigation measures to be employed specified by the project arborist.                                                                                                                                                                                                             |
| <b>Post-Construction Meeting</b><br>Final external construction activity but prior to removal of fencing & landscaping operations.                                                                                             | Site Manager, Project Arborist.<br><br>Tree Officer invited.                                      | Retained trees inspected. Ground conditions assessed and mitigation measures agreed where appropriate. Further landscaping operations and restrictions to be agreed.                                                                                                                                                                                                                                                                                 |