PLANTING SCHEDULE

CLASS	QTY	SPECIES	SIZE & SPECIFICATION	ROOT	DENSITY / NOTES
Trees	3	Acer campestre	Selected Standard,10-12cm girth, 2x, 250-300cm height, min. 175cm clearstem	RB	All multistem trees & trees 18-20cm girth+ to be secured with underground guys. All 10-12cm girth trees to be secured with low double stakes and crossbar. All trees fitted with RootRain irrigation. Tree sundry items available from www.greenblue.com
	2	Alnus glutinosa	Selected Standard,10-12cm girth, 2x, 250-300cm height, min. 175cm clearstem	RB	
	5	Betula pubescens	Selected Standard,10-12cm girth, 2x, 250-300cm height, min. 175cm clearstem	RB	
	3	Crataegus monogyna	Selected Standard,10-12cm girth, 2x, 250-300cm height, min. 175cm clearstem	RB	
	2	Malus 'Adirondack'	Multistem, min. 3 stems, 175-200cm ht	RB	
	1	Quercus robur	Extra heavy standard 18-20cm girth, 3x, 400-450cm height, min 200cm clearstem	RB	
	4	Sorbus aucuparia	Selected Standard,10-12cm girth, 2x, 250-300cm height, min. 175cm clearstem	RB	
Mixed Native Hedgerow	41	Carpinus betulus	60-80cm ht, Transplant 1+1, bushy	BR	Double staggered row, fitted with spiral guards if rabbits present
	28	Cornus sanguinea	60-80cm ht, Transplant 1+1, bushy	BR	
	43	Corylus avellana	60-80cm ht, Transplant 1+1, bushy	BR	
	69	Crataegus monogyna	60-80cm ht, Transplant 1+1, bushy	BR	
	13	Ilex aquafolium	Leader with laterals	2L	
	28	Ligustrum vulgare	60-80cm ht, Transplant 1+1, bushy	BR	
	15	Rosa canina	60-80cm ht, Transplant 1+1, bushy	BR	
	40	Viburnum oplulus	60-80cm ht, Transplant 1+1, bushy	BR	
Grasses & Ferns	12	Deschampsia cespitosa 'Goldtau'	Full pot, fully rooted, healthy crown	3L	5 per m2
	6	Dryopteris filix-mas	Full pot, fully rooted, healthy crown	3L	2 per m2
	7	Luzula nivea	Full pot, fully rooted, healthy crown	3L	5 per m2
	2	Stipa gigantea	Full pot, fully rooted, healthy crown	5L	dot plant
Specimen Shrubs	5	Hebe rakiensis	30-40cm ht, bushy	5L	as shown
	2	Sarcococca confusa	40-60cm ht, bushy	5L	
Shrubs & Perennials	12	Achillea 'Moonshine'	Full pot, fully rooted, healthy crown	3L	5 per m2
	7	Ajuga reptans 'Caitlins Giant'	Full pot, fully rooted, healthy crown	2L	5 per m2
	15	Alchemilla mollis	Full pot, fully rooted, healthy crown	2L	5 per m2
	6	Anemone x hybrida 'September Charm'	Full pot, fully rooted, healthy crown	3L	dot plants
	12	Bistorta amplexicaulis 'Blackfield'	Full pot, fully rooted, healthy crown	2L	5 per m2
	12	Cenolophium denudatum	Full pot, fully rooted, healthy crown	2L	dot plants
	18	Digitalis purpurea	Full pot, fully rooted, healthy crown	2L	dot plants
	3	Digitalis purpurea f. alba	Full pot, fully rooted, healthy crown	2L	dot plants
	5	Epimedium x versicolor 'Sulphureum'	Full pot, fully rooted, healthy crown	2L	2 per m2
	6	Gaura lindheimeri 'Whirling Butterflies'	Full pot, fully rooted, healthy crown	3L	5 per m2
	6	Geranium 'Rozanne'	Full pot, fully rooted, healthy crown	2L	5 per m2
	6	Helleborus foetidus	Full pot, fully rooted, healthy crown	2L	5 per m2
	12	Lavandula angustifolia 'Munstead'	15-20cm dia, bushy, min. 5 breaks	3L	5 per m2
	12	Nepeta 'Walkers Low'	Full pot, fully rooted, healthy crown	2L	5 per m2
	6	Perovskia atriplicifolia 'Blue Spire'	40-60cm ht, bushy, min. 4 breaks	5L	dot plants
	4	Verbena bonariensis	Full pot, fully rooted, healthy crown	3L	dot plants
Climbers	2	Clematis tangutica	60-80cm ht, several shoots, caned	3L	as shown, trained on stainless steel wires, 1m in length afixed to fence /wall 50cm from GL, then every 50cm to top of fence / 3m height
	3	Hedera hibernica	60-80cm ht, several shoots, caned	3L	
	2	Humulus lupulus 'Aureus'	60-80cm ht, several shoots, caned	3L	
	1	Hydrangea subsp. petiolaris	60-80cm ht, several shoots, caned	3L	
	1	Lonicera x periclymenum 'Belgica'	60-80cm ht, several shoots, caned	3L	
	1	Lonicera x periclymenum 'Serotina'	60-80cm ht, several shoots, caned	3L	
	1	Passiflora caerulea	60-80cm ht, several shoots, caned	3L	
	2	Pyracantha 'Red Column'	60-80cm ht, several shoots, caned	3L	
	2	Rosa 'The Generous Gardener'	60-80cm ht, several shoots, caned	3L	
General Notes		All new planting to be top-dressed with a 50mm layer of medium grade bark mulch. All shrubs & seed to be of local (UK) provenance. Use of herbicides to be avoided.			

FLOWERING LAWN SEED MIX SCHEDULE

CLASS	SPECIES	COMMON NAME
Wildflower Species 20%	Achillea millefolium	Yarrow
	Anthyllis vulneraria	Kidney Vetch
	Betonica officinalis	Betony
	Centaurea nigra	Common Knapweed
	Galium album	Hedge Bedstraw
	Galium verum	Lady's Bedstraw
	Knautia arvensis	Field Scabious
	Leontodon hispidus	Rough Hawkbit
	Leucanthemum vulgare	Oxeye Daisy
	Medicago lupulina	Black Medick
	Plantago lanceolata	Ribwort Plantain
	Plantago media	Hoary Plantain
	Primula veris	Cowslip
	Prunella vulgaris	Selfheal
	Ranunculus acris	Meadow Buttercup
	Ranunculus bulbosus	Bulbous Buttercup
	Trifolium repens	White Clover
Grasses 80%	Agrostis capillaris	Common Bent
	Cynosurus cristatus	Crested Dogstail
	Festuca rubra	Red Fescue
	Phleu bertolonii	Smaller Cats Tail
	Poa pratensis	Smooth-stalked Meadow grass

POND EDGE SEED MIX SCHEDULE

CLASS	SPECIES	COMMON NAME
Wildflower Species 20%	Angelica sylvestris	Wild Angelica
	Centaurea nigra	Common Knapweed
	Cruciata laevipes	Crosswort
	Dipsacus fullonum	Wild Teasel
	Eupatorium cannabinum	Hemp Agrimony
	Filipendula ulmaria	Meadowsweet
	Galium album	Hedge Bedstraw
	Geum rivale	Water Avens
	Geranium pyrenaicum	Hedgerow Cranesbill
	Iris pseudoacorus	Yellow Iris
	Lathyrus pratensis	Meadow Vetchling
	Lythrum salicaria	Purpe Loosestrife
	Lycopus europaeus	Gypsywort
	Oenanthepimpinelloides	Corky fruited Water dropwort
	Plantago lanceolata	Ribwort Plantain
	Prunella vulgaris	Selfheal
	Ranunculus acris	Meadow Buttercup
	Silene dioca	Red Campion
	Silene flos-cuculi	Ragged Robin
Grasses 80%	Agrostis capillaris	Common Bent
	Anthoxanthum odoratum	Sweet Vernal Grass
	Carex divulsa ssp. divulsa	Grey Sedge
	Cynosurus cristatus	Crested Dogstail
	Deschampsia cespitosa	Tufted hair grass
	Festuca rubra	Red Fescue
	Hordeum secalinum	Meadow Barley
	Poa trivalis	Rough-stalked Meadow grass
	Schedonorus arundinaceus	Tall fescue



KEY

- Existing trees retained & protected in accordance with BS5837:2012
- Existing vegetation pruned in accordance with LA's instructions
- Bee lawn sown with Emorsgate EL1 Flowering Lawn mix
- Detention basin / dry pond sown with Emorsgate EP1 Pond edge mix
- Mixed native hedgerow - see planting schedule for further information
- Mixed shrub & perennial planting - see planting plans for further information
- Climbing shrubs - see planting plans for further information
- Proposed standard tree
- Proposed multistem tree

NOTES

All ecological enhancements are in accordance with Greenlink Ecology Ltd's PEA dated Feb 2023.

Do not scale off this drawing. Work from the indicated dimensions only. All site dimensions to be verified by contractor and any discrepancies reported back to the designer. All dimensions in millimetres unless otherwise noted. Drainage details to be confirmed by structural engineer and subcontractor. Structural stability of all items to be confirmed by contractor. Drawings represent design intent only. All materials, components and workmanship shall comply with the relevant British Standards Code of Practice & manufacturers written instructions.

To be read in conjunction with Landscape & Ecological Management Plan.

Rev.	Description	Drawn	Date
A	Revised red line boundary	CJO	1.05.25

Christina Odell
Chartered Landscape Architect
07818 566522
christinajodell@gmail.com
Chart House, 15, Leyland Road, Pevensey Bay, East Sussex BN24 6HT

Site:	Brimsole Barns, Meopham
Client	Open Architecture
Drawing Ref.	2506-300 rev. A
Drawing Title:	PLANTING PLAN
Stage:	PLANNING
Scale:	1 : 125 @ A1 (DO NOT SCALE)
Date:	11th April 2025