

Method Statement Title		Repointing to front facade	
Project Name/Address			
Crutches gate cottage			
Contractor			
M.Axell Stone Restoration Ltd			
Method Statement complied by			
Name	Mark Axell	Position	Director
Validity			
Start Date	tbc	Completion Date	tbc
Required Information			
1. Scope of Works	- Using hand tools, remove areas of redundant pointing beneath the previous render. Mortar to be raked out to a depth of at least 20mm - In areas where a particular hard mortar is present, a thin line will be cut using an angle grinder. The mortar will then be removed using hand tools to ensure the brick arises are not damaged. - Where needed replacement bricks will be sourced from a reclamation yard and offered in dry to ensure the correct match - Repoint all areas of raked out redundant pointing, a mixture of coarse sand and lime putty will be used to carry out repointing in a flush finish. Pointing samples will be carried out to ensure the new mortar matches the original in colour and texture. Data sheets provided on request. - Hessian sheets will cover the whole facade to allow fully curing of the lime		
2. Hazards	- Airborne dust - Loose rubble - Trips and slips		
3. Means of Access	Through front garden		
4. Work Details	- Site Induction be carried out prior to works commencement - Before any work commences the method statement and risk assessments will be reviewed to check that they are suitable and sufficient for the activities to be carried out and that they have been signed by all the operatives. - Only hand tools to be used - Lime mortar to be used. Data sheets provided on request for all elements		
5. Plant/Equipment Requirements	N/A		
6. Disconnection & Reconnection of services	N/A		

7. Hazardous Substances	COSHH
8. Permits to work	N/A
9. PPE Required	• Hard Hat • Hi-Vis • Ear protection • Safety Boots • Gloves • Eye protection • Masks
10. Supervision	The work will be supervised by on site supervisor
11. Workforce	All work carried out on site will be performed by competent contractors with training certificates available on request.
12. Health & Safety Monitoring	On a Daily basis.
13. Emergency procedures	As per Integral policy set out in the induction