

install Velux Suntuunnel in roof

remove window install lintol and cut down to form opening through external wall fit new 1100 wide x 975 high white upvc window with opening side light and obscure glazing

remove downpipe and waste pipes connect new 50 mm sink & bath waste pipes to existing 110 mm soil vent pipe provide access at all changes in direction of pipe run & at base of soil pipe

remove doors install lintol widen and cut down opening fit 3200 mm wide x 2100 mm white aluminum bi-fold doors with traffic door

boundary fence to no 1 Rembrant Drive

remove window and infill with facing brickwork to match existing 100 mm filled cavity wall & blockwork plasterboard on dabs inner skin

36 degree (approx) profiled concrete tiled roof to match existing

existing building outline shown dotted

114 mm dia black upvc half round guttering downpipe & white soffit & fascia to match existing

76 mm round upvc rainwater downpipe connected to existing downpipe

facing brickwork to match existing 100 mm filled cavity wall & blockwork plasterboard on dabs inner skin

connect 50 mm shower waste pipe to existing 110 mm soil vent pipe provide access at all changes in direction of pipe run

remove window install lintol and cut down to form opening through external wall fit new 1050 wide x 1050 mm high white upvc window with opening toplight

connect 50 mm sink waste pipe to existing 110 mm soil vent pipe provide access at all changes in direction of pipe run

PLANNING APPLICATION

REVISION
ARCHITECT

TA ARCHITECTS
11 JOYDENS WOOD ROAD BEXLEY
KENT DA5 2HS Tel 07905 130591
ta140256@googlemail.com

JOB
PROPOSED DOUBLE & SINGLE
STOREY EXTENSIONS
AT 1 REMBRANT DRIVE
NORTHFLEET KENT DA11 8NG

DRAWING
PROPOSED REAR ELEVATION

SCALE
1:50 AT A3
DATE
NOV 2022

DRAWING NO.
CP/08

0 1 2 3 4 5 metres