## Legend

LC – Lighting Column
LP – Lighting Pole
TP – Telegraph Pole
SP – Sign Post
DP – Downpipe
SVP – Soil Vent Pipe
PO – Post
BO – Bollard
WL – White Line
SC – Stop Cock (Water)
SG – Stop Cock (Gas)
WP – Water Pipe
IC – Inspection Cover
FLP – Floodlight Pole
GEN – Generator
RWL – Washing Line
WB – Water Butt
OP – Outlet Pipe
GU – Gully
OHW – Overhead Wire
DK – Drop Kerb
TS – Tree Stump

### Fences

CB – Closed Boarded
CP – Chestnut Paling
CL – Chain Linked
PWM – Post/Wire Mesh
PVR – Post V/Rail
PR – Post/Rail
OL – Overlap
WL – Woven Lap
PT – Post/Elec Tape

### Levels

FL – Floor Level
TL – Threshold Level
RL – Ridge Level
EL – Eaves Level
ERL – Edge Roof Level
TWL – Top Wall Level




## Notes

1. Coordinates to OSGB36(15) Grid established by GPS Observations using the OS Active Network
2. Levels based on OS(GPS) Datum established by GPS Observations using the OS Active Network
3. Tree Girths plotted to scale with approx heights indicated Species may require expert verification

SURVEY STATIONS

| Name | Easting | Northing | Height |
|---|---|---|---|
| S1 | 569821.671 | 170434.868 | 97.805 |
| S2 | 569805.096 | 170465.640 | 98.755 |
| S3 | 569794.319 | 170487.569 | 98.834 |
| S4 | 569775.122 | 170527.129 | 97.356 |
| S4A | 569785.697 | 170522.012 | 98.090 |
| S4B | 569780.062 | 170557.278 | 95.528 |
| S5 | 569800.736 | 170550.877 | 96.058 |
| S6 | 569777.854 | 170566.062 | 95.284 |
| S7 | 569798.203 | 170600.944 | 95.256 |


DRAWN AND SURVEYED
G.FRENCH MC Inst CES
Land/Engineering Surveyor
ELVENBROOK
WATER LANE
MAIDSTONE
KENT ME14 3LT
(01622) 734466


DATE OF SURVEY 04.03.2022

Title: STARWOOD TOPOGRAPHIC SURVEY

Location: PEAR TREE LANE SHORNE KENT DA12 3JU

Client: MR T.RUSSELL

Scale: 1:200 | DRG No. 22/07/A

Gravesham Borough Council