

boundary to no 20 Nashcroft

GARAGE

remove existing manhole instalHepworth upvc manhole
and 110 mm upvc extended soil drain run connected to
existing drain run & connect new 110 mm black upvc
soil downpipe to manhole

TOILET

HALL

KITCHEN

LOUNGE

3400

1250

940 x 1140 mm Velux windows over shown dotted

3550

DINING

new floor to be concrete screed finish and level
with existing

remove doors reliane existing opening
and make good as required

facing brickwork to match existing
100 mm filled cavity wall & blockwork
plasterboard on dabs inner skin

garden wall to no 20 Nashcroft

PLANNING APPLICATION

REVISION DATE

ARCHITECT
TA ARCHITECTS
11 JOYDENS WOOD ROAD BEXLEY
KENT DA5 2HS Tel 07905 130591
ta140256@googlemail.com

JOB
PROPOSED REAR EXTENSION
AT 20 NASHCROFT
NORTHFLEET DA11 8SY

DRAWING
PROPOSED GROUND FLOOR PLAN

SCALE
1:50 AT A3 DATE
JAN 2024

DRAWING NO.
DG/14

