



+ DETAILED RUN REPORT - Page 1

Project Name: C1405 - Convent of Mercy, Hillside Drive, Gravesend DA12 1NY

Designer: Anthony Saunter

Project Date: 13th February 2026

Location: 3 Hillside Dr, Gravesend DA12 1NY, UK

Print Date: 13th February 2026

Project Notes:


+ INPUT DATA:- Run 2: 'Channel Run 02', Option A 'Rev 0'

M5-60: 21mm/hr

Ratio R: 0.44

LENGTH (m)	AREA (m2)	SLOPE (%)	IMPERM. FACTOR	CALC. EQUATION	RETURN PERIOD (years)	CLIMATE CHANGE (%)	STORM DURATION (mins)	RAINFALL INTENSITY (mm/hr)	INFLOW CONTROL (l/s/m)	Point Inflow Interlinked from	Cumulative Point Inflows l/s
3.00	14.72	0.19	1.00	SVF	100	45.00	5 mins	255.09	None	None	0.00

+ CHANNEL LAYOUT



+ RAINFALL DATA

Duration	Intensity (mm/h)
5 mins	175.92
10 mins	136.15
15 mins	109.10
30 mins	70.21
1 hour	42.63
2 hours	24.81
4 hours	14.38
6 hours	10.27
10 hours	6.80
24 hours	3.39
48 hours	1.93





Project Name: C1405 - Convent of Mercy, Hillside Drive, Gravesend DA12 1NY

Designer: Anthony Saunter

Project Date: 13th February 2026

Location: 3 Hillside Dr, Gravesend DA12 1NY, UK

Print Date: 13th February 2026

+ OUTPUTS:- Run 2: 'Channel Run 02', Option A 'Rev 0'

OUTFLOW (l/s)	CAPACITY (%)	MAX* VELOCITY (m/s)	MIN FREEBOARD (m)	EXCAVATION VOLUME (m3)	CONCRETE VOLUME (m3)
1.04	39.22	0.42	0.06	0.57	0.51

MultiDrain MD

1	
System	M100D 0.0
W - Width (mm)	100
H - Invert (mm)	130
Length (m)	3.00

