



External Works & Surface Finishes Legend:

Site Boundary

Existing Levels

Finished Floor Level

New Levels

Slope

Half Batter Kerb

Transition Kerb

Flush Kerb

Edging Kerb

Ramp Landing

Permeable Resin Bound Vehicular Grade

Reinforced Gravel

Timber Decking

Self-Binding Gravel

Threshold Drain

Foul Gully

Retaining Feature

100.00

100.000

1/X

HB

TK

FK

ED

TD

150x150

FG

RF

100.00

100.000

1/X

HB

TK

FK

ED

TD

150x150

FG

RF

SAFETY, HEALTH & ENVIRONMENTAL HAZARD INFORMATION BOX.

The hazards noted below are in addition to the normal hazards and risks faced by a competent contractor when dealing with the types of works detailed on this drawing.

CONSTRUCTION RISKS:

- Striking unknown services
- Deep trenches
- Leptospirosis

MAINTENANCE / CLEANING RISKS:

- Leptospirosis

Notes:

- DO NOT SCALE FROM THIS DRAWING.
- All dimensions are in millimetres Unless Noted Otherwise (u.n.o.)
- Drawing is to be read in conjunction with all relevant architect's drawings. Any inconsistencies should be reported to PRP immediately.
- All levels and dimensions are to be checked on site before any work commences.
- The Health and Safety at Work act is to be complied with at all times. Attention is drawn to the wearing of hard hats, reflectorised clothing, and the use of any other required safety equipment.

External Works:

- Prior to any works being carried out within or immediately adjacent to the public highway, a scheme for the safe control of traffic and pedestrians is to be agreed with the Highway Authority and implemented
- Any utilities shown on this drawing are indicative only. It is the Contractor's responsibility to trace and indicate the precise location and nature of all services.
- The Developer/Contractor shall be responsible for liaison with the Statutory Undertakers and other cable service companies for the provision of all required services, diversion.
- The formation of all surfaces shall be trimmed, rolled and treated with a glyphosate based weedkiller in accordance with the manufacturers instructions prior to laying the sub-base
- All in situ concrete shall be Designated Concrete GEN3 produced in accordance with BS 8500-2006.
- In all instances sulphate resisting cement is to be used.
- Half Battered and Splayed kerbs face shall be 125mm above the channel level.
- The minimum depth of concrete below all kerbs shall be 150mm. Kerbs shall be laid on a 10-40mm bed of Class 1 cement mortar unless laid with the foundation in one operation.
- Adequate bond must be made between foundation and haunch if laid in more than one operation. Preferred method of bonding to be by means of steel U-bars reinforcement, any other method to be approved by PRP.
- Mortar joints between kerbs not to be provided unless specified. Gaps between kerbs to be 1 to 2mm.
- The sub-grade shall be prepared to falls to ensure that construction thickness' remain uniform. Following trimming of the sub-grade it shall be protected against the ingress of water, failure to do so will seriously weaken the sub-grade.
- All soft spots shall be excavated and replaced with compacted sub-base material
- The minimum total carriageway construction thickness shall not be less than 450mm.
- All materials used in top 450mm of carriageway construction shall be non-frost susceptible.

P3	27/09/2022	External Levels amended	NN / DE
P3	20/09/2022	FFL's, External Levels amended	NN / DE
P2	05/09/2022	FFL's, External Levels & Surface finishes amended	NN / AGS
P1	30/06/2022	Issued for comments	NN / AGS
Rev	Date	Description	By / Chk

PRP

consulting engineers & surveyors

Catherine House
Old Harbrough Road
Brixworth, NN6 9BX

Telephone: 01604 889 870
northampton@prp.uk.com
www.prp.uk.com

Leicester
Northampton
London

engineering excellence | creating advantage

Client:
Stem Homes

Architect:
Office S&M

Project:
Goldsmith Mews Houses
Lower Higham Road, Gravesend
DA12 2ND

Title:
External Works & Surface Finishes

Status:
PRELIMINARY

Engineer:	NN	Date:	June 2022
Drawn:	NN	Scales @ A1:	
Checked:	DE	1:100	
Project No:	82455	Drg No:	110
		Rev:	P4

copyright all rights reserved PRP UK Ltd 2010