



PROPOSED VOD CODE:
MJ18D+MJ3+MJ30+MJ24

NOTE: EXISTING COMPOUND, TOWER,
EQUIPMENT CABINETS, FOUNDATIONS
AND ALL ASSOCIATED EQUIPMENT TO BE
REMOVED

NOTE: EXISTING DNO POWER SUPPLY TO
EE, VF/TEF TO BE DISCONNECTED PRIOR
TO REMOVAL OF ANY EQUIPMENT.
DNO POWER SUPPLIES TO BE
RECONNECTED UPON COMPLETION OF
INSTALLATION

DEMISE AREA
(8.0m x 6.0m)

PROPOSED 30m HIGH 1S SWANN ENG
LATTICE TOWER ON PROPOSED PILE
CAPPED CONCRETE FOUNDATION

PROPOSED COMPOUND FORMED FROM
1.8m HIGH CHAINLINK FENCE C/W 3No
STRANDS OF BARBED WIRE ON TOP

PROPOSED 3x3x1m (THK) PILE CAPPED
CONCRETE FOUNDATION

PROPOSED VF 300mm WIDE SURFACE
MOUNTED CABLE TRAY TO REAR OF
CABINETS

PROPOSED 3x1m WIG FOUNDATION FOR
EE EQUIPMENT

PROPOSED EE MK5 LINK AC & FCOA &
HUAWEI 3900A CABINETS FIXED TO
PROPOSED WIG FOUNDATION

PROPOSED VF/TEF 450mm WIDE O/H
CABLE LADDER C/W 6No SUPPORT POLES

PROPOSED VF 1No GPS MODULE FIXED
TO TOP OF CABLE MANAGEMENT
SUPPORT POLE

PROPOSED VF CSC CABINET AND SPACE
FOR 2No ERS RACKS FOR FUTURE USE
FIXED TO PROPOSED WIG CONCRETE
FOUNDATION

PROPOSED 5.25x1m WIG FOUNDATION

PROPOSED TEF ELTEK PERCY PSU AND
2No NOKIA 42U FLAT PACK RACKS FIXED
TO PROPOSED WIG CONCRETE
FOUNDATION

PROPOSED 1.0m WIDE SINGLE ACCESS
GATE TO VF/TEF CABINETS

PROPOSED VF/TEF ELECTRICAL METER
CABINET IN COMPOUND FENCE LINE ON
PROPOSED WIG FOUNDATION

PROPOSED TEF 450mm WIDE SURFACE
MOUNTED CABLE TRAY TO REAR OF
CABINETS

PROPOSED TEF 1No GPS MODULE FIXED
TO TOP OF CABLE MANAGEMENT
SUPPORT POLE

GRASSED
AREA

GRASSED
AREA

PROPOSED 2No 3.0m WIDE DOUBLE
GATES TO FRONT OF EE CABINETS TO
ALLOW ACCESS TO CABINETS

PROPOSED SITE PLAN - GROUND LEVEL



ALL DIMENSIONS ARE IN mm UNLESS NOTED OTHERWISE				
N.G.R	E 562040	N 173520		
NOMINATION REFERENCE: N/A				
CONCESSION/FIXIT REQUIRED?		☒	NO	
REASON FOR CONCESSION/FIXIT:				
-				
ICNIRP DETAILS				
IN ACCORDANCE WITH OPERATOR SPECIFIC ICNIRP GUIDELINES				
SITE DESIGN CATEGORY		PUBLIC ACCESS		
ICNIRP CONTROL MEASURE (IF REQUIRED):				
NO CONTROL MEASURES REQUIRED				
DEPENDENCIES FOR DETAILED DESIGN/BUILD				
ASBESTOS SURVEY	☒	NO		
CHERRY PICKER SURVEY	☒	NO		
COMMS SERVICE ALTERATION	☒	NO		
GDC/STRUCTURAL CALCULATIONS	YES	☒		
GEOTECH AND/OR TRIAL DIG	YES	☒		
ICNIRP CONTROL MEASURES	☒	NO		
INTRUSIVE SURVEY	☒	NO		
MEWP/SCAFFOLD REQUIREMENTS	☒	NO		
REC SERVICE ALTERATION	YES	☒		
STAT SEARCHES	YES	☒		
GPRS REQUIREMENT	☒	NO		
TENSILE PROOF TESTS	☒	NO		
TOWER CLIMB	☒	NO		
COLOUR CHART				
BLACK	TEXT, EXISTING BUILDINGS, TOWERS, STRUCTURES, TREES, ETC.			
BLUE	PROPOSED INSTALLATION			
F	AMENDED TO SUIT DAF 23/07/24	DP	MC	09.08.2024
E	ERS DETAILS CORRECTED	DP	MC	15.07.2024
D	AMENDED TO SUIT DAF 04/03/24	DP	MC	23.04.2024
C	MINOR AMENDS	DM	DP	15.02.2024
B	MINOR AMENDS	NM	RL	24.07.2023
REV	DESCRIPTION OF REVISION	BY	CH	DATE
DESIGN CONSULTANT		WIG PROJECT NUMBER		
TELENT		CTIL-C-SWS0063-3-UPGRADE		
TEF	CTIL	VF		
067713	13776925	37177_16		
SITE NAME AND ADDRESS				
NORTHFLEET WTW SPRINGFIELD GROVE THAMES WAY GRAVESEND - KENT DA11 8HN				
DRAWING TITLE:				
PROPOSED SITE PLAN - GROUND LEVEL				
PURPOSE OF ISSUE:				
CONSTRUCTION				
DRAWING NUMBER:				
102				
SCALE:		DRAWN:	DATE:	REV:
AS SHOWN @ A3		RN	03.12.2020	F
CHECKED:	DATE:	APPROVED:	DATE:	
DP	03.12.2020	DP	03.12.2020	