

ALAN BAXTER PARTNERSHIP_{LLP}

CONSULTING STRUCTURAL ENGINEERS



Convent of Mercy Phase 3,
Hillside Drive,
Gravesend
DA12 1NY

Flood Risk Assessment and
Drainage Strategy Report

C1477 / November 2024

Document Status and Signatures

Document Status		
Document Reference: B2240-FRA & Drainage Strategy		
Issue Date	Version / Revision Notes	Rev
29/01/2025	First Issue	0

Signed on behalf of ABP	
Originator:	 Anthony Saunter

Contents

1.0	Introduction.....	1
2.0	Proposed Development.....	2
3.0	Existing Site	2
3.1	Site Location and Use	2
3.2	Topography	3
3.3	Hydrology	3
3.4	Geology	3
3.5	Existing Site Drainage.....	3
4.0	Flood Risk	4
4.1	Sources of Flooding	4
4.2	Flooding from Rivers and Seas.....	5
4.3	Flooding from Surface Water	5
4.4	Flooding from Water Infrastructure	6
4.5	Flooding from Ground Water.....	6
4.6	Flooding from Sewers and Drainage	6
4.7	Flooding from Development Drainage	6
4.8	Summary of Flood Risk.....	6
4.9	Flood Risk Conclusion	7
5.0	Surface Water Drainage Strategy	7
6.0	Foul Water Drainage Strategy.....	7
7.0	Maintenance of Drainage Systems	7
8.0	Conclusions.....	8

Appendices

- Appendix A: Architectural Layout
- Appendix B: Topographic Survey
- Appendix C: CCTV Survey & Sewer Records
- Appendix D: Site Investigation
- Appendix E: Outline MicroDrainage Calculations
- Appendix F: Schematic Drainage Design

1.0 Introduction

Alan Baxter Partnership LLP (ABP) have been engaged by the St Joseph's Convent of Mercy to prepare a site-specific Flood Risk Assessment (FRA) and Drainage Strategy for the proposed development works at the St Joseph's Convent of Mercy site, on Hillside Drive, Gravesend DA12 1NY.

ABP has no responsibility to any other parties to whom this report may be circulated, in part or in full, and any such parties who rely on the contents of this report do so solely at their own risk.

All copyright and other intellectual rights in and over this report and its contents shall remain vested in ABP. The Client and any person authorised by them is granted an irrevocable royalty free licence to use and reproduce this report for all purposes relating to the property, but ABP shall not be liable for any use of the report for any purpose other than that for which it was originally prepared.

The flood risk assessment has been prepared in accordance with guidance given in the National Planning Policy Framework (NPPF) and the relevant local Strategic Flood Risk Assessment and supporting documents, plus Environment Agency (EA) standing advice on flood risk plus modelled flood data.

The assessment covers the identification of all sources of flooding, their impact on the development, and their residual risk and mitigation.

A preliminary strategy for surface and foul water drainage has also been included and is subject to further detailed design.

2.0 Proposed Development

The development proposal involves the construction of 4No. large residential properties within the surplus garden area of the convent, within the northeast portion of the overall site.

Each property will have its own driveway providing off road parking facilities, with a new road running along in front of the properties to provide access. A turning head will be provided at the eastern end of the site, adjacent to the boundary.

A copy of the Architectural design is provided in **Appendix A**.

3.0 Existing Site

3.1 Site Location and Use

The proposed development covers an area of approximately 0.35ha. The area of the development is essentially greenfield land, save for a small area of (undrained) tarmac currently utilised for vehicle parking and a memorial structure.

The Convent and the development area (plus a number of existing privately owned dwellings) are accessed from the main highway (B261, Old Road East) via a private road within the ownership of the Convent, known as Hillside Drive. Given this road already has a drainage system associated with it, and there are no amendments proposed to be made to this part of the site, it has essential been discounted from the remainder of this report.

The location of the development area is shown below in **Figure 1**.



Figure 1: Site Location (approximate site boundary shown in Blue, approximate development boundary in Red)

3.2 Topography

The site falls roughly from the south to north, with the high point in the southwest corner at 38.1m A.O.D. with the low point in the northwest corner at around 34.4, A.O.D.

A copy of the topographic survey of the development site is provided within **Appendix B**.

3.3 Hydrology

There are no major water ways / rivers within the vicinity of the development works.

3.4 Geology

The British Geological Survey (BGS) records for this area indicate the site is underlain by Thanet Formation - Sand. See **Figure 2** below.




Figure 2: British Geology Survey Map Extract

The development site is located within a Source Protection zone (Zone II – Outer Protection Zone).

3.5 Existing Site Drainage

Whilst the area of development itself is greenfield (and has no drainage), there is drainage associated with the existing convent building. A CCTV Survey of the existing below ground drainage serving the convent is provided in **Appendix C**, along with a copy of the Public Sewer records.

The survey indicates that foul waste is conveyed by a series of gravity pipes before discharging into the foul Public Sewers within Hillside Drive.

There is relatively little in the way of formal surface water drainage, however what there is runs under gravity into what appear to be traditional soakaways.

The survey also highlights that whilst the drainage for the Convent building itself is in relatively poor condition, the Public Sewer is actually in a good state of repair.

4.0 Flood Risk

The Environment Agency uses Flood Zones to determine the vulnerability of every new development. These Flood Zones refer to the probability of river or sea flooding affecting the proposals, ignoring the presence of defences. An interactive flood zone map is accessible on the Environment Agency website.

With reference to the Environment Agency's Risk of Flooding from Rivers and Sea Map (**Figure 4**) the entirety of the site is located within Flood Zone 1 (Low Probability).




Figure 3: Extract from E.A. Flood Mapping for Planning (approximate site boundary shown in red)

Given the site is located within Flood Zone 1 and covers an area less than 1ha, the NPPF does not require that risk of flooding from all possible sources are investigated. However, for completeness, we have investigated the potential impact of various sources below.

4.1 Sources of Flooding

The NPPF lists the key sources of flooding (see below), which could potentially affect the development site. An assessment of how these forms of flooding may affect the site and details on how they will be managed safely within the development are considered in the following sections.

- Flooding from Rivers and the Sea
- Flood from Surface Water Flows
- Flooding from Water Infrastructure
- Flooding from Sewers and Drainage
- Flooding from Development Drainage

4.2 Flooding from Rivers and Seas

The Environment Agency Flood Risk Map indicates that the entirety of the proposed development site has no risk of flooding from rivers or the sea – see **Figure 4** below:




Figure 4: Extract from E.A. Flood Mapping from Rivers and Seas (approximate site boundary shown in red)

4.3 Flooding from Surface Water

The Environment Agency Flood Risk Map indicates that the proposed development area has a 'Very Low' risk of flooding from rivers or the sea, as indicated on **Figure 5** below:



Figure 5: Extract from E.A. Flood Mapping from Surface Water (approximate site boundary shown in red)

There are areas within the overall sports grounds boundaries which do have a potential 'Low' risk of flooding from this source, however the proposed developments are outside of this location and will not be affected by or have an impact on this risk.

4.4 Flooding from Water Infrastructure

An interactive map is available on the Environment Agency website which indicates the maximum extent of flooding in the event of failure of a large reservoir. This map indicates that the site would not be flooded in the event of such a failure – See **Figure 6**.




Figure 6: Extract from E.A. Flood Mapping from Surface Water (approximate site boundary shown in red)

4.5 Flooding from Ground Water

Groundwater flooding occurs when water originally in aquifers reaches the surface, typically as a result of high ground water levels caused by prolonged rainfall, obstructions to ground water flows, or rebound of previously depressed ground levels.

There are no records of groundwater flooding occurring on the site, and the relatively elevated location of the site (nearly 40m above sea level) leads us to anticipate that there is a low risk of flooding from this source.

4.6 Flooding from Sewers and Drainage

There are no records of historic sewer flood incidents on or within the vicinity of the site.

4.7 Flooding from Development Drainage

As is demonstrated in the Drainage Strategy section of this report (see **Section 4**), the proposals will incorporate a robust drainage strategy, which will be designed to accommodate the most severe of storm events and will ensure any minor flooding which may occur will be retained within the boundary of the development. As such, it is considered that the risk from flooding from this source is very low.

4.8 Summary of Flood Risk

An assessment of key sources of flooding has been carried out and is summarised below:

- | | |
|--------------------------------------|--------------------------|
| • Flooding from Rivers and the Sea | Very Low / No Risk |
| • Flooding from Surface Water Flows | Low Risk / Very Low Risk |
| • Flooding from Water Infrastructure | Very Low Risk |
| • Flooding from Groundwater | Very Low Risk |

- Flooding from Sewers and Drainage Very Low Risk
- Flooding from Development Very Low Risk

4.9 Flood Risk Conclusion

Based on this desktop investigation, it can be concluded that the proposed development is located in an area with essentially no risk of flooding from all possible sources, and that the proposals would have (at worst) a negligible impact on the flood risk of the site and the surrounding areas.

5.0 Surface Water Drainage Strategy

It is proposed to discharge all surface water generated by the development into the ground using soakaways.

Each proposed property will have its own private surface water drainage network. Each system will utilise rainwater pipes and a gravity network (for the building roofs), along with subbase storage within the private driveways. All surface water system each building will discharge to individual soakaways located at the rear of each property.

The new access road and turning head for the development will utilise gullies and a channel drain before discharging to a separate, dedicated soakaway, via catchpit chambers.

Infiltration testing was undertaken on site, the results of which are provided in **Appendix D**. Whilst the rates calculated was towards the lower end of what is considered useable, because of the relatively small size of the development, initial modelling has determined that soakaways are viable.

Preliminary soakaway designs have been modelled and are provided in **Appendix E**, and a schematic drainage design is shown in **Appendix F**.

6.0 Foul Water Drainage Strategy

It is proposed to discharge the foul water from all four properties into the Public Sewer located in front of the existing Convent Buildings. However, the depth of the existing sewer and the topography of the development site means that it will not be possible to connect to the Public Sewer using an entirely gravity system.

Therefore, it is proposed to run all foul waste from the proposed properties to a pumping station. The wastewater will then be conveyed through a rising main up to a new chamber nearby to the Public Sewer which will act as a 'break chamber' to enable the final connection to be made under gravity.

The final connection will be made using a vitrified clay pipe and will be subject to approval by the relevant authorities.

A schematic layout o provided in **Appendix F**.

7.0 Maintenance of Drainage Systems

The following maintenance regimes would be recommended as a minimum for both surface water and (where appropriate) foul drainage, but actions and frequencies should be adjusted to suit the specific requirements of this development. The schedules below are based on the most preferred drainage solution.

Regular inspection and maintenance of drainage systems is essential to ensure effective long-term performance. Maintenance needs of the system should be monitored, and schedules adjusted to suit the specific requirements of the development. In addition, component specific regimes and any manufacturer's specific recommendations should always be followed.

Main Drainage Network Maintenance - Surface & Foul Water

Item	Required Works/Action	Frequency	Responsibility
Guttering, Gullies & Chambers	Clean out guttering, gullies and chambers (grates and sumps), removing debris & sediment.	Annually	Land Owner or Maintenance Contractor
Pipe network	All pipes (including filter pipes) to be cleaned (jetted) and condition assessed.	Annually	Land Owner or Maintenance Contractor
Permeable Paving	Clear debris & weeds from paving, apply weed killer	Annually	Land Owner or Maintenance Contractor

Attenuation Tanks – Surface Water

Item	Required Works/Action	Frequency	Responsibility
Silt removal	Tanks to be cleaned (jetted) and condition assessed.	Annually	Land Owner or Maintenance Contractor

The foul pumping station will be maintained in accordance with the manufacturer's requirements, and sufficient pipe protection or remediation measures for the existing drain routes to be maintained will be implemented.

8.0 Conclusions

The requirements for Flood Risk Assessment are provided in the National Planning Policy Framework and associated Planning Practice Guidance, together with the Environment Agency's Guidance Notes. This policy and associated guidance have been followed in the preparation of this FRA.

The proposed development covers an area of approximately 0.35ha. The vast majority of this is greenfield land with the remaining area consists of a small area of tarmac used for vehicle parking and memorial structure.

Based on this desktop investigation, it can be concluded that the proposed development is located in an area with essentially no risk of flooding from all possible sources, and that the proposals will have no discernible impact on the flood risk associated with the development site, or those areas adjacent to it.

A robust surface water drainage scheme is proposed, incorporating permeable paving, catchpit gullies and chambers, and soakaways. All surface water drainage will run under gravity and be designed to accommodate a 100 year storm, with a 45% allowance for climate change.

In the event of an exceedance event (if the drainage system gets blocked for example), any waterflows will be routed to the external grassed area around the development, replicating the natural flows of the current site.

Foul wastewater from the development will be conveyed under gravity to a pumping station before being conveyed to the Public Sewer via rising main and break chamber.

It is therefore concluded that the proposed development will not increase flood risk off site, and that all occupants / users will be able to be kept safe in the most extreme of events. On that basis it is considered that the development should be considered acceptable in terms of the planning policy requirements.

Appendix A
Architectural Layout



B	11/10/24	KG	Rear driveway extended to serve convent garden to the south
A	8/10/24	KG	Layout revised to enable turning into private driveway
Rev.	Date	By	Notes
Copyright Clay Architecture Ltd All dimensions are to be verified by the contractor before commencing works			
Project CONVENT OF MERCY, GRAVESEND			
Client SISTERS OF MERCY			

clayarchitecture
Great Lines Studios, Marlborough Road, Gillingham, Kent ME7 5HB
T: 01634 573 017
www.clayarchitecture.com
E: design@clayarchitects.com

Title	Scale
SCHEME DESIGN	1:500
PROPOSED BLOCK PLAN	@ A1 size
Drawing No.	Date
5296/PL/102	27/09/2024
Revision	Drawn
B	GEN
Authorised	

Appendix B
Topographic Survey



Appendix C
CCTV Survey & Sewer Records



*Sewer Inspection,
Cleaning and Repair*

Project ref: TV231025

18th October 2023

CCTV Survey Report

**CLIENT: SISTER ANNE CAECILIA O'CONNEL, CONVENT OF
MERCY**

SITE: Convent of Mercy

Hillside Drive

DA12 1NY

www.insewer.co.uk

Tel : 01634 861 768



Project Information

Project Name
TV231025

Project Number

Project Date
18/10/2023

Client

Company: Sister Anne Caecilia O'Connell. Convent of Mercy
Description: c/o Clay Architecture
Contact: Camilla Prizeman
Department: Great Lines Studios
Street: Marlborough Road
Town or City: Gillingham
County: Kent
Post Code: ME7 5HB
Phone: 01634 573 017

Site

Department: Convent of Mercy
Street: Hillside Drive
Town or City: Gravesend
County: Kent
Post Code: DA12 1NY

Contractor

Company: Insewer Surveys
Contact: Liam Sellar
Street: 16a Revenge Road
Town or City: Chatham
County: Kent
Post Code: ME5 8UD
Phone: 01634 861 768
Fax: 01634 201376
Mobile: 07802 660 752



Table of Contents

Project Name	Project Number	Project Date
TV231025		18/10/2023

Project Information	P-1
Scoring Summary	P-2
Section Item 1: 6802-A > 6802 (6802-AX)	1
Section Item 2: 6802 > 6803 (6802X)	3
Section Item 3: SVP 1 > RUN X (SVP 1X)	5
Section Item 4: SP 1 > RUN X (SP 1X)	7
Section Item 5: 6803-A > 6803 (6803-AX)	8
Section Item 6: 6803 > 6804 (6803X)	9
Section Item 7: IC1-A > IC1 (IC1-AX)	11
Section Item 8: IC1-B > IC1 (IC1-BX)	12
Section Item 9: IC1-C > IC1 (IC1-CX)	14
Section Item 10: IC1 > RUN X (IC1X)	15
Section Item 11: IC2-A > IC2 (IC2-AX)	16
Section Item 12: IC2-B > IC2 (IC2-BX)	17
Section Item 13: IC2-C > IC2 (IC2-CX)	19
Section Item 14: IC2 > IC3 (IC2X)	21
Section Item 15: IC2 > RUN Y (IC2Y)	22
Section Item 16: IC3-A > IC3 (IC3-AX)	23
Section Item 17: IC3 > RUN X (IC3X)	25
Section Item 18: IC4-A > IC4 (IC4-AX)	26
Section Item 19: IC4-B > IC4 (IC4-BX)	28
Section Item 20: IC4 > 6801 (IC4X)	30
Section Item 21: 6801 > 6804 (6801X)	32
Section Item 22: IC6 > IC5 (IC6X)	35
Section Item 23: IC5 > RUN X (IC5X)	36
Section Item 24: IC6-A > IC6 (IC6-AX)	38
Section Item 25: IC6-B > IC6 (IC6-BX)	39
Section Item 26: IC6-C > IC6 (IC6-CX)	40
Section Item 27: IC6-D > IC6 (IC6-DX)	41



Table of Contents

Project Name
TV231025

Project Number

Project Date
18/10/2023

SectionItem28: RWP+GY6-A > RWP+GY6 (RWP+GY6-AX)	42
SectionItem29: RWP+GY6 > RUNX (RWP+GY6X)	43
SectionItem30: COMBGY5-A > COMBGY5 (COMBGY5-AX)	45
SectionItem31: COMBGY5 > RUNX (COMBGY5X)	46
SectionItem32: 6804 > 5901 (6804X)	48



Scoring Summary

Project Name
TV231025

Project Number

Project Date
18/10/2023

Structural Defects

- Grade 3: Best practice suggests consideration should be given to repairs in the medium term.
- Grade 4: Best practice suggests consideration should be given to repairs to avoid a potential collapse.
- Grade 5: Best practice suggests that this pipe is at risk of collapse at any time. Urgent consideration should be given to repairs to avoid total failure.

Section	PLR	Grade	Description
1	6802-AX	3	Multiple defects

Service / Operational Condition

- Grade 3: Best practice suggests consideration should be given to maintenance activities in the medium term.
- Grade 4: Best practice suggests consideration should be given to maintenance activity to avoid potential blockages.
- Grade 5: Best practice suggests that this pipe is at a high risk of backing up or causing flooding.

Section	PLR	Grade	Description
1	6802-AX	2	Multiple defects
2	6802X	3	Multiple defects
3	SVP 1X	5	Roots, mass at joint, 25% cross-sectional area loss
6	6803X	3	Roots, mass, 10% cross-sectional area loss
13	IC2-CX	5	Settled deposits, hard or compacted, 90% cross-sectional area loss
16	IC3-AX	3	Attached deposits, encrustation at joint from 03 o'clock to 06 o'clock, 5% cross-sectional area loss
18	IC4-AX	3	Multiple defects
19	IC4-BX	3	Settled deposits, hard or compacted, 5% cross-sectional area loss, finish
20	IC4X	3	Roots, mass at joint, 10% cross-sectional area loss
21	6801X	5	Roots, mass at joint, 30% cross-sectional area loss
29	RWP+GY6X	5	Settled deposits, hard or compacted, 95% cross-sectional area loss
31	COMB GY5X	3	Settled deposits, hard or compacted, 10% cross-sectional area loss, finish
32	6804X	5	Roots, mass at joint, 20% cross-sectional area loss

Abandoned Surveys

Section	PLR	Description
13	IC2-CX	Survey abandoned
29	RWP+GY6X	Survey abandoned
31	COMB GY5X	Survey abandoned
32	6804X	Survey abandoned



Scoring Summary

Project Name
TV231025

Project Number

Project Date
18/10/2023

Information

These scoring summaries are based on the SRM grading from the WRc.



*Sewer Inspection,
Cleaning and Repair*

Site Photos

www.insewer.co.uk

Tel : 01634 861 768





IC1



LOCATION OF IC1



IC2



LOCATION OF IC2



IC3



LOCATION OF IC3



IC4



LOCATION OF IC4



IC5



LOCATION OF IC5



IC6



LOCATION OF IC6



IC7. INTERNAL.
UNABLE TO LIFT - COVER SEIZED



LOCATION OF IC7



6801



LOCATION OF 6801



6802



LOCATION OF 6802



6803



LOCATION OF 6803

6804. UNABLE TO LIFT -
BURIED / COVERED OVER



LOCATION OF 6804



COMBINED GULLY 1.
TRAPPED - NO CCTV



LOCATION OF CPMBINED GULLY 1



COMBINED GULLY 2.
TRAPPED - NO CCTV



LOCATION OF COMBINED GULLY 2



COMBINED GULLY 3.
TRAPPED - NO CCTV



LOCATION OF COMBINED GULLY 3



COMBINED GULLY 4.
TRAPPED - NO CCTV



LOCATION OF COMBINED GULLY 4



COMBINED GULLY 5



LOCATION OF COMBINED GULLY 5



FOUL GULLY 1.
TRAPPED - NO CCTV



LOCATION OF FOUL GULLY 1



FOUL GULLY 2.
TRAPPED - NO CCTV



LOCATION OF FOUL GULLY 2



FOUL GULLY 3.
TRAPPED - NO CCTV



LOCATION OF FOUL GULLY 3



FOUL GULLY 4.
TRAPPED - NO CCTV



LOCATION OF FOUL GULLY 4



FOUL GULLY 5.
TRAPPED - NO CCTV



LOCATION OF FOUL GULLY 5



GULLY 1.
TRAPPED - NO CCTV



LOCATION OF GULLY 1



GULLY 2.
TRAPPED - NO CCTV



LOCATION OF GULLY 2



GULLY 3.
TRAPPED - NO CCTV



LOCATION OF GULLY 3




GULLY 4.
TRAPPED - NO CCTV




LOCATION OF GULLY 4



RWP + GULLY 1.
DEBRIS FILLED



LOCATION OF RWP + GULLY 1



RWP + GULLY 2.
TRAPPED - NO CCTV



LOCATION OF RWP + GULLY 2



RWP + GULLY 3.
TRAPPED - NO CCTV



LOCATION OF RWP + GULLY 3



RWP + GULLY 4.
TRAPPED - NO CCTV



LOCATION OF RWP + GULLY 4



RWP + GULLY 5.
TRAPPED - NO CCTV



LOCATION OF RWP + GULLY 5



RWP + GULLY 6



LOCATION OF RWP + GULLY 6



RWP 1.
INTO GROUND



LOCATION OF RWP 1

RWP 2.
ONTO GROUND



LOCATION OF RWP 2



RWP 3.
ONTO GROUND




LOCATION OF RWP 3




RWP 4.
INTO GROUND



LOCATION OF RWP 4



RWP 5.
INTO GROUND



LOCATION OF RWP 5

SOIL PIPE 1



LOCATION OF SOIL PIPE 1

SVP 1



LOCATION OF SVP 1



SVP 2.
UNABLE TO CCTV



LOCATION OF SVP 2

VENT PIPE 1.
UNABLE TO CCTV



LOCATION OF VENT PIPE 1



MH1.
CHAMBER FILLED IN



LOCATION OF MH1



MH2.
SERVICES



LOCATION OF MH2



MH3.
SERVICES



LOCATION OF MH3



5901



LOCATION OF 5901




*Sewer Inspection,
Cleaning and Repair*

Site Plan

www.insewer.co.uk

Tel : 01634 861 768





clay architecture

FOR PLANNING

ISSUE DATE: 01/09/23

Rev. Date By Notes

Copyright Clay Architecture Ltd

All dimensions are to be verified by the contractor before commencing works

Project
CONVENT OF MERCY, GRAVESEND
PROPOSAL FOR DOWNSIZING
Client
SISTERS OF MERCY



clay architecture

Great Lines Studios, Marlborough Road, Gillingham, Kent ME7 5HB
T: 01634 573 017
www.clayarchitecture.com
E: design@clayarchitects.com

Title: PLANNING EXISTING Scale: 1:100
@ A1 size
LOWER-GROUND FLOOR PLAN Date: 19/07/2023

Drawing No.	Revision	Drawn DA
5285/PL/110	/	Authorised

Disclaimer
Detail shown on this plan is for reference only.
The positions of the pipes and their route and location are believed to be correct.
InSewer Surveys accept no responsibility in the event of inaccuracy.
Before mechanical plan is used the actual position and route of the drainage system should be verified on site.



NOTES

Rev.	Date	By	Notes
------	------	----	-------

Copyright Clay Architecture Ltd
All dimensions are to be verified by the contractor before commencing works

Project
CONVENT OF MERCY, GRAVESEND
PROPOSAL FOR DOWNSIZING
Client
SISTERS OF MERCY

clay architecture

Great Lines Studios, Marlborough Road, Gillingham, Kent ME7 5HB
T: 01634 573 017
www.clayarchitecture.com
E: design@clayarchitects.com

Title	Scale	AS SHOWN
CONCEPT DESIGN	@ A1 size	
LOCATION & BLOCK PLAN	Date	05/06/2023
Drawing No.	Revision	Drawn GEN
5285/PL/100	/	Authorised



*Sewer Inspection,
Cleaning and Repair*

Report

www.insewer.co.uk

Tel : 01634 861 768





Section Inspection - 18/10/2023 - 6802-AX



Item No. 1	Insp. No. 1	Date 18/10/23	Time 9:00	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR 6802-AX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	6802-A
Road:	Convent Of Mercy	Inspected Length:	2.39 m	Upstream Pipe Depth:	
Location:		Total Length:	2.39 m	Downstream Node:	6802
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.900 m
Use:	Foul	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	150 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale:	1:50	Position [m]	Code	Observation	Grade
Depth: 0.90 m					
6802					
		0.00	MH	Start node, manhole, reference: 6802	
		0.00	WL	Water level, 5% of the vertical dimension	
		0.71	FLJ	Fracture, longitudinal at joint at 3 o'clock	3 / 2
		0.71	FLJ	Fracture, longitudinal at joint at 8 o'clock	3 / 2
		0.71	SC	Pipe size changes, new size(s), 100mm high	
		0.93	JN	Junction at 1 o'clock, 100mm dia: from foul gully 1	
		1.52	LL	Line deviates left	
		2.27	LU	Line deviates up	
		2.39	OFF	Finish node, outfall, reference: 6802-A: At svp	



Depth: m

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
2	80.0	33.5	80.0	3.0	2	2.0	0.8	2.0	3.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
1	Upstream	6802-AX	TV231025	



1, 00:00:16, 0.71 m
Fracture, longitudinal at joint at 3 o'clock



2, 00:00:23, 0.71 m
Fracture, longitudinal at joint at 8 o'clock



Section Inspection - 18/10/2023 - 6802X



Item No.	Insp. No.	Date	Time	Client's Job Ref	Weather	Pre Cleaned	PLR
2	1	18/10/23	9:05	TV231025	No Rain Or Snow	No	6802X
Operator		Vehicle		Camera	Preset Length	Legal Status	Alternative ID
InSewer MO		-		Not Specified	Not Specified	-	-

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	6802
Road:	Convent Of Mercy	Inspected Length:	23.75 m	Upstream Pipe Depth:	0.900 m
Location:		Total Length:	23.75 m	Downstream Node:	6803
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined		Pipe Shape:	Circular	
Type of Pipe:			Dia/Height:	150 mm	
Flow Control:	-		Material:	Vitrified clay	
Year Constructed:	Not Specified		Lining Type:	No Lining	
Inspection Purpose:	Routine inspection		Lining Material:	No Lining	
Comments:					
Recommendations: -					

Scale: 1:206	Position [m]	Code	Observation	Grade
Depth: 0.90 m 6802				
	0.00	MH	Start node, manhole, reference: 6802	
	0.00	WL	Water level, 5% of the vertical dimension	
	2.89	DEE	Attached deposits, encrustation from 05 o'clock to 07 o'clock, 5% cross-sectional area loss	3
	3.16	JN	Junction at 2 o'clock, 100mm dia: from svp 1	
	6.04	JN	Junction at 1 o'clock, 100mm dia: from combined gully 1	
	6.04	RM	Roots, mass, 5% cross-sectional area loss	3
	7.84	JN	Junction at 1 o'clock, 100mm dia: from wc	
	15.28	JN	Junction at 2 o'clock, 100mm dia: from soil pipe 1	
	21.32	RFJ	Roots, fine at joint	2
	22.51	DEC	Settled deposits, hard or compacted, 5% cross-sectional area loss	3
	22.68	JN	Junction at 2 o'clock, 100mm dia: Assumed from IC7	
	23.08	RMJ	Roots, mass at joint, 5% cross-sectional area loss	3
	23.75	MHF	Finish node, manhole, reference: 6803	
6803 Depth: m				
DEE - 2.89 RM - 6.04 RFJ - 21.32 DEC - 22.51 RMJ - 23.08				

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	5	4.0	0.5	13.0	3.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
2	Downstream	6802X	TV231025	



1, 00:00:29, 2.89 m
Attached deposits, encrustation from 05 o'clock to 07 o'clock,
5% cross-sectional area loss



2, 00:01:13, 6.04 m
Roots, mass, 5% cross-sectional area loss



3, 00:02:58, 21.32 m
Roots, fine at joint



4, 00:03:27, 22.51 m
Settled deposits, hard or compacted, 5% cross-sectional area
loss



5, 00:03:46, 23.08 m
Roots, mass at joint, 5% cross-sectional area loss



Section Inspection - 18/10/2023 - SVP 1X



Item No. 3	Insp. No. 1	Date 18/10/23	Time 9:20	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR SVP 1X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	SVP 1
Road:	Convent Of Mercy	Inspected Length:	4.35 m	Upstream Pipe Depth:	
Location:		Total Length:	4.35 m	Downstream Node:	RUN X
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Foul	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Polyvinyl chloride		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale: 1:50 Position [m] Code Observation Grade

Depth: m
SVP 1



0.00

OF

Start node, outfall, reference: SVP 1

0.00

WL

Water level, 5% of the vertical dimension

0.78

LD

Line deviates down

1.71

MCVC

Pipe material changes to vitrified clay at this point

2.49

RMJ

Roots, mass at joint, 25% cross-sectional area loss

5

3.21

JN

Junction at 12 o'clock, 100mm dia

3.61

RMJ

Roots, mass at joint, 5% cross-sectional area loss

3

4.03

LR

Line deviates right

4.35

BRF

Finish node, major connection without manhole, reference: RUN X: At saddle connection

RUN X

Depth: m



RMJ - 2.49



RMJ - 3.61

Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	2	10.0	3.2	14.0	5.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
3	Downstream	SVP 1X	TV231025	



1, 00:00:54, 2.49 m
Roots, mass at joint, 25% cross-sectional area loss



2, 00:01:28, 3.61 m
Roots, mass at joint, 5% cross-sectional area loss



Section Inspection - 18/10/2023 - SP 1X



Item No. 4	Insp. No. 1	Date 18/10/23	Time 9:23	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR SP 1X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	SP 1
Road:	Convent Of Mercy	Inspected Length:	4.48 m	Upstream Pipe Depth:	
Location:		Total Length:	4.48 m	Downstream Node:	RUN X
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Foul	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Polyvinyl chloride		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		
Comments:					
Recommendations: -					

Scale:1:50

Position [m]


Code

Observation

Grade

Depth: m

SP 1



Depth: m

0.00

OF

Start node, outfall, reference: SP 1

0.00

WL

Water level, 5% of the vertical dimension

0.30

LD

Line deviates down

1.08

LL

Line deviates left

2.98

LD

Line deviates down

3.70

LL

Line deviates left

3.89

LR

Line deviates right

4.10

MCVC

Pipe material changes to vitrified clay at this point

4.48

BRF

Finish node, major connection without manhole, reference: RUN X: At saddle connection

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
1	1.0	0.2	1.0	1.0	1	2.0	0.4	2.0	3.0



Section Inspection - 18/10/2023 - 6803-AX



Item No. 5	Insp. No. 1	Date 18/10/23	Time 9:38	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR 6803-AX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	6803-A
Road:	Convent Of Mercy	Inspected Length:	10.67 m	Upstream Pipe Depth:	
Location:		Total Length:	10.67 m	Downstream Node:	6803
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Foul	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Polyvinyl chloride		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale: 1:93 Position [m] Code Observation Grade

Depth: m
6803



0.00

MH

Start node, manhole, reference: 6803

0.73

LL

Line deviates left

10.40

LU

Line deviates up

10.67

OFF

Finish node, outfall, reference: 6803-A: At svp

6803-A
Depth: m



Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 18/10/2023 - 6803X



Item No. 6	Insp. No. 1	Date 18/10/23	Time 9:42	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR 6803X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	6803
Road:	Convent Of Mercy	Inspected Length:	23.96 m	Upstream Pipe Depth:	
Location:		Total Length:	23.96 m	Downstream Node:	6804
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	150 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		
Comments:					
Recommendations: -					

Scale: 1:208	Position [m]	Code	Observation	Grade
Depth: m 6803				
	0.00	MH	Start node, manhole, reference: 6803	
	0.00	WL	Water level, 5% of the vertical dimension	
	0.50	RFJ	Roots, fine at joint	2
	10.51	RFJ	Roots, fine at joint	2
	23.50	RM	Roots, mass, 10% cross-sectional area loss	3
	23.96	MHF	Finish node, manhole, reference: 6804: Unable to lift - buried / covered over	
6804 Depth: m				
				RFJ - 0.50
				RFJ - 10.51
				RM - 23.50
				MHF - 23.96

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	3	4.0	0.3	6.0	3.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
6	Downstream	6803X	TV231025	




1, 00:00:05, 0.50 m
Roots, fine at joint



2, 00:01:00, 10.51 m
Roots, fine at joint



3, 00:02:20, 23.50 m
Roots, mass, 10% cross-sectional area loss



4, 00:02:37, 23.96 m
Finish node, manhole, reference: 6804, Unable to lift - buried / covered over



Section Inspection - 18/10/2023 - IC1-AX



Item No. 7	Insp. No. 1	Date 18/10/23	Time 10:12	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC1-AX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC1-A
Road:	Convent Of Mercy	Inspected Length:	1.70 m	Upstream Pipe Depth:	
Location:		Total Length:	1.70 m	Downstream Node:	IC1
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.530 m
Use:	Foul	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:	
Recommendations:	-

Scale:	1:50	Position [m]	Code	Observation	Grade
		0.00	MH	Start node, manhole, reference: IC1	
		0.00	WL	Water level, 5% of the vertical dimension	
		0.92	JN	Junction at 9 o'clock, 100mm dia: from vent pipe 1	
		1.49	LU	Line deviates up	
		1.70	GYF	Finish node, gully, reference: IC1-A: At foul gully	

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0

Section Inspection - 18/10/2023 - IC1-BX



Item No. 8	Insp. No. 1	Date 18/10/23	Time 10:13	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC1-BX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC1-B
Road:	Convent Of Mercy	Inspected Length:	1.91 m	Upstream Pipe Depth:	
Location:		Total Length:	1.91 m	Downstream Node:	IC1
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.530 m
Use:	Foul		Pipe Shape:	Circular	
Type of Pipe:			Dia/Height:	100 mm	
Flow Control:	-		Material:	Vitrified clay	
Year Constructed:	Not Specified		Lining Type:	No Lining	
Inspection Purpose:	Routine inspection		Lining Material:	No Lining	
Comments:					
Recommendations:	-				

Scale: 1:50 Position [m]

Depth: 0.53 m

IC1

0.00

0.00

1.09

1.53

1.91

IC1-B

Depth: m


Code	Observation	Grade
MH	Start node, manhole, reference: IC1	
WL	Water level, 5% of the vertical dimension	
CC	Crack, circumferential from 04 o'clock to 09 o'clock	2 / 2
LU	Line deviates up	
OFF	Finish node, outfall, reference: IC1-B: At wc	

CC - 1.09

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
1	10.0	5.2	10.0	2.0	1	1.0	0.5	1.0	2.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
8	Upstream	IC1-BX	TV231025	



1, 00:00:17, 1.09 m
Crack, circumferential from 04 o'clock to 09 o'clock



Section Inspection - 18/10/2023 - IC1-CX




Item No. 9	Insp. No. 1	Date 18/10/23	Time 10:14	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC1-CX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC1-C
Road:	Convent Of Mercy	Inspected Length:	2.52 m	Upstream Pipe Depth:	
Location:		Total Length:	2.52 m	Downstream Node:	IC1
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.530 m
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Polyvinyl chloride		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -



Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0




Section Inspection - 18/10/2023 - IC1X



Item No. 10	Insp. No. 1	Date 18/10/23	Time 10:16	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC1X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	IC1
Road:	Convent Of Mercy	Inspected Length:	9.20 m	Upstream Pipe Depth:	0.530 m
Location:		Total Length:	9.20 m	Downstream Node:	RUN X
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		
Comments:					
Recommendations: -					



Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 18/10/2023 - IC2-AX



Item No. 11	Insp. No. 1	Date 18/10/23	Time 10:38	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC2-AX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC2-A
Road:	Convent Of Mercy	Inspected Length:	0.01 m	Upstream Pipe Depth:	
Location:		Total Length:	0.01 m	Downstream Node:	IC2
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.600 m
Use:	Surface water	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	75 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale:	1:50	Position [m]	Code	Observation	Grade
Depth: 0.60 m					
IC2					
		0.00	MH	Start node, manhole, reference: IC2	
		0.00	WL	Water level, 5% of the vertical dimension	
		0.00	LD	Line deviates down	
		0.01	GYF	Finish node, gully, reference: IC2-A: At gully	
Depth: m					

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 18/10/2023 - IC2-BX



Item No. 12	Insp. No. 1	Date 18/10/23	Time 10:39	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC2-BX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -


Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC2-B
Road:	Convent Of Mercy	Inspected Length:	2.23 m	Upstream Pipe Depth:	
Location:		Total Length:	2.23 m	Downstream Node:	IC2
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.600 m
Use:	Foul	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale: 1:50 Position [m] Code Observation Grade

Depth: 0.60 m



0.00

MH

Start node, manhole, reference: IC2

0.00

WL

Water level, 5% of the vertical dimension

0.30

CC

Crack, circumferential from 10 o'clock to 02 o'clock

2 / 2

1.66

CCJ

Crack, circumferential at joint from 02 o'clock to 07 o'clock

2 / 2

1.87

LU


Line deviates up

2.23

OFF

Finish node, outfall, reference: IC2-B: At wc

IC2-B
Depth: m



CC - 0.30



CCJ - 1.66

Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations


STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
2	10.0	9.0	20.0	2.0	2	1.0	0.9	2.0	2.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
12	Upstream	IC2-BX	TV231025	



1, 00:00:08, 0.30 m
Crack, circumferential from 10 o'clock to 02 o'clock



2, 00:00:38, 1.66 m
Crack, circumferential at joint from 02 o'clock to 07 o'clock



Section Inspection - 18/10/2023 - IC2-CX



Item No. 13	Insp. No. 1	Date 18/10/23	Time 10:42	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC2-CX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC2-C
Road:	Convent Of Mercy	Inspected Length:	7.14 m	Upstream Pipe Depth:	
Location:		Total Length:	7.14 m	Downstream Node:	IC2
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.600 m
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		
Comments:					
Recommendations: -					

Scale:	1:62	Position [m]	Code	Observation	Grade
Depth: 0.60 m IC2					
	0.00	MH	Start node, manhole, reference: IC2		
	0.00	WL	Water level, 5% of the vertical dimension		
	2.14	JN	Junction at 09 o'clock, 100mm dia		
	4.55	LL	Line deviates left		
	6.61	JN	Junction at 03 o'clock, 100mm dia		
	6.97	DEC	Settled deposits, hard or compacted, 20% cross-sectional area loss	4	
	7.07	LR	Line deviates right		
	7.14	DEC	Settled deposits, hard or compacted, 90% cross-sectional area loss	5	
	7.14	SA	Survey abandoned: Unable to continue		



Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	2	10.0	2.1	15.0	5.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
13	Upstream	IC2-CX	TV231025	



1, 00:01:20, 6.97 m
Settled deposits, hard or compacted, 20% cross-sectional area loss



2, 00:01:44, 7.14 m
Settled deposits, hard or compacted, 90% cross-sectional area loss



Section Inspection - 18/10/2023 - IC2X



Item No. 14	Insp. No. 1	Date 18/10/23	Time 10:51	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC2X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	IC2
Road:	Convent Of Mercy	Inspected Length:	7.75 m	Upstream Pipe Depth:	0.600 m
Location:		Total Length:	7.75 m	Downstream Node:	IC3
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.770 m
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale: 1:68 Position [m] Code Observation Grade

Depth: 0.60 m

IC2



0.00

MH

Start node, manhole, reference: IC2

0.00

WL

Water level, 5% of the vertical dimension

0.11

JN

Junction at 3 o'clock, 100mm dia: from IC2 (Run Y)

5.97

JN

Junction at 03 o'clock, 100mm dia

7.75

MHF

Finish node, manhole, reference: IC3

IC3

Depth: 0.77 m

Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 18/10/2023 - IC2Y




Item No. 15	Insp. No. 1	Date 18/10/23	Time 10:55	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC2Y
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	IC2
Road:	Convent Of Mercy	Inspected Length:	0.10 m	Upstream Pipe Depth:	0.600 m
Location:		Total Length:	0.10 m	Downstream Node:	RUN Y
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale: 1:50 Position [m] Code Observation Grade



Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 18/10/2023 - IC3-AX



Item No. 16	Insp. No. 1	Date 18/10/23	Time 11:12	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC3-AX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC3-A
Road:	Convent Of Mercy	Inspected Length:	2.95 m	Upstream Pipe Depth:	
Location:		Total Length:	2.95 m	Downstream Node:	IC3
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.770 m
Use:	Foul	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale: 1:50 Position [m] Code Observation Grade

Depth: 0.77 m

IC3



0.00

MH

Start node, manhole, reference: IC3

0.00

WL

Water level, 5% of the vertical dimension

1.82

CCJ

Crack, circumferential at joint from 09 o'clock to 02 o'clock 2 / 2

1.82

DEEJ

Attached deposits, encrustation at joint from 03 o'clock to 06 o'clock, 5% cross-sectional area loss 3

2.69

LU

Line deviates up

2.95

OFF

Finish node, outfall, reference: IC3-A: At wc

IC3-A

Depth: m



CCJ - 1.82



DEEJ - 1.82

Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
1	10.0	3.4	10.0	2.0	2	3.0	1.0	3.0	3.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
16	Upstream	IC3-AX	TV231025	



1, 00:00:20, 1.82 m
Crack, circumferential at joint from 09 o'clock to 02 o'clock



2, 00:00:28, 1.82 m
Attached deposits, encrustation at joint from 03 o'clock to 06 o'clock, 5% cross-sectional area loss



Section Inspection - 18/10/2023 - IC3X



Item No. 17	Insp. No. 1	Date 18/10/23	Time 11:14	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC3X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	IC3
Road:	Convent Of Mercy	Inspected Length:	1.51 m	Upstream Pipe Depth:	0.770 m
Location:		Total Length:	1.51 m	Downstream Node:	RUN X
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale:	1:50	Position [m]	Code	Observation	Grade
		0.00	MH	Start node, manhole, reference: IC3	
		0.00	WL	Water level, 5% of the vertical dimension	
		0.68	LL	Line deviates left	
		1.41	LL	Line deviates left	
		1.51	BRF	Finish node, major connection without manhole, reference: RUN X: At saddle connection	

Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 18/10/2023 - IC4-AX



Item No. 18	Insp. No. 1	Date 18/10/23	Time 11:39	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC4-AX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC4-A
Road:	Convent Of Mercy	Inspected Length:	20.37 m	Upstream Pipe Depth:	
Location:		Total Length:	20.37 m	Downstream Node:	IC4
Surface Type:		Joint Length:		Downstream Pipe Depth:	1.280 m
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Cast iron		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		
Comments:					
Recommendations: -					

Scale:	1:177	Position [m]	Code	Observation	Grade
Depth: 1.28 m	IC4	0.00	MH	Start node, manhole, reference: IC4	
		0.00	WL	Water level, 5% of the vertical dimension	
		13.49	JN	Junction at 12 o'clock, 100mm dia	
		13.92	DEC	Settled deposits, hard or compacted, 5% cross-sectional area loss	3
		14.82	JN	Junction at 03 o'clock, 100mm dia	
		15.03	DEC	Settled deposits, hard or compacted, 10% cross-sectional area loss	3
		18.49	S01	Attached deposits, encrustation from 07 o'clock to 05 o'clock, 5% cross-sectional area loss, start	
		20.35	F01	Attached deposits, encrustation from 7 o'clock to 5 o'clock, 5% cross-sectional area loss, finish	3
	IC4-A	20.37	OFF	Finish node, outfall, reference: IC4-A: At Y junction - unable to continue	
Depth: m					



DEC - 13.92



DEC - 15.03



DEE - 18.49



OFF - 20.37

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	3	2.0	0.4	8.0	3.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
18	Upstream	IC4-AX	TV231025	



1, 00:01:49, 13.92 m
Settled deposits, hard or compacted, 5% cross-sectional area loss



2, 00:02:12, 15.03 m
Settled deposits, hard or compacted, 10% cross-sectional area loss



3, 00:02:47, 18.49 m
Attached deposits, encrustation from 07 o'clock to 05 o'clock, 5% cross-sectional area loss, start



4, 00:03:36, 20.37 m
Finish node, outfall, reference: IC4-A, At Y junction - unable to continue




Section Inspection - 18/10/2023 - IC4-BX



Item No. 19	Insp. No. 1	Date 18/10/23	Time 11:57	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC4-BX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC4-B
Road:	Convent Of Mercy	Inspected Length:	16.56 m	Upstream Pipe Depth:	
Location:		Total Length:	16.56 m	Downstream Node:	IC4
Surface Type:		Joint Length:		Downstream Pipe Depth:	1.280 m
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	150 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		
Comments:					
Recommendations: -					



Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	1	2.0	1.7	28.0	3.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
19	Upstream	IC4-BX	TV231025	



1, 00:00:42, 3.31 m
Settled deposits, hard or compacted, 5% cross-sectional area loss, start



2, 00:02:30, 16.56 m
Finish node, outfall, reference: IC4-B, At capped / redundant end




Section Inspection - 18/10/2023 - IC4X



Item No. 20	Insp. No. 1	Date 18/10/23	Time 12:04	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC4X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	IC4
Road:	Convent Of Mercy	Inspected Length:	7.24 m	Upstream Pipe Depth:	1.280 m
Location:		Total Length:	7.24 m	Downstream Node:	6801
Surface Type:		Joint Length:		Downstream Pipe Depth:	1.610 m
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	150 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		
Comments:					
Recommendations: -					



Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	1	4.0	0.6	4.0	3.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
20	Downstream	IC4X	TV231025	



1, 00:00:53, 5.84 m
Roots, mass at joint, 10% cross-sectional area loss



Section Inspection - 18/10/2023 - 6801X



Item No. 21	Insp. No. 1	Date 18/10/23	Time 12:14	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR 6801X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	6801
Road:	Convent Of Mercy	Inspected Length:	40.23 m	Upstream Pipe Depth:	1.610 m
Location:		Total Length:	40.23 m	Downstream Node:	6804
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	150 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		
Comments:					
Recommendations: -					


Scale:	1:349	Position [m]	Code	Observation	Grade
Depth: 1.61 m					
6801		0.00	MH	Start node, manhole, reference: 6801	
		0.00	WL	Water level, 5% of the vertical dimension	
		8.31	DEC	Settled deposits, hard or compacted, 10% cross-sectional area loss	3
		9.45	S01 DEC	Settled deposits, hard or compacted, 5% cross-sectional area loss, start	
		14.53	JN	Junction at 9 o'clock, 100mm dia	
		28.47	WL	Water level, 10% of the vertical dimension	
		28.71	JN	Junction at 02 o'clock, 100mm dia	
		28.93	DEC	Settled deposits, hard or compacted, 20% cross-sectional area loss	4
		34.91	JN	Junction at 09 o'clock, 100mm dia	
		34.91	RF	Roots, fine	2
		35.69	WL	Water level, 5% of the vertical dimension	
		35.69	F01 DEC	Settled deposits, hard or compacted, 5% cross-sectional area loss, finish	3
		37.78	RMJ	Roots, mass at joint, 30% cross-sectional area loss	5
		38.07	JN	Junction at 03 o'clock, 150mm dia	
6804		40.23	MHF	Finish node, manhole, reference: 6804: Unable to lift - buried / covered over	
Depth: m					



Section Inspection - 18/10/2023 - 6801X



Item No. 21	Insp. No. 1	Date 18/10/23	Time 12:14	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR 6801X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -



MHF - 40.23

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	5	10.0	1.8	72.0	5.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
21	Downstream	6801X	TV231025	



1, 00:00:46, 8.31 m
Settled deposits, hard or compacted, 10% cross-sectional area loss



2, 00:01:07, 9.45 m
Settled deposits, hard or compacted, 5% cross-sectional area loss, start



3, 00:03:59, 28.93 m
Settled deposits, hard or compacted, 20% cross-sectional area loss



4, 00:05:06, 34.91 m
Roots, fine



5, 00:05:36, 37.78 m
Roots, mass at joint, 30% cross-sectional area loss



6, 00:06:09, 40.23 m
Finish node, manhole, reference: 6804, Unable to lift - buried / covered over



Section Inspection - 18/10/2023 - IC6X



Item No. 22	Insp. No. 1	Date 18/10/23	Time 13:02	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC6X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC6
Road:	Convent Of Mercy	Inspected Length:	10.92 m	Upstream Pipe Depth:	0.600 m
Location:		Total Length:	10.92 m	Downstream Node:	IC5
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.940 m
Use:	Surface water	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Polyvinyl chloride		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale: 1:95 Position [m] Code Observation Grade

Depth: 0.94 m

IC5



0.00

MH

Start node, manhole, reference: IC5

0.00

WL

Water level, 5% of the vertical dimension

4.46

JN

Junction at 3 o'clock, 100mm dia: from rwp + gully
2

8.01

LR

Line deviates right

10.92

MHF

Finish node, manhole, reference: IC6

IC6

Depth: 0.60 m

Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 18/10/2023 - IC5X




Item No. 23	Insp. No. 1	Date 18/10/23	Time 13:05	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC5X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	IC5
Road:	Convent Of Mercy	Inspected Length:	4.38 m	Upstream Pipe Depth:	0.940 m
Location:		Total Length:	4.38 m	Downstream Node:	RUN X
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Surface water	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Polyvinyl chloride		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -



Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
23	Downstream	IC5X	TV231025	



1, 00:00:43, 4.38 m
Finish node, soakaway, reference: RUN X, At buried rubble
filled soakaway




Section Inspection - 18/10/2023 - IC6-AX



Item No. 24	Insp. No. 1	Date 18/10/23	Time 13:22	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC6-AX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC6-A
Road:	Convent Of Mercy	Inspected Length:	2.17 m	Upstream Pipe Depth:	
Location:		Total Length:	2.17 m	Downstream Node:	IC6
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.600 m
Use:	Surface water	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Polyvinyl chloride		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		
Comments:					
Recommendations:	-				



Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 18/10/2023 - IC6-BX



Item No. 25	Insp. No. 1	Date 18/10/23	Time 13:23	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC6-BX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC6-B
Road:	Convent Of Mercy	Inspected Length:	0.57 m	Upstream Pipe Depth:	
Location:		Total Length:	0.57 m	Downstream Node:	IC6
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.600 m
Use:	Surface water	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Polyvinyl chloride		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:
Recommendations: -

Scale:	1:50	Position [m]	Code	Observation	Grade
		0.00	MH	Start node, manhole, reference: IC6	
		0.00	WL	Water level, 5% of the vertical dimension	
		0.57	LD	Line deviates down	
		0.57	GYF	Finish node, gully, reference: IC6-B: At gully	

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0

Section Inspection - 18/10/2023 - IC6-DX



Item No. 27	Insp. No. 1	Date 18/10/23	Time 13:24	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR IC6-DX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	IC6-D
Road:	Convent Of Mercy	Inspected Length:	1.89 m	Upstream Pipe Depth:	
Location:		Total Length:	1.89 m	Downstream Node:	IC6
Surface Type:		Joint Length:		Downstream Pipe Depth:	0.600 m
Use:	Surface water		Pipe Shape:	Circular	
Type of Pipe:			Dia/Height:	100 mm	
Flow Control:	-		Material:	Polyvinyl chloride	
Year Constructed:	Not Specified		Lining Type:	No Lining	
Inspection Purpose:	Routine inspection		Lining Material:	No Lining	
Comments:					
Recommendations:	-				

Scale: 1:50 Position [m]

Code Observation Grade

MH	Start node, manhole, reference: IC6	
WL	Water level, 5% of the vertical dimension	
LR	Line deviates right	
LU	Line deviates up	
OFF	Finish node, outfall, reference: IC6-D: At rwp	

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 19/10/2023 - RWP+GY6X





Item No. 29	Insp. No. 1	Date 19/10/23	Time 8:34	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR RWP+GY6X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	RWP+GY6
Road:	Convent Of Mercy	Inspected Length:	0.42 m	Upstream Pipe Depth:	
Location:		Total Length:	0.42 m	Downstream Node:	RUN X
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Surface water	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale:	1:50	Position [m]	Code	Observation	Grade
Depth: m RWP+GY6 					
		0.00	GY	Start node, gully, reference: RWP+GY6	
		0.00	WL	Water level, 5% of the vertical dimension	
		0.00	DEC	Settled deposits, hard or compacted, 95% cross-sectional area loss	5
		0.42	SA	Survey abandoned: Loss of vision	



CONVENT OF MERCY
1906723

PRELIMINARY
DOWNSTREAM
RUN X
100mm

DEC - 0.00



SURVEY ABANDONED

0.42m

SA - 0.42

Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations


STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	1	10.0	23.8	10.0	5.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
29	Downstream	RWP+GY6X	TV231025	



1, 00:00:02, 0.00 m
Settled deposits, hard or compacted, 95% cross-sectional area loss



2, 00:00:15, 0.42 m
Survey abandoned, Loss of vision



Section Inspection - 19/10/2023 - COMB GY5-AX




Item No. 30	Insp. No. 1	Date 19/10/23	Time 8:35	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR COMB GY5-AX
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	COMB GY5-A
Road:	Convent Of Mercy	Inspected Length:	0.32 m	Upstream Pipe Depth:	
Location:		Total Length:	0.32 m	Downstream Node:	COMB GY5
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:

Recommendations: -

Scale: 1:50 Position [m] Code Observation Grade



Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0



Section Inspection - 19/10/2023 - COMB GY5X



Item No. 31	Insp. No. 1	Date 19/10/23	Time 8:36	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR COMB GY5X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Downstream	Upstream Node:	COMB GY5
Road:	Convent Of Mercy	Inspected Length:	0.30 m	Upstream Pipe Depth:	
Location:		Total Length:	0.30 m	Downstream Node:	RUN X
Surface Type:		Joint Length:		Downstream Pipe Depth:	
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	100 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine Inspection	Lining Material:	No Lining		

Comments:	
Recommendations:	-

Scale: 1:50	Position [m]	Code	Observation	Grade
Depth: m COMB GY5				
	0.00	GY	Start node, gully, reference: COMB GY5	
	0.00	WL	Water level, 5% of the vertical dimension	
	0.00	S01	DEC Settled deposits, hard or compacted, 10% cross-sectional area loss, start	
	0.13	LR	Line deviates right	
	0.30	F01	DEC Settled deposits, hard or compacted, 10% cross-sectional area loss, finish	3
	0.30	SA	Survey abandoned: Unable to continue	



DEC - 0.00



SA - 0.30

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	1	2.0	6.7	2.0	5.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
31	Downstream	COMB GY5X	TV231025	



1, 00:00:00, 0.00 m
Settled deposits, hard or compacted, 10% cross-sectional area loss, start



2, 00:00:12, 0.30 m
Survey abandoned, Unable to continue



Section Inspection - 19/10/2023 - 6804X



Item No. 32	Insp. No. 1	Date 19/10/23	Time 10:14	Client's Job Ref TV231025	Weather No Rain Or Snow	Pre Cleaned No	PLR 6804X
Operator InSewer MO		Vehicle -		Camera Not Specified	Preset Length Not Specified	Legal Status -	Alternative ID -

Town or Village:	Gravesend	Inspection Direction:	Upstream	Upstream Node:	6804
Road:	Convent Of Mercy	Inspected Length:	70.43 m	Upstream Pipe Depth:	
Location:		Total Length:	70.43 m	Downstream Node:	5901
Surface Type:		Joint Length:		Downstream Pipe Depth:	1.600 m
Use:	Combined	Pipe Shape:	Circular		
Type of Pipe:		Dia/Height:	150 mm		
Flow Control:	-	Material:	Vitrified clay		
Year Constructed:	Not Specified	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection	Lining Material:	No Lining		
Comments:					
Recommendations: -					

Scale: 1:610	Position [m]	Code	Observation	Grade
Depth: 1.60 m 5901 0.00 0.00 0.70 1.18 7.42 10.49 15.56 33.77 38.03 43.38 50.67 51.11 51.33 70.43 70.43				
		MH	Start node, manhole, reference: 5901	
		WL	Water level, 5% of the vertical dimension	
		RMJ	Roots, mass at joint, 5% cross-sectional area loss	3
		JN	Junction at 02 o'clock, 100mm dia	
		JN	Junction at 09 o'clock, 100mm dia	
		DEE	Attached deposits, encrustation from 05 o'clock to 07 o'clock, 5% cross-sectional area loss, start	
		CN	Connection other than junction at 09 o'clock, 100mm dia	
		JN	Junction at 09 o'clock, 100mm dia	
		JN	Junction at 03 o'clock, 100mm dia	
		CN	Connection other than junction at 02 o'clock, 100mm dia	
		RMJ	Roots, mass at joint, 20% cross-sectional area loss	5
		CN	Connection other than junction at 10 o'clock, 100mm dia	
		RMJ	Roots, mass at joint, 5% cross-sectional area loss	3
		DEE	Attached deposits, encrustation from 5 o'clock to 7 o'clock, 5% cross-sectional area loss, finish	3
		SA	Survey abandoned: Loss of vision	



RMJ - 0.70



DEE - 10.49



RMJ - 51.33



SA - 70.43

Construction Features					Miscellaneous Features				
Structural Defects					Service & Operational Observations				
STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	4	12.0	2.0	138.0	5.0



Item No.	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
32	Upstream	6804X	TV231025	



1, 00:00:26, 0.70 m
Roots, mass at joint, 5% cross-sectional area loss



2, 00:01:45, 10.49 m
Attached deposits, encrustation from 05 o'clock to 07 o'clock, 5% cross-sectional area loss, start



3, 00:07:16, 51.33 m
Roots, mass at joint, 5% cross-sectional area loss



4, 00:10:11, 70.43 m
Survey abandoned, Loss of vision



*Sewer Inspection,
Cleaning and Repair*

Recommendations

www.insewer.co.uk

Tel : 01634 861 768



Section number	Upstream manhole	Flow direction	Downstream manhole	Recommendations / Notes
1	6802-A	Upstream	6802	Repair defect(s) by lining
2	6802	Downstream	6803	Public Sewer
3	SVP 1	Downstream	RUN X	Clean by specialist root cutting and repair by lining
4	SP 1	Downstream	RUN X	
5	6803-A	Upstream	6803	
6	6803	Downstream	6804	Public Sewer
7	IC1-A	Upstream	IC1	
8	IC1-B	Upstream	IC1	Repair defect(s) by lining
9	IC1-C	Upstream	IC1	
10	IC1	Downstream	RUN X	
11	IC2-A	Upstream	IC2	
12	IC2-B	Upstream	IC2	Repair defect(s) by lining
13	IC2-C	Upstream	IC2	Clean by van pack jetting unit and resurvey
14	IC2	Downstream	IC3	
15	IC2	Downstream	RUN Y	
16	IC3-A	Upstream	IC3	Repair defect(s) by lining
17	IC3	Downstream	RUN X	
18	IC4-A	Upstream	IC4	Clean by specialist high pressure descaling and resurvey
19	IC4-B	Upstream	IC4	
20	IC4	Downstream	6801	Clean by specialist root cutting and repair by lining
21	6801	Downstream	6804	Public Sewer
22	IC6	Upstream	IC5	
23	IC5	Downstream	RUN X	
24	IC6-A	Upstream	IC6	
25	IC6-B	Upstream	IC6	
26	IC6-C	Upstream	IC6	
27	IC6-D	Upstream	IC6	
28	RWP+GY6-A	Upstream	RWP+GY6	
29	RWP+GY6	Downstream	RUN X	Attempt to clean by van pack jetting unit and resurvey
30	COMB GY5-A	Upstream	COMB GY5	
31	COMB GY5	Downstream	RUN X	Attempt to clean by van pack jetting unit and resurvey
32	6804	Upstream	5901	Public Sewer



Our Services

- *CCTV Surveys*
- *Sewer and Utility Location*
- *Topographical Surveys*
- *Tanker Jetting*
- *High Pressure Jetting*
- *Cesspool Emptying*
- *Interceptor Cleaning*
- *Pump Station Cleaning*
- *Root and Scale Cutting*
- *Pipe Lining*
- *Trenchless Technology*
- *Confined Space Entry*

Call : 01634 861768

CCTV Sewer Inspection • Electronic Location • Cleaning and Repair

Registered Office Address:
Hydro Descaling Limited
16a Revenge Rd, Lordswood Ind. Est.
Chatham, Kent ME5 8UD
Company Reg No: 1304128
VAT No. 573 7537 09



"A Family Run Business Since 1977"




(c) Crown copyright and database rights 2023 Ordnance Survey 100031673 Date: 15/08/23 Scale: 1:1250 Map Centre: 565633,172863 Data updated: 05/05/23 Our Ref: 1250656 - 2 Wastewater Plan A3

The positions of pipes shown on this plan are believed to be correct, but Southern Water Services Ltd accept no responsibility in the event of inaccuracy. The actual positions should be determined on site. This plan is produced by Southern Water Services Ltd (c) Crown copyright and database rights 2023 Ordnance Survey 100031673. This map is to be used for the purposes of viewing the location of Southern Water plant only. Any other uses of the map data or further copies is not permitted.

WARNING: BAC pipes are constructed of Bonded Asbestos Cement.

WARNING: Unknown (UNK) materials may include Bonded Asbestos Cement.



mail@pciconsult.co.uk

Convent of Mercy



Appendix D
Site Investigation

BRE 365 SOAKAGE TEST REPORT

Date : 25th October 2024

Report No : 10577/30

Client :

Sister Anne O'Connell

Site :

Convent of Mercy
Hillside Drive
Gravesend
DA12 1NY

Approx Grid Ref: 569632 155285

Approx. Elevation: 36m

Soiltec have been commissioned to carry out a BRE 365 Soakaway Design Test at the above site. To this end a single trial pit was excavated by on site contractors prior to our arrival at a location deemed suitable and shown on the included site plan.

Anticipated geological deposit - From an examination of the online BGS geological map for the area the solid geological deposit appears as Thanet Formation. No Superficial deposits are recorded.

Thanet Formation

Typically composed of homogeneous, bioturbated, glauconitic silty fine-grained sand, with sandy silt, silt or sandy, silty clay especially in the lower part, forming a coarsening-upwards sequence. The deposits are generally pale yellow-brown in colour, typically with 'peppering' of dark-coloured glauconite grains. Spare white mica occurs throughout. Rare coarse gravel is present in places in London.

Soakage Test Results – The trial pit was filled with water from a bowser to anticipated invert level of proposed drainage.

During the test period the water levels are recorded and a graph of depth to water against time is plotted. From this plot, utilising the times for the water level to drop from 25% empty to 75% empty, the infiltration rate is calculated.

The result of the soakage test indicated a soakage potential for the site with a soil infiltration rate (f) of 5.20×10^{-6} m/s.

Traditional soakaways could effectively dispose of surface water from the proposed development provided that they are installed at least 5.00m from any foundations.

For and on behalf of
Soiltec Laboratories Limited



Andrew Hayward
Director

BRE Digest 365 Soakage Test (Trial Pit)

Client :	Sister Anne O'Connell	Date of Test :	23/10/24
Site :	Convent of mercy Phase 3, Hillside Drive	Report No:	10577/30
Trial Pit :	1		


Trial Pit	
Length	1.50 m
Width	0.90 m
Depth	1.65 m
Assumed invert level*	0.29 m
Ground conditions	Sandy, silty CLAY

Results

Effective storage depth	1.36 m
75% effective storage depth	1.02 m
depth below GL	1.31 m
25% effective storage depth	0.34 m
depth below GL	0.63 m
Effective volume of outflowing between 75% - 25%	0.92 m ³
Effective storage depth 75%-25%	0.68 m
Mean surface area (a_{p50})	4.61 m ²
Out flow time to 75% effective depth (tp75)	69.7 mins
Out flow time to 25% effective depth (tp 25)	707.2 mins
Outflow time (Tp75%-Tp25%)	637.5 mins

Soil Infiltration Rate (f) = 5.20E-06 m/s

Time mins	Depth to water
0	0.29
6	0.36
32	0.52
80	0.66
153	0.78
248	0.90
1312	1.65



*or water level at start of test	Tested by	AH/RF
	Approved	AH/RF



Scale: nts

Drawn : AJH

Location : Convent of Mercy, Hillside Drive

Report: 10577/30

Title : Site Location Plan

Fig. No.: 2

Appendix E
Outline MicroDrainage Calculations

Alan Baxter Partnership LLP		Page 1
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Plot 1	
Date 29/01/2025 File C1477-Soakaway Design-Plot 1 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+45%)

Half Drain Time : 1391 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m ³)	Status
15 min Summer	33.826	0.226	0.1	6.4	O K
30 min Summer	33.894	0.294	0.1	8.4	O K
60 min Summer	33.963	0.363	0.1	10.3	O K
120 min Summer	34.038	0.438	0.1	12.5	O K
180 min Summer	34.084	0.484	0.1	13.8	O K
240 min Summer	34.116	0.516	0.1	14.7	O K
360 min Summer	34.154	0.554	0.1	15.8	O K
480 min Summer	34.171	0.571	0.1	16.3	O K
600 min Summer	34.178	0.578	0.1	16.5	O K
720 min Summer	34.179	0.579	0.1	16.5	O K
960 min Summer	34.168	0.568	0.1	16.2	O K
1440 min Summer	34.137	0.537	0.1	15.3	O K
2160 min Summer	34.097	0.497	0.1	14.2	O K
2880 min Summer	34.062	0.462	0.1	13.2	O K
4320 min Summer	34.004	0.404	0.1	11.5	O K
5760 min Summer	33.957	0.357	0.1	10.2	O K
7200 min Summer	33.918	0.318	0.1	9.1	O K
8640 min Summer	33.885	0.285	0.1	8.1	O K
10080 min Summer	33.857	0.257	0.1	7.3	O K
15 min Winter	33.853	0.253	0.1	7.2	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Time-Peak (mins)
15 min Summer	166.246	0.0	27
30 min Summer	108.697	0.0	41
60 min Summer	67.702	0.0	70
120 min Summer	41.667	0.0	130
180 min Summer	31.264	0.0	188
240 min Summer	25.407	0.0	248
360 min Summer	18.809	0.0	366
480 min Summer	15.045	0.0	486
600 min Summer	12.589	0.0	604
720 min Summer	10.851	0.0	722
960 min Summer	8.538	0.0	960
1440 min Summer	6.054	0.0	1176
2160 min Summer	4.286	0.0	1548
2880 min Summer	3.357	0.0	1960
4320 min Summer	2.383	0.0	2772
5760 min Summer	1.878	0.0	3576
7200 min Summer	1.571	0.0	4392
8640 min Summer	1.364	0.0	5120
10080 min Summer	1.215	0.0	5944
15 min Winter	166.246	0.0	26

Alan Baxter Partnership LLP		Page 2
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtER Soakaway Design Plot 1	
Date 29/01/2025 File C1477-Soakaway Design-Plot 1 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Summary of Results for 100 year Return Period (+45%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
30 min Winter	33.930	0.330	0.1	9.4	O K
60 min Winter	34.007	0.407	0.1	11.6	O K
120 min Winter	34.093	0.493	0.1	14.0	O K
180 min Winter	34.146	0.546	0.1	15.6	O K
240 min Winter	34.183	0.583	0.1	16.6	O K
360 min Winter	34.228	0.628	0.1	17.9	O K
480 min Winter	34.250	0.650	0.1	18.5	O K
600 min Winter	34.260	0.660	0.1	18.8	O K
720 min Winter	34.263	0.663	0.1	18.9	O K
960 min Winter	34.257	0.657	0.1	18.7	O K
1440 min Winter	34.223	0.623	0.1	17.7	O K
2160 min Winter	34.173	0.573	0.1	16.3	O K
2880 min Winter	34.128	0.528	0.1	15.1	O K
4320 min Winter	34.047	0.447	0.1	12.7	O K
5760 min Winter	33.978	0.378	0.1	10.8	O K
7200 min Winter	33.921	0.321	0.1	9.1	O K
8640 min Winter	33.872	0.272	0.1	7.7	O K
10080 min Winter	33.830	0.230	0.1	6.6	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
30 min Winter	108.697	0.0	41
60 min Winter	67.702	0.0	70
120 min Winter	41.667	0.0	128
180 min Winter	31.264	0.0	186
240 min Winter	25.407	0.0	244
360 min Winter	18.809	0.0	360
480 min Winter	15.045	0.0	476
600 min Winter	12.589	0.0	592
720 min Winter	10.851	0.0	706
960 min Winter	8.538	0.0	928
1440 min Winter	6.054	0.0	1340
2160 min Winter	4.286	0.0	1656
2880 min Winter	3.357	0.0	2112
4320 min Winter	2.383	0.0	2996
5760 min Winter	1.878	0.0	3864
7200 min Winter	1.571	0.0	4688
8640 min Winter	1.364	0.0	5456
10080 min Winter	1.215	0.0	6256

Alan Baxter Partnership LLP		Page 3
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Plot 1	
Date 29/01/2025 File C1477-Soakaway Design-Plot 1 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Rainfall Details

Rainfall Model	FEH	Data Type	Point	Cv (Winter)	0.840
Return Period (years)	100	Summer Storms	Yes	Shortest Storm (mins)	15
FEH Rainfall Version	2013	Winter Storms	Yes	Longest Storm (mins)	10080
Site Location	GB 565706 172866 TQ 65706 72866	Cv (Summer)	0.750	Climate Change %	+45

Time Area Diagram

Total Area (ha) 0.021

Time (mins)	Area	Time (mins)	Area	Time (mins)	Area
From: To:	(ha)	From: To:	(ha)	From: To:	(ha)
0 4	0.007	4 8	0.007	8 12	0.007

Alan Baxter Partnership LLP		Page 4
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAter Soakaway Design Plot 1	
Date 29/01/2025 File C1477-Soakaway Design-Plot 1 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Model Details

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 33.600 Infiltration Coefficient Side (m/hr) 0.02016 Porosity 0.95
Infiltration Coefficient Base (m/hr) 0.02016 Safety Factor 2.0

Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)
0.000	30.0	30.0	0.800	30.0	47.6	0.900	0.0	47.6

Alan Baxter Partnership LLP		Page 1
The Clock Building	C1477 - Convent of Mercy Ph. 3	
Loose	Surface WAtEr Soakaway Design	
ME15 0HZ	Plot 2	
Date 29/01/2025	Designed by ARWS	
File C1477-Soakaway Design-Plot 2 (0).SRCX	Checked by ARWS	
XP Solutions	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+45%)

Half Drain Time : 1290 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m ³)	Status
15 min Summer	33.808	0.208	0.1	5.9	O K
30 min Summer	33.870	0.270	0.1	7.7	O K
60 min Summer	33.933	0.333	0.1	9.5	O K
120 min Summer	34.002	0.402	0.1	11.5	O K
180 min Summer	34.044	0.444	0.1	12.6	O K
240 min Summer	34.072	0.472	0.1	13.5	O K
360 min Summer	34.106	0.506	0.1	14.4	O K
480 min Summer	34.121	0.521	0.1	14.8	O K
600 min Summer	34.126	0.526	0.1	15.0	O K
720 min Summer	34.125	0.525	0.1	15.0	O K
960 min Summer	34.113	0.513	0.1	14.6	O K
1440 min Summer	34.084	0.484	0.1	13.8	O K
2160 min Summer	34.046	0.446	0.1	12.7	O K
2880 min Summer	34.013	0.413	0.1	11.8	O K
4320 min Summer	33.958	0.358	0.1	10.2	O K
5760 min Summer	33.913	0.313	0.1	8.9	O K
7200 min Summer	33.876	0.276	0.1	7.9	O K
8640 min Summer	33.844	0.244	0.1	7.0	O K
10080 min Summer	33.817	0.217	0.1	6.2	O K
15 min Winter	33.833	0.233	0.1	6.6	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Time-Peak (mins)
15 min Summer	166.246	0.0	26
30 min Summer	108.697	0.0	41
60 min Summer	67.702	0.0	70
120 min Summer	41.667	0.0	130
180 min Summer	31.264	0.0	188
240 min Summer	25.407	0.0	248
360 min Summer	18.809	0.0	366
480 min Summer	15.045	0.0	484
600 min Summer	12.589	0.0	604
720 min Summer	10.851	0.0	722
960 min Summer	8.538	0.0	936
1440 min Summer	6.054	0.0	1146
2160 min Summer	4.286	0.0	1524
2880 min Summer	3.357	0.0	1936
4320 min Summer	2.383	0.0	2736
5760 min Summer	1.878	0.0	3536
7200 min Summer	1.571	0.0	4328
8640 min Summer	1.364	0.0	5104
10080 min Summer	1.215	0.0	5856
15 min Winter	166.246	0.0	26

Alan Baxter Partnership LLP		Page 2
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Plot 2	
Date 29/01/2025 File C1477-Soakaway Design-Plot 2 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+45%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
30 min Winter	33.903	0.303	0.1	8.6	O K
60 min Winter	33.974	0.374	0.1	10.7	O K
120 min Winter	34.052	0.452	0.1	12.9	O K
180 min Winter	34.101	0.501	0.1	14.3	O K
240 min Winter	34.134	0.534	0.1	15.2	O K
360 min Winter	34.174	0.574	0.1	16.4	O K
480 min Winter	34.193	0.593	0.1	16.9	O K
600 min Winter	34.202	0.602	0.1	17.1	O K
720 min Winter	34.203	0.603	0.1	17.2	O K
960 min Winter	34.195	0.595	0.1	17.0	O K
1440 min Winter	34.160	0.560	0.1	16.0	O K
2160 min Winter	34.114	0.514	0.1	14.6	O K
2880 min Winter	34.070	0.470	0.1	13.4	O K
4320 min Winter	33.991	0.391	0.1	11.1	O K
5760 min Winter	33.925	0.325	0.1	9.3	O K
7200 min Winter	33.870	0.270	0.1	7.7	O K
8640 min Winter	33.824	0.224	0.1	6.4	O K
10080 min Winter	33.785	0.185	0.1	5.3	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
30 min Winter	108.697	0.0	41
60 min Winter	67.702	0.0	70
120 min Winter	41.667	0.0	128
180 min Winter	31.264	0.0	186
240 min Winter	25.407	0.0	244
360 min Winter	18.809	0.0	360
480 min Winter	15.045	0.0	476
600 min Winter	12.589	0.0	590
720 min Winter	10.851	0.0	704
960 min Winter	8.538	0.0	924
1440 min Winter	6.054	0.0	1316
2160 min Winter	4.286	0.0	1644
2880 min Winter	3.357	0.0	2104
4320 min Winter	2.383	0.0	2984
5760 min Winter	1.878	0.0	3808
7200 min Winter	1.571	0.0	4616
8640 min Winter	1.364	0.0	5376
10080 min Winter	1.215	0.0	6152

Alan Baxter Partnership LLP		Page 3
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAter Soakaway Design Plot 2	
Date 29/01/2025 File C1477-Soakaway Design-Plot 2 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Rainfall Details

Rainfall Model	FEH	Data Type	Point	Cv (Winter)	0.840
Return Period (years)	100	Summer Storms	Yes	Shortest Storm (mins)	15
FEH Rainfall Version	2013	Winter Storms	Yes	Longest Storm (mins)	10080
Site Location	GB 565706 172866 TQ 65706 72866	Cv (Summer)	0.750	Climate Change %	+45

Time Area Diagram

Total Area (ha) 0.019

Time (mins)	Area	Time (mins)	Area	Time (mins)	Area
From:	To:	From:	To:	From:	To:
	(ha)		(ha)		(ha)
0	4 0.007	4	8 0.006	8	12 0.006

Alan Baxter Partnership LLP		Page 4
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Plot 2	
Date 29/01/2025 File C1477-Soakaway Design-Plot 2 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Model Details

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 33.600 Infiltration Coefficient Side (m/hr) 0.02016 Porosity 0.95
Infiltration Coefficient Base (m/hr) 0.02016 Safety Factor 2.0

Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)
0.000	30.0	30.0	0.800	30.0	47.6	0.900	0.0	47.6

Alan Baxter Partnership LLP		Page 1
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Plot 3	
Date 29/01/2025 File C1477-Soakaway Design-Plot 3 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Summary of Results for 100 year Return Period (+45%)

Half Drain Time : 1290 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
15 min Summer	33.808	0.208	0.1	5.9	O K
30 min Summer	33.870	0.270	0.1	7.7	O K
60 min Summer	33.933	0.333	0.1	9.5	O K
120 min Summer	34.002	0.402	0.1	11.5	O K
180 min Summer	34.044	0.444	0.1	12.6	O K
240 min Summer	34.072	0.472	0.1	13.5	O K
360 min Summer	34.106	0.506	0.1	14.4	O K
480 min Summer	34.121	0.521	0.1	14.8	O K
600 min Summer	34.126	0.526	0.1	15.0	O K
720 min Summer	34.125	0.525	0.1	15.0	O K
960 min Summer	34.113	0.513	0.1	14.6	O K
1440 min Summer	34.084	0.484	0.1	13.8	O K
2160 min Summer	34.046	0.446	0.1	12.7	O K
2880 min Summer	34.013	0.413	0.1	11.8	O K
4320 min Summer	33.958	0.358	0.1	10.2	O K
5760 min Summer	33.913	0.313	0.1	8.9	O K
7200 min Summer	33.876	0.276	0.1	7.9	O K
8640 min Summer	33.844	0.244	0.1	7.0	O K
10080 min Summer	33.817	0.217	0.1	6.2	O K
15 min Winter	33.833	0.233	0.1	6.6	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
15 min Summer	166.246	0.0	26
30 min Summer	108.697	0.0	41
60 min Summer	67.702	0.0	70
120 min Summer	41.667	0.0	130
180 min Summer	31.264	0.0	188
240 min Summer	25.407	0.0	248
360 min Summer	18.809	0.0	366
480 min Summer	15.045	0.0	484
600 min Summer	12.589	0.0	604
720 min Summer	10.851	0.0	722
960 min Summer	8.538	0.0	936
1440 min Summer	6.054	0.0	1146
2160 min Summer	4.286	0.0	1524
2880 min Summer	3.357	0.0	1936
4320 min Summer	2.383	0.0	2736
5760 min Summer	1.878	0.0	3536
7200 min Summer	1.571	0.0	4328
8640 min Summer	1.364	0.0	5104
10080 min Summer	1.215	0.0	5856
15 min Winter	166.246	0.0	26

Summary of Results for 100 year Return Period (+45%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
30 min Winter	33.903	0.303	0.1	8.6	O K
60 min Winter	33.974	0.374	0.1	10.7	O K
120 min Winter	34.052	0.452	0.1	12.9	O K
180 min Winter	34.101	0.501	0.1	14.3	O K
240 min Winter	34.134	0.534	0.1	15.2	O K
360 min Winter	34.174	0.574	0.1	16.4	O K
480 min Winter	34.193	0.593	0.1	16.9	O K
600 min Winter	34.202	0.602	0.1	17.1	O K
720 min Winter	34.203	0.603	0.1	17.2	O K
960 min Winter	34.195	0.595	0.1	17.0	O K
1440 min Winter	34.160	0.560	0.1	16.0	O K
2160 min Winter	34.114	0.514	0.1	14.6	O K
2880 min Winter	34.070	0.470	0.1	13.4	O K
4320 min Winter	33.991	0.391	0.1	11.1	O K
5760 min Winter	33.925	0.325	0.1	9.3	O K
7200 min Winter	33.870	0.270	0.1	7.7	O K
8640 min Winter	33.824	0.224	0.1	6.4	O K
10080 min Winter	33.785	0.185	0.1	5.3	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
30 min Winter	108.697	0.0	41
60 min Winter	67.702	0.0	70
120 min Winter	41.667	0.0	128
180 min Winter	31.264	0.0	186
240 min Winter	25.407	0.0	244
360 min Winter	18.809	0.0	360
480 min Winter	15.045	0.0	476
600 min Winter	12.589	0.0	590
720 min Winter	10.851	0.0	704
960 min Winter	8.538	0.0	924
1440 min Winter	6.054	0.0	1316
2160 min Winter	4.286	0.0	1644
2880 min Winter	3.357	0.0	2104
4320 min Winter	2.383	0.0	2984
5760 min Winter	1.878	0.0	3808
7200 min Winter	1.571	0.0	4616
8640 min Winter	1.364	0.0	5376
10080 min Winter	1.215	0.0	6152

Alan Baxter Partnership LLP		Page 3
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Plot 3	
Date 29/01/2025 File C1477-Soakaway Design-Plot 3 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Rainfall Details

Rainfall Model	FEH	Data Type	Point	Cv (Winter)	0.840
Return Period (years)	100	Summer Storms	Yes	Shortest Storm (mins)	15
FEH Rainfall Version	2013	Winter Storms	Yes	Longest Storm (mins)	10080
Site Location	GB 565706 172866 TQ 65706 72866	Cv (Summer)	0.750	Climate Change %	+45

Time Area Diagram

Total Area (ha) 0.019

Time (mins)	Area	Time (mins)	Area	Time (mins)	Area
From: To:	(ha)	From: To:	(ha)	From: To:	(ha)
0 4	0.007	4 8	0.006	8 12	0.006

Alan Baxter Partnership LLP		Page 4
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAter Soakaway Design Plot 3	
Date 29/01/2025 File C1477-Soakaway Design-Plot 3 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Model Details

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 33.600 Infiltration Coefficient Side (m/hr) 0.02016 Porosity 0.95
Infiltration Coefficient Base (m/hr) 0.02016 Safety Factor 2.0

Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)
0.000	30.0	30.0	0.800	30.0	47.6	0.900	0.0	47.6

Alan Baxter Partnership LLP		Page 1
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtER Soakaway Design Plot 4	
Date 29/01/2025 File C1477-Soakaway Design-Plot 4 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Summary of Results for 100 year Return Period (+45%)

Half Drain Time : 1290 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m ³)	Status
15 min Summer	33.808	0.208	0.1	5.9	O K
30 min Summer	33.870	0.270	0.1	7.7	O K
60 min Summer	33.933	0.333	0.1	9.5	O K
120 min Summer	34.002	0.402	0.1	11.5	O K
180 min Summer	34.044	0.444	0.1	12.6	O K
240 min Summer	34.072	0.472	0.1	13.5	O K
360 min Summer	34.106	0.506	0.1	14.4	O K
480 min Summer	34.121	0.521	0.1	14.8	O K
600 min Summer	34.126	0.526	0.1	15.0	O K
720 min Summer	34.125	0.525	0.1	15.0	O K
960 min Summer	34.113	0.513	0.1	14.6	O K
1440 min Summer	34.084	0.484	0.1	13.8	O K
2160 min Summer	34.046	0.446	0.1	12.7	O K
2880 min Summer	34.013	0.413	0.1	11.8	O K
4320 min Summer	33.958	0.358	0.1	10.2	O K
5760 min Summer	33.913	0.313	0.1	8.9	O K
7200 min Summer	33.876	0.276	0.1	7.9	O K
8640 min Summer	33.844	0.244	0.1	7.0	O K
10080 min Summer	33.817	0.217	0.1	6.2	O K
15 min Winter	33.833	0.233	0.1	6.6	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Time-Peak (mins)
15 min Summer	166.246	0.0	26
30 min Summer	108.697	0.0	41
60 min Summer	67.702	0.0	70
120 min Summer	41.667	0.0	130
180 min Summer	31.264	0.0	188
240 min Summer	25.407	0.0	248
360 min Summer	18.809	0.0	366
480 min Summer	15.045	0.0	484
600 min Summer	12.589	0.0	604
720 min Summer	10.851	0.0	722
960 min Summer	8.538	0.0	936
1440 min Summer	6.054	0.0	1146
2160 min Summer	4.286	0.0	1524
2880 min Summer	3.357	0.0	1936
4320 min Summer	2.383	0.0	2736
5760 min Summer	1.878	0.0	3536
7200 min Summer	1.571	0.0	4328
8640 min Summer	1.364	0.0	5104
10080 min Summer	1.215	0.0	5856
15 min Winter	166.246	0.0	26

Alan Baxter Partnership LLP		Page 2
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Plot 4	
Date 29/01/2025	Designed by ARWS	
File C1477-Soakaway Design-Plot 4 (0).SRCX	Checked by ARWS	
XP Solutions	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+45%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
30 min Winter	33.903	0.303	0.1	8.6	O K
60 min Winter	33.974	0.374	0.1	10.7	O K
120 min Winter	34.052	0.452	0.1	12.9	O K
180 min Winter	34.101	0.501	0.1	14.3	O K
240 min Winter	34.134	0.534	0.1	15.2	O K
360 min Winter	34.174	0.574	0.1	16.4	O K
480 min Winter	34.193	0.593	0.1	16.9	O K
600 min Winter	34.202	0.602	0.1	17.1	O K
720 min Winter	34.203	0.603	0.1	17.2	O K
960 min Winter	34.195	0.595	0.1	17.0	O K
1440 min Winter	34.160	0.560	0.1	16.0	O K
2160 min Winter	34.114	0.514	0.1	14.6	O K
2880 min Winter	34.070	0.470	0.1	13.4	O K
4320 min Winter	33.991	0.391	0.1	11.1	O K
5760 min Winter	33.925	0.325	0.1	9.3	O K
7200 min Winter	33.870	0.270	0.1	7.7	O K
8640 min Winter	33.824	0.224	0.1	6.4	O K
10080 min Winter	33.785	0.185	0.1	5.3	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
30 min Winter	108.697	0.0	41
60 min Winter	67.702	0.0	70
120 min Winter	41.667	0.0	128
180 min Winter	31.264	0.0	186
240 min Winter	25.407	0.0	244
360 min Winter	18.809	0.0	360
480 min Winter	15.045	0.0	476
600 min Winter	12.589	0.0	590
720 min Winter	10.851	0.0	704
960 min Winter	8.538	0.0	924
1440 min Winter	6.054	0.0	1316
2160 min Winter	4.286	0.0	1644
2880 min Winter	3.357	0.0	2104
4320 min Winter	2.383	0.0	2984
5760 min Winter	1.878	0.0	3808
7200 min Winter	1.571	0.0	4616
8640 min Winter	1.364	0.0	5376
10080 min Winter	1.215	0.0	6152

Alan Baxter Partnership LLP		Page 3
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Plot 4	
Date 29/01/2025 File C1477-Soakaway Design-Plot 4 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Rainfall Details

Rainfall Model	FEH	Data Type	Point	Cv (Winter)	0.840
Return Period (years)	100	Summer Storms	Yes	Shortest Storm (mins)	15
FEH Rainfall Version	2013	Winter Storms	Yes	Longest Storm (mins)	10080
Site Location	GB 565706 172866 TQ 65706 72866	Cv (Summer)	0.750	Climate Change %	+45

Time Area Diagram

Total Area (ha) 0.019

Time (mins)	Area	Time (mins)	Area	Time (mins)	Area
From: To:	(ha)	From: To:	(ha)	From: To:	(ha)
0 4	0.007	4 8	0.006	8 12	0.006

Alan Baxter Partnership LLP		Page 4
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Plot 4	
Date 29/01/2025 File C1477-Soakaway Design-Plot 4 (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Model Details

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 33.600 Infiltration Coefficient Side (m/hr) 0.02016 Porosity 0.95
Infiltration Coefficient Base (m/hr) 0.02016 Safety Factor 2.0

Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)
0.000	30.0	30.0	0.800	30.0	47.6	0.900	0.0	47.6

Alan Baxter Partnership LLP		Page 1
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3	
	Surface WATER Soakaway Design	
	Access Road	
Date 29/01/2025	Designed by ARWS	
File C1477-Soakaway Design-Access Road (0).SRCX	Checked by ARWS	
XP Solutions	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+45%)

Half Drain Time : 1396 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
15 min Summer	33.812	0.212	0.2	12.6	O K
30 min Summer	33.876	0.276	0.2	16.4	O K
60 min Summer	33.940	0.340	0.2	20.2	O K
120 min Summer	34.010	0.410	0.2	24.4	O K
180 min Summer	34.053	0.453	0.2	26.9	O K
240 min Summer	34.083	0.483	0.2	28.7	O K
360 min Summer	34.119	0.519	0.2	30.8	O K
480 min Summer	34.135	0.535	0.2	31.8	O K
600 min Summer	34.142	0.542	0.2	32.2	O K
720 min Summer	34.142	0.542	0.2	32.2	O K
960 min Summer	34.132	0.532	0.2	31.6	O K
1440 min Summer	34.102	0.502	0.2	29.8	O K
2160 min Summer	34.064	0.464	0.2	27.5	O K
2880 min Summer	34.031	0.431	0.2	25.6	O K
4320 min Summer	33.975	0.375	0.2	22.3	O K
5760 min Summer	33.930	0.330	0.2	19.6	O K
7200 min Summer	33.892	0.292	0.2	17.3	O K
8640 min Summer	33.860	0.260	0.2	15.4	O K
10080 min Summer	33.832	0.232	0.2	13.8	O K
15 min Winter	33.837	0.237	0.2	14.1	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
15 min Summer	166.246	0.0	27
30 min Summer	108.697	0.0	41
60 min Summer	67.702	0.0	70
120 min Summer	41.667	0.0	130
180 min Summer	31.264	0.0	188
240 min Summer	25.407	0.0	248
360 min Summer	18.809	0.0	366
480 min Summer	15.045	0.0	486
600 min Summer	12.589	0.0	604
720 min Summer	10.851	0.0	722
960 min Summer	8.538	0.0	960
1440 min Summer	6.054	0.0	1188
2160 min Summer	4.286	0.0	1560
2880 min Summer	3.357	0.0	1964
4320 min Summer	2.383	0.0	2772
5760 min Summer	1.878	0.0	3576
7200 min Summer	1.571	0.0	4392
8640 min Summer	1.364	0.0	5112
10080 min Summer	1.215	0.0	5864
15 min Winter	166.246	0.0	26

Alan Baxter Partnership LLP		Page 2
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3	
	Surface WAtEr Soakaway Design	
	Access Road	
Date 29/01/2025	Designed by ARWS	
File C1477-Soakaway Design-Access Road (0).SRCX	Checked by ARWS	
XP Solutions	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+45%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
30 min Winter	33.909	0.309	0.2	18.4	O K
60 min Winter	33.982	0.382	0.2	22.7	O K
120 min Winter	34.062	0.462	0.2	27.4	O K
180 min Winter	34.112	0.512	0.2	30.4	O K
240 min Winter	34.146	0.546	0.2	32.4	O K
360 min Winter	34.188	0.588	0.2	34.9	O K
480 min Winter	34.210	0.610	0.2	36.2	O K
600 min Winter	34.219	0.619	0.2	36.8	O K
720 min Winter	34.222	0.622	0.2	36.9	O K
960 min Winter	34.216	0.616	0.2	36.6	O K
1440 min Winter	34.184	0.584	0.2	34.7	O K
2160 min Winter	34.136	0.536	0.2	31.8	O K
2880 min Winter	34.093	0.493	0.2	29.3	O K
4320 min Winter	34.014	0.414	0.2	24.6	O K
5760 min Winter	33.947	0.347	0.2	20.6	O K
7200 min Winter	33.891	0.291	0.2	17.3	O K
8640 min Winter	33.843	0.243	0.2	14.4	O K
10080 min Winter	33.802	0.202	0.2	12.0	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
30 min Winter	108.697	0.0	41
60 min Winter	67.702	0.0	70
120 min Winter	41.667	0.0	128
180 min Winter	31.264	0.0	186
240 min Winter	25.407	0.0	244
360 min Winter	18.809	0.0	360
480 min Winter	15.045	0.0	476
600 min Winter	12.589	0.0	592
720 min Winter	10.851	0.0	706
960 min Winter	8.538	0.0	930
1440 min Winter	6.054	0.0	1346
2160 min Winter	4.286	0.0	1668
2880 min Winter	3.357	0.0	2132
4320 min Winter	2.383	0.0	3024
5760 min Winter	1.878	0.0	3864
7200 min Winter	1.571	0.0	4688
8640 min Winter	1.364	0.0	5448
10080 min Winter	1.215	0.0	6248

Alan Baxter Partnership LLP		Page 3
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAter Soakaway Design Access Road	
Date 29/01/2025 File C1477-Soakaway Design-Access Road (0).SRCX	Designed by ARWS Checked by ARWS	
XP Solutions Source Control 2020.1.3		

Rainfall Details

Rainfall Model	FEH	Data Type	Point	Cv (Winter)	0.840
Return Period (years)	100	Summer Storms	Yes	Shortest Storm (mins)	15
FEH Rainfall Version	2013	Winter Storms	Yes	Longest Storm (mins)	10080
Site Location	GB 565706 172866 TQ 65706 72866	Cv (Summer)	0.750	Climate Change %	+45

Time Area Diagram

Total Area (ha) 0.041

Time (mins)	Area	Time (mins)	Area	Time (mins)	Area
From:	To:	From:	To:	From:	To:
	(ha)		(ha)		(ha)
0	4 0.014	4	8 0.014	8	12 0.014

Alan Baxter Partnership LLP		Page 4
The Clock Building Loose ME15 0HZ	C1477 - Convent of Mercy Ph. 3 Surface WAtEr Soakaway Design Access Road	
Date 29/01/2025	Designed by ARWS	
File C1477-Soakaway Design-Access Road (0).SRCX	Checked by ARWS	
XP Solutions	Source Control 2020.1.3	

Model Details

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 33.600 Infiltration Coefficient Side (m/hr) 0.02016 Porosity 0.95
Infiltration Coefficient Base (m/hr) 0.02016 Safety Factor 2.0

Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)
0.000	62.5	62.5	0.800	62.5	90.5	0.900	0.0	90.5

Appendix F
Schematic Drainage Design



- Notes**
- © Copyright Alan Baxter Partnership LLP
- This drawing & design is the copyright of Alan Baxter Partnership LLP and must not be copied in part or whole without consent.
- Do not scale off this drawing
- To be read in conjunction with all Architects and Engineers drawings
 - Level design is based on information from a topographical survey provided by others. Alan Baxter Partnership LLP takes no responsibility for the accuracy of the original topographical survey. All existing levels are to be confirmed by the contractor prior to the commencement of the works.
 - All discrepancies to be notified immediately to contract administrator and engineers.
 - Only 'Construction' drawings shall be used for construction or the ordering of materials. Any other drawings (tender / billing / work in progress etc.) drawings shall not be used for this purpose.
 - All proposals to be in accordance with Design and Construction Guidance (Sewerage Sector Guidance).
 - All rainwater pipe (RWP), soil vent pipe (SVP) and stub stack (SS) locations are approximate. Refer to Architects drawings for exact locations.
 - All special DPC detailing (required due to levels) to be in accordance with Architect details.
 - Stub stack's (SS) are to incorporate air admittance valves.
 - The invert level of the bottom bends for all SVP's and SS's are to be 600mm below F.F.L.
 - Pipes to be laid soffit-to-soffit unless otherwise noted.
 - 100mmØ Foul Drains to be laid at a minimum gradient of 1:80. 150mmØ Foul Drains to be laid at a minimum gradient of 1:150.
 - Diffuser units to be laid on top of impermeable liner at road formation level within subbase storage areas.
 - All above ground drainage to be in accordance with Architect drawings.
 - Contractor to avoid clashes with any existing services or infrastructure (any infrastructure to be retained/diverted/abandoned to be done by others and in accordance with Engineering drawings).
 - All critical existing levels to be determined on site by Contractor prior to construction.
 - If any drainage connections from adjacent sites are discovered, the engineer is to be notified immediately.
 - For Channel Drain details refer to channel drain run schedule / calculations, Channel access and outlet boxes to have silt traps. Grating Finish to Architects Specification.
 - Foul Water Pump and Rising Main to specialists design with suitable emergency storage capacity to be provided.
 - All below ground drainage materials and installation to be in accordance with the most up to date Sewerage Sector Guidance Design & Construction Guide.

Key

Existing

Foul Water (Retained)

Carrier pipe

Chamber

Proposed

Surface Water (Private)

RWP Rainwater Pipe (refer to note)

Carrier Pipe (100mm UPVC unless stated otherwise)

Rising Main (refer to note)

1200 CP Inspection Chamber (with ref. no.)

1200 CP Catchpit Chamber (with ref. no.)

RG Road Gully

CH Channel Drain (refer to note)

AP Channel Drain Access Point with Sump

Permeable Paving (Sub-Base Storage) (formation to fall towards filter pipe)

Diffuser Unit (Refer to note 13 - 710 wide x 710 long x 150mm (deep units)

Soakaway (install to manufacturers detail)

Soakaway Access Turret

Foul Water (Private)

SVP/SS Soil Vent Pipe / Stub Stack (refer to notes)

Carrier Pipe (100mm UPVC unless stated otherwise)

Rising Main (refer to note)

1200 CP Inspection chamber (with ref. no.)

Pump Station (refer to note)

-				
-				
0	FIRST ISSUE	ARWS	-	29/01/2025

ALAN BAXTER PARTNERSHIP LLP
CONSULTING STRUCTURAL ENGINEERS

THE CLOCK BUILDING
PYMPES COURT
BUSBRIDGE ROAD
LOOSE
MAIDSTONE
KENT ME15 0HZ
TELEPHONE: 01622 744263
FAX: 01622 749270
EMAIL: mail@abpengineers.co.uk

ABP

Project Title:

**Convent of Mercy Phase 3,
Hillside Drive,
Gravesend
DA12 1NY**

Drawing Title:

**Below Ground Drainage
Schematic**

Scale:	1:200 @A1	Do not scale from drawing
Drawing Number:	C1477-SK-001	Rev: 0

FOR APPROVAL