

Delegated Report

Lawful Development Certificate (Existing)

Application no:	20240086
Location	99 Lamorna Avenue Gravesend Kent DA12 5PS
Proposal:	Application for a Lawful Development Certificate in respect of the existing single storey rear extension, dormer extension in rear roof slope and two rooflights in front roof slope.
Applicant:	Mr D Ponsford
Site Visit	N/A Desktop Assessment

Plans & Documents

- Application form;
- Drawing no. PA-01 – Location Plan
- Existing Block Plan;
- Proposed Block Plan; and
- Drawing no. 7636-P-01 Rev. A – Existing & Proposed Plans and Elevations.

Property Type

The property comprises a terraced dwelling.

Material Consideration

Town and Country Planning (General Permitted Development) (England) Order 2015 (as amended)

Relevant Planning History

Reference	Description	Decision	Decision Date
20230424	Application for Lawful Development Certificate in respect of the continued use of a single storey rear extension and loft conversion.	Certificate Refused	07.07.2023

Officer Assessment

Permitted Developments Rights Restrictions

Article 2 (3) Land (AONB, Conservation Area)	N
Article 4 Direction	N

Permitted Development Rights Removed/Restricted

N

The existing single storey rear stands to be considered under Class A:

Class A - The enlargement, improvement or other alteration of a dwellinghouse

A.1	Development is not permitted by Class A if –	Y/N
(a)	permission to use the dwellinghouse as a dwellinghouse has been granted only by virtue of Class M, N, P, PA or Q of Part 3 of this Schedule (changes of use)	N
(b)	as a result of the works, the total area of ground covered by buildings within the curtilage of the dwellinghouse (other than the original dwellinghouse) would exceed 50% of the total area of the curtilage (excluding the ground area of the original dwellinghouse)	N
(c)	the height of the part of the dwellinghouse enlarged, improved or altered would exceed the height of the highest part of the roof of the existing dwellinghouse	N
(d)	the height of the eaves of the part of the dwellinghouse enlarged, improved or altered would exceed the height of the eaves of the existing dwellinghouse	N
(e)	the enlarged part of the dwellinghouse would extend beyond a wall which – (i) forms the principal elevation of the original dwellinghouse; or (ii) fronts a highway and forms a side elevation of the original dwellinghouse	N N
(f)	subject to paragraph (g), the enlarged part of the dwellinghouse would have a single storey and - (i) extend beyond the rear wall of the original dwellinghouse by more than 4 metres in the case of a detached dwellinghouse, or 3 metres in the case of any other dwellinghouse, or (ii) exceed 4 metres in height	(i) N – its depth is 3m. (ii) N – it's height is 2.9m.
(g)	for a dwellinghouse not on article 2(3) land nor on a site of special scientific interest, the enlarged part of the dwellinghouse would have a single storey and - (i) extend beyond the rear wall of the original dwellinghouse by more than 8 metres in the case of a detached dwellinghouse, or 6 metres in the case of any other dwellinghouse, or (ii) exceed 4 metres in height;	N/A
(h)	the enlarged part of the dwellinghouse would have more than a single storey and – (i) extend beyond the rear wall of the original dwellinghouse by more than 3 metres, or (ii) be within 7 metres of any boundary of the curtilage of the dwellinghouse being enlarged which is opposite the rear wall of	N/A

	that dwellinghouse;	
(i)	the enlarged part of the dwellinghouse would be within 2 metres of the boundary of the curtilage of the dwellinghouse, and the height of the eaves of the enlarged part would exceed 3 metres	N – it is within 2m of two boundaries of the dwelling but its height is 2.9m.
(j)	the enlarged part of the dwellinghouse would extend beyond a wall forming a side elevation of the original dwellinghouse, and would – (i) exceed 4 metres in height, (ii) have more than a single storey, or (iii) have a width greater than half the width of the original dwelling; or	N/A
(ja)	any total enlargement (being the enlarged part together with any existing enlargement of the original dwellinghouse to which it will be joined) exceeds or would exceed the limits set out in sub-paragraphs (e) to (j);	N/A
(k)	it would consist of or include – (i) the construction or provision of a verandah, balcony or raised platform, (ii) the installation, alteration or replacement of a microwave antenna, (iii) the installation, alteration or replacement of a chimney, flue or soil and vent pipe, or (iv) an alteration to any part of the roof of the dwellinghouse	(i) N (ii) N (iii) N (iv) N
(l)	the dwellinghouse is built under Part 20 of this Schedule (construction of new dwellinghouses)	N
A.2	In the case of a dwellinghouse on article 2(3) land, development is not permitted by Class A if –	Y/N
(a)	it would consist of or include the cladding of any part of the exterior of the dwellinghouse with stone, artificial stone, pebble dash, render, timber, plastic or tiles;	N/A
(b)	the enlarged part of the dwellinghouse would extend beyond a wall forming a side elevation of the original dwellinghouse; or	N/A
(c)	the enlarged part of the dwellinghouse would have more than a single storey and extend beyond the rear wall of the original dwellinghouse.	N/A
(d)	any total enlargement (being the enlarged part together with any existing enlargement of the original dwellinghouse to which it will be joined) exceeds or would exceed the limits set out in sub-paragraphs (b) and (c).	N/A
A.3	Development is permitted by Class A subject to the following conditions –	Y/N
(a)	the materials used in any exterior work (other than materials used in the construction of a conservatory) must be of a similar appearance to those	Y – the extension is faced with painted render as per

	used in the construction of the exterior of the existing dwellinghouse;	the main dwelling.
(b)	any upper-floor window located in a wall or roof slope forming a side elevation of the dwellinghouse must be – (i) obscure-glazed, and (ii) non-opening unless the parts of the window which can be opened are more than 1.7 metres above the floor of the room in which the window is installed; and	N/A
(c)	where the enlarged part of the dwellinghouse has more than a single storey, or forms an upper storey on an existing enlargement of the original dwellinghouse, the roof pitch of the enlarged part must, so far as practicable, be the same as the roof pitch of the original dwellinghouse.	N/A

The existing rear dormer stands to be considered under Class B:

Class B - The enlargement of a dwellinghouse consisting of an addition or alteration to its roof.

1, Original Roof Volume (m ³)	N/A
2. Existing Roof Extensions (m ³)	N/A
Remaining Roof Volume (m ³)	N/A. No previous roof works had been undertaken therefore 40m ³ volume remains.

B.1	Development is not permitted by Class B if –	Y/N
(a)	Permission to use the dwellinghouse as a dwellinghouse has been granted only by virtue of Class M, N, P, PA or Q of Part 3 of this Schedule (changes of use);	N
(b)	Any part of the dwellinghouse would, as a result of the works, exceed the height of the highest part of the existing roof;	N
(c)	Any part of the dwellinghouse would, as a result of the works, extend, beyond the plane of any existing roof slope which forms the principal elevation of the dwellinghouse and fronts a highway;	N
(d)	The cubic content of the resulting roof space would exceed the cubic content of the original roof space by more than – (i) 40 cubic metres in the case of a terrace house, or (ii) 50 cubic metres in any other case;	(i) N – Total volume would be 27.98 cubic metres. (ii) N/A
(e)	It would consist of or include – the construction or provision of a verandah, balcony or raised platform or the installation, alteration or replacement of a chimney, flue or soil and vent pipe; or	N N

(f)	The dwellinghouse is on article 2 (3) land	N
B.2	Development is permitted by Class B subject to the following conditions –	Y/N
(a)	The materials used in any exterior work must be of a similar appearance to those used in the construction of the exterior of the existing dwellinghouse;	Y – they would not be tiles which the main roof is but the plastic cladding is of a similar red/brown appearance as the previous roof tiles.
(b)	The enlargement must be constructed so that – (i) other than in the case of a hip-to-gable enlargement or an enlargement which joins the original roof to the roof of a rear or side – extension (aa) the eaves of the original roof are maintained or reinstated; and (bb) the edge of the enlargement closest to the eaves of the original roof is, so far as practicable, not less than 0.2 metres from the eaves, measured along the roof slope from the outside edge of the eaves; and (ii) other than in the case of an enlargement which joins the original roof to the roof of a rear or side extension, no part of the enlargement extends beyond the outside face of any external wall of the original dwelling house; and	(i) The plans show that the dormer would be set up 0.4m from the eaves. (ii) N
(c)	Any window inserted on a wall or roof slope forming a side elevation of the dwellinghouse must be – (i) obscure-glazed, and (ii) non-opening unless the parts of the window which can be opened are more than 1.7 metres above the floor of the room in which the window is installed.	N/A

The existing rooflights in the front roof slope stand to be considered under Class C:


Class C - Any other alteration to the roof of a dwellinghouse.

C.1	Development is not permitted by Class C if -	Y/N
(a)	permission to use the dwelling as a dwellinghouse has been granted only by virtue of Class M, N, P, PA or Q of Part 3 of this Schedule (changes of use);	N
(b)	the alteration would protrude more than 0.15 metres beyond the plane of the slope of the original roof when measured from the perpendicular with the external surface of the original roof;	N
(c)	it would result in the highest part of the alteration being higher than the	N


	highest part of the original roof;	
(d)	it would consist of or include – (i) the installation, alteration or replacement of a chimney, flue or soil and vent pipe, or (ii) the installation, alteration or replacement of solar photovoltaics or solar thermal equipment.	(i) N (ii) N
C.2	Development is permitted by Class C subject to the condition that any window located on a roof slope forming a side elevation of the dwellinghouse must be- (a) obscure-glazed; and (b) non-opening unless the parts of the window which can be opened are more than 1.7 metres above the floor of the room in which the window is installed.	N/A

Analysis

The dormer calculations are as follows:



Dormer window — flat roof



Height (metres)

02.79

Depth (metres)

03.7

Length (metres)

05.42


Total Volume:

27.98

Calculate Volume

Reset

In respect of Class B B2 (b) (i) (bb) the previous application ref. 20230424 showed the existing dormer was 0.11m from the eaves, it therefore did not comply with this section as it was not less than 0.2m from the eaves. In this application the plans entitled 'As Constructed' show the dormer is set up 0.44m from the eaves. The agent was asked for a photograph to show this is how the dormer has been constructed. The photographs taken out of the dormer window looking down onto the roof show that the dormer is set up from the eaves. The agent advises that for context each row of tiles is approx. 120mm and so with two rows of tiles it can be seen that the dormer is now compliant with the 200mm distance from the eaves:



Overall the existing single storey rear extension, rear dormer extension and front rooflights comply with the parameters set out in Classes A, B and C of the Town and Country Planning (General Permitted Development) (England) Order 2015, as amended. As such planning permission is not required and a lawful development certificate can be granted.

Recommendation: Grant Lawful Development Certificate

Case Officer:	Ms Rebecca Harrison	Team Leader:	Miss Faye Hobbs
Signed:	<i>Rebecca Harrison</i>	Signed:	
Dated:	5th April 2024	Dated:	08 April 2024