



Application: 20240386

**TOWN AND COUNTRY PLANNING ACT 1990: SECTION 192 TOWN AND COUNTRY
PLANNING (DEVELOPMENT MANAGEMENT PROCEDURE) (ENGLAND) ORDER 2015 (AS
AMENDED)**

To: **Mr Guljar Singh**
C/O Mr Manahil Khan, Sanaa Designs
18 Grenadier Close
Rainham
ME8 8NQ

CERTIFICATE OF PROPOSED LAWFUL USE OR DEVELOPMENT

GRAVESHAM BOROUGH COUNCIL hereby certify that on 10th May 2024 the use, operation or matter described in the First Schedule hereto in respect of the land specified in the Second Schedule hereto and edged red on the plan attached to this certificate, **WOULD HAVE BEEN LAWFUL** within the meaning of Section 192 of the Town and Country Planning Act 1990 (as amended), for the following reason(s):-

The proposed development complies with the provisions of Schedule 2, Part 3, Class L of the Town and Country Planning (General Permitted Development) (England) Order 2015 (as amended) and as such, planning permission would not be required and a lawful development certificate can be granted.

First Schedule

Application for a Lawful Development Certificate for a proposed change of use to a 5 bed HMO.

Second Schedule

69 Milton Road
Gravesend
Kent
DA12 2PJ

INFORMATIVES:-

1 DECISION PLANS

For the avoidance of doubt, the forms, plans and documents upon which this decision is made comprise:

Application form for a Lawful Development Certificate for a Proposed Use or Development;
Drawing no. PL/69MR/SD100 Existing layouts;
Drawing no. PL/69MR/SD101 Existing elevations
Drawing no. PL/69MR/SD102A Proposed basement layout;
Drawing no. PL/69MR/SD103A Proposed ground floor layout;
Drawing no. PL/69MR/SD104A Proposed first floor layout;
Drawing no. PL/69MR/SD105A Proposed second floor layout;
Drawing no. PL/69MR/SD106 Proposed elevations;
Drawing no. PL/69MR/SD107 Red line site boundary plan; and
Letter from the agent dated 03 July 2024.

2 WORKS OF CONSTRUCTION

Hours of work of construction site plant, equipment and machinery, should be restricted to not earlier than 7.00 a.m. and not later than 6.00 p.m. weekdays and Saturday working should be restricted to not earlier than 8.00a.m. and not later than 1.00 p.m. No work shall be carried out on Sundays, Bank or Public Holidays.

- i. Suitable sound attenuation shall be used at all times in respect of all plant, machinery and equipment in operation on site in order to aid prevention of noise nuisance. Compliance with BS 5228: Part 1: 1984 and subsequent amendments regarding the use of equipment on site will be required in appropriate cases.
- ii. A suitable method of control shall be used in order to aid prevention of dust nuisance arising from work activities on site.
- iii. Burning of waste materials shall not be carried out on site. Such materials are to be stored in a suitable receptacle, as far from residential accommodation as reasonably practicable, pending disposal off site.
- iv. Adequate arrangements shall be made to remove all waste material from the site on a regular basis and to dispose of it at a suitably licensed waste disposal site.

3 SMALL HOUSE IN MULTIPLE OCCUPATION (HMO)

The applicant is requested to note that small HMOs are defined in Class C4 in the Town and Country Planning (Use Classes) Order 1987 (as amended) as;

"Small shared houses occupied by between three and six unrelated individuals, as their only or main residence, who share basic amenities such as a kitchen or bathroom."

As such, the application property cannot be occupied by more than six persons without planning permission having first been obtained.

4 ADVICE FROM KENT POLICE DESIGNING OUT CRIME TEAM

Please note the following comments;

We have reviewed this application in regard to Crime Prevention Through Environmental Design (CPTED) and in accordance with the National Planning Policy Framework (NPPF).

Applicants/agents should consult us as Designing out Crime Officers (DOCO's) to address CPTED and incorporate Secured By Design (SBD) as appropriate. We use details of the site, relevant crime levels/type and intelligence information to help design out the opportunity for Crime, Fear of Crime, Anti-Social Behaviour (ASB), Nuisance and Conflict.

There is a carbon cost for crime and new developments give an opportunity to address it. Using CPTED along with attaining an SBD award using SBD guidance, policies and academic research would be evidence of the applicants' efforts to design out the opportunity for crime.

We recommend SBD guidance is utilised to address designing out crime to show a clear audit trail for Designing Out Crime, Crime Prevention and Community Safety and to meet our Local Authority statutory duties under Section 17 of the Crime and Disorder Act 1998. The points below identify my recommendations for the layout and design of this scheme.

1. Perimeter, boundary and divisional treatments must be a minimum of 1.8m high. Any alleyways must have secure side gates, which are lockable from both sides, located flush to the front building line.
2. We advise against the use of parking courts as they can create an opportunity for crime. Where unavoidable, the areas must be covered by natural surveillance from an "active" window e.g. lounge or kitchen and sufficient lighting - the same recommendations apply to on plot parking bays. In addition, we request appropriate signage for visitor bays to avoid conflict and misuse.

3. New trees should help protect and enhance security without reducing the opportunity for surveillance or the effectiveness of lighting. Tall slender trees with a crown of above 2m rather than low crowned species are more suitable than "round shaped" trees with a low crown. New trees should not be planted within parking areas or too close to street lighting. Any hedges should be no higher than 1m, so that they do not obscure vulnerable areas.
4. Lighting. Please note, whilst we are not qualified lighting engineers, any lighting plan should be approved by a professional lighting engineer (e.g. a Member of the ILP), particularly where a lighting condition is imposed, to help avoid conflict and light pollution. Bollard lighting should be avoided, SBD Homes 2019 states: "18.3 Bollard lighting is purely for wayfinding and can be easily obscured. It does not project sufficient light at the right height making it difficult to recognise facial features and as a result causes an increase in the fear of crime. It should be avoided." Lighting of all roads including main, side roads, cul de sacs and car parking areas should be to BS5489-1:2020 in accordance with SBD and the British Parking Association (BPA) Park Mark Safer Parking Scheme specifications and standards.
5. All external doorsets (a doorset is the door, fabrication, hinges, frame, installation and locks) including folding, sliding or patio doors to meet PAS 24: 2022 UKAS certified standard, STS 201 or LPS 2081 Security Rating B+. Please Note, PAS 24: 2012 tested for ADQ (Building Regs) has been superseded and is not suitable for this development.
6. Windows on the ground floor or potentially vulnerable e.g. from flat roofs or balconies to meet PAS 24: 2022 UKAS certified standard, STS 204 Issue 6:2016, LPS 1175 Issue 8:2018 Security Rating 1/A1, STS 202 Issue 7:2016 Burglary Rating 1 or LPS 2081 Issue 1.1:2016 Security Rating A. Glazing to be laminated. Toughened glass alone is not suitable for security purposes.
7. Bedroom windows on the ground floor require a defensive treatment to deflect loitering, especially second bedrooms often used by children.
8. We recommend "A GUIDE FOR SELECTING FLAT ENTRANCE DOORSETS 2019" for buildings featuring multiple units, any covered access must deflect loitering that can stop residents and their visitors from using it without fearing crime. Entrance doors must be lit and designed to provide no hiding place.
9. For the main communal doors audio/visual door entry systems are required. We strongly advise against trade buttons and timed-release mechanisms, as they permit unlawful access and have previously resulted in issues with Crime and ASB.
10. Cycle and Bin Stores must be well lit and lockable, with controlled access for the residents within the flats.
11. Mail delivery to meet SBD TS009 are strongly recommended for buildings with multiple occupants along with a freestanding post box of SBD/Sold Secure approved Gold standard. If mail is to be delivered within the lobby, there must be an access controlled door leading from the lobby to the apartments/ stairs on the ground floor to prevent access to all areas.
12. CCTV is advised for all communal entry points and to cover the mail delivery area.

If approved, site security is required for the construction phase. There is a duty for the principle contractor "to take reasonable steps to prevent access by unauthorised persons to the construction site" under the Construction (Design and Management) Regulations 2007. The site security should incorporate plant, machinery, supplies, tools and other vehicles and be site specific to geography and site requirements.

We welcome a discussion with the applicant/agent about site specific designing out crime. If the points above are not addressed, they can affect the development and local policing.

This information is provided by Kent Police DOCO's and refers to situational crime prevention. This advice focuses on CPTED and Community Safety with regard to this specific planning application.

Dated: 3 July 2024

Civic Centre
Windmill Street
Gravesend
Kent
DA12 1AU

Shazad Ghani
MPhil, MA, BA (Hons)
Head of Planning
Planning Service

NOTES

This certificate is issued solely for the purpose of Section 192 of the Town and Country Planning Act 1990 (as amended).

It certifies that the use, operation or matter specified in the First Schedule taking place on the land described in the Second Schedule would have been lawful, on the specified date and, thus, was would not have been liable to enforcement action under Section 172 of the 1990 Act on that date.


This certificate applies only to the use, operation or matter described in the First Schedule and identified on the attached plan. Any use, operation or matter which is materially different from that described or which relates to other land may render the owner or occupier liable to enforcement action.

The effect of the certificate is also qualified by the proviso in Section 192(4) of the 1990 Act, as amended, which states that the lawfulness of a described use, operation or matter is only conclusively presumed where there has been no material change, before the use is instituted or the operation begun, in any of the other matters relevant to determining such lawfulness.

Gravesham Borough Council

Application	20240386
Site Address	69 Milton Road Gravesend Kent DA12 2PJ
Date	3 July 2024
PMSA Number	0100019166

OS Map – Scale 1:1,250



Reproduced from the Ordnance Survey map with permission of the Controller of Her Majesty's Stationery Office © Crown Copyright 2012.

Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings.