TREE SCHEDULE

NO.	GIRTH (1M)	SPREAD	HEIGHT	TYPE
1	0.30	6.00	7.00	?
2	0.30	6.00	7.00	?
3	0.40	7.00	7.00	?
4	0.50	6.00	10.00	FIR
5	0.45	8.00	10.00	?
6	0.35	6.00	8.00	FIR
7	0.35	6.00	8.00	FIR
8	0.50MS	10.00	12.00	?
9	1.90	10.00	1.00	MAST
10	0.60MS	5.00	8.00	FIR
11	0.60TB	8.00	10.00	HOLLY
12	0.50MS	4.00	8.00	FIR
13	1.00MS	6.00	8.00	FIR
14	0.60MS	6.00	8.00	FIR
15	0.60MS	6.00	8.00	FIR
16	0.60MS	6.00	8.00	FIR
17	0.60MS	6.00	8.00	FIR
18	0.60MS	6.00	8.00	FIR
19	0.60	10.00	12.00	?
20	0.45	8.00	10.00	OAK
21	0.60	0.00	0.00	STUMP
22	0.50	8.00	10.00	?
23	0.40	10.00	12.00	?
24	0.65	16.00	20.00	FIR
25	0.35	12.00	12.00	?
26	0.50	10.00	12.00	COPPER BEECH
27	0.30	6.00	8.00	FIR
28	0.30	5.00	3.00	?
29	0.40	10.00	12.00	OAK
30	0.60	12.00	12.00	?
31	0.55	12.00	15.00	COPPER BEECH
32	0.30	6.00	6.00	FIR
33	0.50	3.00	3.00	?
34	0.60	12.00	12.00	?
35	0.30	8.00	10.00	FIR
36	0.70TB	8.00	10.00	FIG
37	1.00MS	10.00	12.00	?
38	0.35	6.00	8.00	FIR
39	0.35	6.00	8.00	FIR
40	0.25	8.00	10.00	BEECH
41	0.25	8.00	10.00	BEECH
42	0.25	8.00	10.00	BEECH
43	0.30	6.00	8.00	?

564550 564575 564600 564625 564650 564675 564700

172400 172375 172350 172325 172300 1724375

Copyright Land Utility Group

ABBREVIATIONS

ABH	Arched Beam Height	KO	Kerb Outlet
B	Brick	L	Light
BAL	Balcony	LP	Lamp Post
BB	Bellaha Beacon	MH	Manhole
BD	Bollard	MKR	Marker
BH	Beam Height	MSF	Metal Security Fence
BL	Bed Level	N/A	No Access
BP	Brick Pier	OHC	Overhead Cables
BRW	Brick Retaining Wall	P	Post
BS	Bus Stop	PALF	Palisade Fence
BT	British Telecom	PF	Picket Fence
BW	Brick Wall	PIT	Trial Pit
BWF	Barbed Wire Fence	PL	Pavement Light
C	Concrete	PM	Parking Meter
CAB	Cabinet	PRF	Post & Rail Fence
CBF	Close Boarded Fence	PWF	Post & Wire Fence
CBW	Concrete Block Wall	R	Render
CIF	Corrugated Iron Fence	RAD	Radiator
CL	Cover Level	RE	Rodding Eye
CLF	Chain Link Fence	RH	RH
COL	Column	RS	Road Sign
CPF	Concrete Panel Fence	RWP	Rain Water Pipe
CPS	Concrete Paving Slabs	S	Stone
CRW	Concrete Retaining Wall	SV	Stop Valve
CSU	Ceiling Slopes Up	SL	Skylight
CTV	Cable Television	SP	Soil Pipe
CW	Concrete Wall	SPS	Stone Paving Slabs
CZY	Crazy Paving	SRW	Stone Retaining Wall
D	Door	SW	Stone Wall
DH	Door Height	SWS	Surface Water Sewer
EC	Electricity Cover	TJ	Top of Joist
ESG	Electrical Switch Gear	T	TILE
EH	EH	TI	Timber
EP	Electricity Pole	TRW	Timber Retaining Wall
FB	Flower Bed	UJ	Underside of Joist
FC	False Ceiling	UR	Underside of Ridge Board
F/E	Fire Escape	UWP	Underside of Wall Plate
FH	Fire Hydrant	V	Vent
FL	Floor Level	VP	Vent Pipe
GY	Gully	W	Window
GV	Gas Valve	WL	Water Level
HA	Hatch	WM	Water Meter
IC	Inspection Cover	WMF	Wire Mesh Fence
IL	Invert Level	WPF	Wooden Panel Fence
IRF	Iron Railing Fence	WCL	Window Cill Height
IWF	Interwoven Fence	WHL	Window Head Height
		WRW	Wooden Retaining Wall

Top / Banks / Bottom — Fences — Change in Surface — Edge of Vegetation — OS Data

3.28 Floor to Ceiling Height — Gate — Survey Station — +10.60 Floor Level — Tree

STATION CO-ORDINATE TABLE

Ref.	East	North	Elevation
1	564619.500	172381.890	34.150
2	564685.842	172367.720	35.740

NOTES

1. ALL LEVELS SHOWN ARE RELATED TO ORDNANCE SURVEY GPS DATUM.
2. TREE TYPES SHOWN ON THIS DRAWING CANNOT BE GUARANTEED AND IF CRITICAL SHOULD BE VERIFIED BY A TREE SPECIALIST, TREE SPREADS ARE AVERAGES UNLESS OTHERWISE INDICATED. TREE HEIGHTS ARE APPROXIMATE.
3. ALTHOUGH CARE HAS BEEN TAKEN, DUE TO ACCESS LIMITATIONS ALL HIGH LEVEL DETAIL HAS BEEN SURVEYED REMOTELY AND NOT CHECKED BY PHYSICAL MEASUREMENTS.
4. ALL CRITICAL MEASUREMENTS MUST BE CHECKED / VERIFIED.
5. ALL CO-ORDINATES AND LEVELS SHOWN RELATE TO AN ORDNANCE SURVEY DERIVED GRID.
6. ALL DRAINAGE INFORMATION SHOWN SHOULD BE VALIDATED IF CRITICAL. PIPE SIZES SHOWN ARE APPROXIMATE. CONNECTIONS BETWEEN MANHOLES HAVE BEEN DETERMINED BY SOUNDING METHODS ONLY AND CONSEQUENTLY SHOULD NOT BE RELIED UPON.

REVISIONS	DATE

INDICATIVE ONLY

SCALE: 1:250@A1
DATE: AUGUST 2021
DRAWN: SDC

TITLE: SITE SURVEY

JOB: MID KENT GOLF CLUB

CLIENT: MID KENT GOLF CLUB

DWG. No: LUG / 9.0

SCALE BAR 0 5M 10M

LAND UTILITY GROUP LTD.

MIDLANDS OFFICE
UNIT 10
STRENSHAM BUSINESS PARK
TWYNING ROAD
WORCESTER
WR8 9JZ

T: 0845 602 3966
M: 07979 367282

LONDON OFFICE
BRICKFIELD HOUSE
HIGH ROAD
THORNWOOD
EPPING
ESSEX
CM16 6TH

T: 01992 566698
M: 07977 112286
M: 07977 111935

smas worksafe contractor www.smasltd.com as recognised by SSIP SAFETY SCHEMES IN PROCUREMENT THE SURVEY INITIATIVE