

1. The Contractor is to locate, protect and divert as necessary all existing services on site prior to commencing work.
2. All areas of excavation are to be scanned and marked for existing services prior to any excavation.
3. Be aware of possible live drainage flows and foul effluent during construction. The Contractor shall assess and implement a safe working system and equipment (PPE) as necessary.
4. When working with live drainage there is an increased risk from waterborne diseases such as leptospirosis and wels disease.
5. Site is in proximity to Network Rail land, Railway embankment and Railway.
6. UXO risk (Unexploded Ordinance). Contractor to undertake all reasonable precaution to mitigate the risk of unexploded ordnance on site, in accordance with recommendations in site investigation report.

KEY

-
- 10 m
- 1m 2m 3m 4m 5m
- SCALE 1-100
- GRASS

Notes:

-

KEY PLAN

considine
civil + structural engineers

25 Hollingworth Court, Turkey Mill
Ashford Road, Maidstone. Kent ME14 5PP
t: 01622 919918 e: info@considine.co.uk
www.considine.co.uk

Project:
2 VALE ROAD, NORTHFLEET
GRAVESEND
KENT, DA11 8BZ

Drawing Title:
DRAINAGE LAYOUT
SHEET 1 OF 2

considine ref	drawn by	date	drawing scales	original paper size
3474	AM	DEC' 20	1:100@A1, 1:200@A3	A1

drawing reference :
 project originator volume level type role number
 3474- CON - 00 - XX - DR - C - 1510

status :	status description :
S0	SUITABLE FOR INFORMATION
revision :	revision status :
P04	PRELIMINARY