

**Results for 100 year +45% CC Critical Storm Duration. Lowest mass balance: 99.57%**



| Node Event        | US Node | Peak (mins) | Level (m) | Depth (m) | Inflow (l/s) | Node Vol (m³) | Flood (m³) | Status     |
|-------------------|---------|-------------|-----------|-----------|--------------|---------------|------------|------------|
| 15 minute summer  | 1       | 10          | 51.890    | 0.115     | 57.5         | 0.2367        | 0.0000     | OK         |
| 15 minute summer  | 2       | 11          | 50.526    | 0.208     | 137.4        | 0.5180        | 0.0000     | OK         |
| 15 minute summer  | 3       | 11          | 49.885    | 0.479     | 162.2        | 0.7809        | 0.0000     | SURCHARGED |
| 15 minute summer  | 4       | 11          | 49.378    | 0.342     | 156.6        | 0.3865        | 0.0000     | SURCHARGED |
| 15 minute summer  | 5       | 11          | 49.096    | 0.670     | 197.6        | 1.2614        | 0.0000     | SURCHARGED |
| 15 minute summer  | 6       | 11          | 48.344    | 0.646     | 195.7        | 0.7305        | 0.0000     | SURCHARGED |
| 15 minute summer  | 7       | 12          | 47.758    | 0.533     | 194.9        | 0.6030        | 0.0000     | SURCHARGED |
| 15 minute summer  | 8       | 12          | 44.766    | 1.459     | 60.5         | 3.2353        | 0.0000     | FLOOD RISK |
| 15 minute summer  | 9       | 12          | 44.713    | 1.468     | 56.3         | 1.6604        | 0.0000     | SURCHARGED |
| 15 minute summer  | 10      | 12          | 44.657    | 1.469     | 70.0         | 1.6609        | 0.0000     | SURCHARGED |
| 15 minute summer  | 11      | 11          | 46.784    | 0.345     | 53.0         | 0.7336        | 0.0000     | SURCHARGED |
| 15 minute summer  | 12      | 10          | 48.571    | 0.109     | 67.1         | 0.2717        | 0.0000     | OK         |
| 15 minute summer  | 13      | 10          | 47.316    | 0.155     | 66.9         | 0.1753        | 0.0000     | OK         |
| 15 minute summer  | 14      | 11          | 44.573    | 1.616     | 163.2        | 2.3124        | 0.0000     | SURCHARGED |
| 15 minute summer  | 15      | 11          | 44.491    | 1.587     | 243.2        | 3.0103        | 0.0000     | SURCHARGED |
| 15 minute summer  | 16      | 11          | 44.252    | 1.973     | 471.8        | 3.7731        | 0.0000     | SURCHARGED |
| 15 minute summer  | 17      | 11          | 44.136    | 2.157     | 1005.3       | 9.2227        | 0.0000     | SURCHARGED |
| 15 minute summer  | 18      | 11          | 43.791    | 1.945     | 1034.9       | 3.8258        | 0.0000     | SURCHARGED |
| 15 minute summer  | 19      | 11          | 46.160    | 1.105     | 39.6         | 1.9145        | 0.0000     | SURCHARGED |
| 15 minute summer  | 20      | 12          | 43.247    | 1.684     | 1132.6       | 3.6816        | 0.0000     | SURCHARGED |
| 960 minute summer | 21      | 660         | 43.102    | 1.602     | 124.7        | 2.8314        | 0.0000     | SURCHARGED |
| 960 minute summer | 22      | 660         | 43.102    | 1.632     | 179.2        | 1424.1640     | 0.0000     | OK         |
| 15 minute summer  | 23      | 12          | 52.703    | 0.838     | 41.8         | 1.5678        | 0.0000     | SURCHARGED |
| 15 minute summer  | 24      | 12          | 52.624    | 1.175     | 77.0         | 2.2844        | 0.0000     | FLOOD RISK |
| 15 minute summer  | 25      | 12          | 52.008    | 0.736     | 69.5         | 0.8319        | 0.0000     | SURCHARGED |
| 15 minute summer  | 26      | 12          | 53.016    | 1.345     | 23.2         | 2.1056        | 0.0000     | FLOOD RISK |
| 15 minute summer  | 27      | 12          | 51.664    | 0.491     | 84.4         | 0.5552        | 0.0000     | SURCHARGED |
| 15 minute summer  | 28      | 12          | 51.207    | 0.998     | 137.3        | 1.9519        | 0.0000     | SURCHARGED |

| Link Event (Outflow) | US Node | Link         | DS Node | Outflow (l/s) | Velocity (m/s) | Flow/Cap | Link Vol (m³) |
|----------------------|---------|--------------|---------|---------------|----------------|----------|---------------|
| 15 minute summer     | 1       | 1.000        | 2       | 57.5          | 2.710          | 0.500    | 0.6299        |
| 15 minute summer     | 2       | 1.001        | 3       | 133.8         | 2.116          | 0.728    | 2.0576        |
| 15 minute summer     | 3       | 1.002        | 4       | 156.6         | 2.522          | 1.015    | 1.3550        |
| 15 minute summer     | 4       | 1.003        | 5       | 153.1         | 2.785          | 0.507    | 0.5872        |
| 15 minute summer     | 5       | 1.004        | 6       | 195.7         | 2.852          | 0.850    | 1.2033        |
| 15 minute summer     | 6       | 1.005        | 7       | 194.9         | 2.768          | 0.885    | 0.8563        |
| 15 minute summer     | 7       | 1.006        | 16      | 194.9         | 2.768          | 1.092    | 0.5850        |
| 15 minute summer     | 8       | 2.000        | 9       | 56.3          | 0.979          | 0.796    | 1.0684        |
| 15 minute summer     | 9       | 2.001        | 10      | 70.0          | 0.994          | 0.985    | 0.9730        |
| 15 minute summer     | 10      | 2.002        | 14      | 84.0          | 1.193          | 1.186    | 1.3932        |
| 15 minute summer     | 11      | 3.000        | 14      | 50.6          | 1.285          | 1.270    | 1.5196        |
| 15 minute summer     | 12      | 4.000        | 13      | 66.9          | 2.762          | 0.472    | 0.4271        |
| 15 minute summer     | 13      | 4.001        | 14      | 66.5          | 2.519          | 0.632    | 0.2246        |
| 15 minute summer     | 14      | 2.003        | 15      | 180.1         | 1.145          | 1.127    | 3.3958        |
| 15 minute summer     | 15      | 2.004        | 16      | 252.2         | 1.950          | 0.744    | 5.7640        |
| 15 minute summer     | 16      | 1.007        | 17      | 479.2         | 1.342          | 0.530    | 11.5375       |
| 15 minute summer     | 17      | 1.008        | 18      | 993.5         | 2.783          | 1.058    | 4.7385        |
| 15 minute summer     | 18      | 1.009        | 20      | 1029.5        | 2.884          | 1.099    | 10.1182       |
| 15 minute summer     | 19      | 5.000        | 20      | 34.6          | 1.964          | 1.955    | 0.5230        |
| 15 minute summer     | 20      | 1.010        | 21      | 1127.4        | 3.159          | 3.129    | 15.0045       |
| 15 minute summer     | 21      | 1.011        | 22      | 1119.0        | 3.674          | 3.123    | 7.2256        |
| 720 minute summer    | 22      | Infiltration |         | 34.9          |                |          |               |
| 15 minute summer     | 23      | 6.000        | 24      | 34.1          | 0.980          | 0.379    | 0.5577        |
| 15 minute summer     | 24      | 6.001        | 25      | 69.5          | 1.747          | 1.745    | 1.1926        |
| 15 minute summer     | 25      | 6.002        | 27      | 68.1          | 1.712          | 1.616    | 0.5945        |
| 30 minute summer     | 26      | 7.000        | 27      | 16.4          | 2.097          | 1.779    | 0.1263        |
| 15 minute summer     | 27      | 6.003        | 28      | 88.3          | 2.261          | 0.606    | 0.4943        |
| 15 minute summer     | 28      | 6.004        | 29      | 133.1         | 3.407          | 1.223    | 0.7123        |

**Results for 100 year +45% CC Critical Storm Duration. Lowest mass balance: 99.57%**

| Node Event        | US Node | Peak (mins) | Level (m) | Depth (m) | Inflow (l/s) | Node Vol (m³) | Flood (m³) | Status     |
|-------------------|---------|-------------|-----------|-----------|--------------|---------------|------------|------------|
| 15 minute summer  | 29      | 12          | 49.554    | 0.181     | 133.1        | 0.2049        | 0.0000     | OK         |
| 15 minute summer  | 30      | 10          | 47.016    | 0.111     | 43.3         | 0.2215        | 0.0000     | OK         |
| 15 minute summer  | 31      | 11          | 46.462    | 0.197     | 171.6        | 0.2233        | 0.0000     | OK         |
| 15 minute summer  | 32      | 10          | 49.245    | 0.100     | 76.1         | 0.2488        | 0.0000     | OK         |
| 15 minute summer  | 33      | 10          | 47.150    | 0.118     | 76.0         | 0.1335        | 0.0000     | OK         |
| 15 minute summer  | 34      | 10          | 45.757    | 0.126     | 75.7         | 0.1421        | 0.0000     | OK         |
| 15 minute summer  | 35      | 11          | 44.564    | 0.325     | 75.4         | 0.3675        | 0.0000     | SURCHARGED |
| 15 minute summer  | 36      | 12          | 44.246    | 0.606     | 102.4        | 1.0490        | 0.0000     | SURCHARGED |
| 15 minute summer  | 37      | 11          | 44.049    | 0.483     | 103.4        | 0.5461        | 0.0000     | SURCHARGED |
| 15 minute summer  | 38      | 11          | 43.906    | 0.541     | 335.1        | 1.1827        | 0.0000     | SURCHARGED |
| 15 minute summer  | 39      | 11          | 43.615    | 0.626     | 412.0        | 1.6483        | 0.0000     | SURCHARGED |
| 960 minute summer | 40      | 660         | 43.103    | 0.779     | 49.3         | 1.1143        | 0.0000     | SURCHARGED |
| 960 minute summer | 41      | 660         | 43.102    | 1.321     | 60.9         | 1.8910        | 0.0000     | SURCHARGED |

| Link Event (Outflow) | US Node | Link  | DS Node | Outflow (l/s) | Velocity (m/s) | Flow/Cap | Link Vol (m³) |
|----------------------|---------|-------|---------|---------------|----------------|----------|---------------|
| 15 minute summer     | 29      | 6.005 | 31      | 133.3         | 4.043          | 0.910    | 1.2738        |
| 15 minute summer     | 30      | 8.000 | 31      | 43.2          | 2.248          | 0.436    | 0.3183        |
| 15 minute summer     | 31      | 6.006 | 38      | 170.8         | 3.637          | 0.696    | 1.7750        |
| 15 minute summer     | 32      | 9.000 | 33      | 76.0          | 3.983          | 0.382    | 0.2800        |
| 15 minute summer     | 33      | 9.001 | 34      | 75.7          | 3.451          | 0.488    | 0.3491        |
| 15 minute summer     | 34      | 9.002 | 35      | 75.4          | 2.714          | 0.606    | 0.7638        |
| 15 minute winter     | 35      | 9.003 | 36      | 69.5          | 1.902          | 0.669    | 0.4896        |
| 15 minute summer     | 36      | 9.004 | 37      | 103.4         | 1.469          | 1.461    | 1.2719        |
| 15 minute summer     | 37      | 9.005 | 38      | 103.7         | 1.488          | 1.454    | 0.8647        |
| 15 minute summer     | 38      | 6.007 | 39      | 332.7         | 2.478          | 0.686    | 2.6530        |
| 15 minute summer     | 39      | 6.008 | 40      | 404.2         | 2.892          | 0.879    | 5.2283        |
| 15 minute summer     | 40      | 6.009 | 41      | 403.3         | 2.546          | 0.490    | 1.3393        |
| 15 minute summer     | 41      | 6.010 | 22      | 404.2         | 2.551          | 2.535    | 4.1164        |



TYPICAL INFILTRATION BASIN ARRANGEMENT  
N.T.S.

- NOTES:
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE RELEVANT SPECIFICATION AND ALL OTHER RELATED DRAWINGS ISSUED BY THE ENGINEER.
  - DO NOT SCALE FROM THIS DRAWING. WORK FROM FIGURED DIMENSIONS ONLY.
  - ALL DIMENSIONS SHOWN ON THIS DRAWING ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
  - ALL DIMENSIONS, LEVELS AND SURVEY GRID CO-ORDINATES ARE TO BE CHECKED ON SITE AND THE ENGINEER NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF THE WORKS.
  - NO DEVIATION FROM THE DETAILS SHOWN ON THIS DRAWING IS PERMITTED WITHOUT PRIOR PERMISSION FROM THE ENGINEER.
  - ALL MATERIALS AND WORKMANSHIP SHALL COMPLY FULLY WITH THE MANUAL OF CONTRACT DOCUMENTS FOR HIGHWAY WORKS, VOLUME ONE, SPECIFICATION FOR HIGHWAY WORKS AND THE LOCAL AUTHORITY SPECIFICATION FOR ROAD CONSTRUCTION AND STANDARD DETAILS.
  - THE CONTRACTOR SHALL UNDERTAKE SUCH MATERIALS TESTING AS INDICATED IN THE SPECIFICATIONS AND SHALL INCLUDE THE COST OF TESTING IN THE TENDER.
  - UNLESS STATED OTHERWISE, ALL EXCAVATED MATERIAL SHALL BE DISPOSED OF AT AN APPROVED TIP OFF-SITE.
  - THE PUBLIC HIGHWAY AND WORKS WILL BE KEPT CLEAN AND FREE OF DEBRIS BY USE OF WHEEL WASHING FACILITIES AND ROAD SWEEPERS TO THE COUNCIL'S SATISFACTION.
  - ALL SETTING OUT SHALL BE AGREED ON-SITE WITH THE ENGINEER, PRIOR TO THE COMMENCEMENT OF THE WORKS.
  - UPON COMPLETION OF THE WORKS, THE CONTRACTOR SHALL UNDERTAKE ALL NECESSARY MAINTENANCE REPAIRS TO RETURN THE HIGHWAY TO ITS FORMER CONDITION.
  - THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY APPROVALS FROM THE LOCAL AUTHORITY PRIOR TO COMMENCING WORKS ON THE HIGHWAY.

- KERB NOTES:
- ALL KERBS TO BE IN ACCORDANCE WITH BS EN 1340.
  - ALL INSTITU CONCRETE TO FOUNDATION AND HAUNCH TO BE CLASS ST2 TO CL. 2602 OF SHW.
  - KERB FOUNDATION TO BE LAID ON ROLLED SUB-BASE OF MINIMUM THICKNESS 100mm.
  - THE KERB BED AND BACKING SHALL NORMALLY BE LAID IN ONE OPERATION.
  - WHERE THE BED IS LAID IN ADVANCE OF THE KERBS A 200x20mm DIA. MILD STEEL DOVEL BARS WILL BE REQUIRED IN BACKING AT 600mm CENTRES AND KERBS WILL BE BEDDED ON 10mm THICK MORTAR TO DESIGNATION (i) OF CL. 2404 OF SHW.
  - KERBS SHALL BE LAID WITH DRY JOINTS AND CLOSELY BUTTED TO ADJACENT KERBS AND CHANNELS.
  - TRANSITION KERBS SHALL BE USED AT ALL CHANGES IN KERB FACE.
  - FOR RADII OF 12m OR LESS AND CHANNELS OF THE APPROPRIATE RADIUS SHALL BE USED.
  - FOR RADII OF BETWEEN 12m AND 18m STRAIGHT KERBS 600mm LONG SHALL BE USED.
  - CUTTING KERBS AND CHANNELS SHALL BE APPROVED MECHANICAL MEANS.
  - THE LENGTH OF ANY KERB OR CHANNEL SHALL NOT BE LESS THAN 300mm.

- CONSTRUCTION NOTES:
- ALL SOFT SPOTS AND VOIDS SHALL BE REMOVED BEFORE CONSTRUCTION AND REPLACED WITH SUITABLE FILL MATERIAL.
  - APPROVED RESIDUAL WEEDKILLER, WHICH DOES NOT CONTAIN ATRAZINE OR SIMAZINE, MUST BE APPLIED TO ALL FORMATIONS.
  - ALL CONCRETE AND CEMENT MORTAR MUST BE SULPHATE RESISTING TO BS4021.
  - ALL CARBIDEWAY MATERIALS SHALL BE SUPPLIED.
  - ALL MATERIALS IN CARBIDEWAYS TO BE LAID BY MACHINE.
  - MINIMUM PAVEMENT DEPTH OF 450mm IS REQUIRED FOR NON FROST SUSCEPTIBLE MATERIAL.
  - CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING THE CBR VALUES FOR EACH ACCESS ROAD AND SHALL SUBMIT DETAILS OF THE PROPOSED CONSTRUCTION TO THE ENGINEER IN WRITING FOR APPROVAL PRIOR TO COMMENCING THE WORKS.
  - A CAPPING LAYER, WITH A MINIMUM THICKNESS OF 600mm WILL BE REQUIRED WHEN THE CBR OF THE SUB-GRADE IS LESS THAN 2.5%.
  - THE CBR OF THE COMPACTED CAPPING LAYER SHALL BE AT LEAST 15%.
  - ALL EARTHWORKS TO BE IN ACCORDANCE WITH SERIES 600 OF SHW.
  - PROPOSED PAVEMENT CONSTRUCTION DETAILS BASED ON A DESIGN CBR VALUE OF 3.0%, TO BE CONFIRMED AS NOTED.

|     |             |     |     |     |          |
|-----|-------------|-----|-----|-----|----------|
| P1  | FIRST ISSUE | JSH | AMC | AD  | 18-11-25 |
| Rev | Description | Drn | Chk | App | Date     |

|             |                  |
|-------------|------------------|
| Purpose:    | Status:          |
| PRELIMINARY | NOT YET APPROVED |

**ARDENT** CONSULTING ENGINEERS  
AN EMPLOYEE OWNED COMPANY

Third Floor  
The Hallmark Building  
52-56 Leadenhall Street  
London  
EC3M 5JE

Tel: 020 7680 4088  
Web: [www.ardent-ce.co.uk](http://www.ardent-ce.co.uk)  
E-mail: [enquiries@ardent-ce.co.uk](mailto:enquiries@ardent-ce.co.uk)

Client

**ESQUIRE DEVELOPMENTS**




Project Title:

**ROSE FARM, ISTEAD RISE**

Drawing Title:

**SUDS PRIVATE CONSTRUCTION DETAILS  
SHEET 1**

|                             |            |             |          |
|-----------------------------|------------|-------------|----------|
| Drawn by                    | Checked by | Approved by | Revision |
| JSH                         | AMC        | AD          | P1       |
| Scale                       | Date       |             |          |
| 1:NTS@A1                    | 18-11-25   |             |          |
| Drawing Number              |            |             |          |
| 2500920-ACE-XX-XX-DR-C-0611 |            |             |          |



- NOTES:
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE RELEVANT SPECIFICATION AND ALL OTHER RELATED DRAWINGS ISSUED BY THE ENGINEER.
  - DO NOT SCALE FROM THIS DRAWING. WORK FROM FIGURED DIMENSIONS ONLY.
  - ALL DIMENSIONS SHOWN ON THIS DRAWING ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
  - ALL DIMENSIONS, LEVELS AND SURVEY GRID CO-ORDINATES ARE TO BE CHECKED ON SITE AND THE ENGINEER NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF THE WORKS.
  - NO DEVIATION FROM THE DETAILS SHOWN ON THIS DRAWING IS PERMITTED WITHOUT PRIOR PERMISSION FROM THE ENGINEER.
  - ALL MATERIALS AND WORKMANSHIP SHALL COMPLY FULLY WITH THE MANUAL OF CONTRACT DOCUMENTS FOR HIGHWAY WORKS, VOLUME ONE, SPECIFICATION FOR HIGHWAY WORKS AND THE LOCAL AUTHORITY SPECIFICATION FOR ROAD CONSTRUCTION AND STANDARD DETAILS.
  - THE CONTRACTOR SHALL UNDERTAKE SUCH MATERIALS TESTING AS INDICATED IN THE SPECIFICATIONS AND SHALL INCLUDE THE COST OF TESTING IN THE TENDER.
  - UNLESS STATED OTHERWISE, ALL EXCAVATED MATERIAL SHALL BE DISPOSED OF AT AN APPROVED TIP OFF-SITE.
  - THE PUBLIC HIGHWAY AND WORKS WILL BE KEPT CLEAN AND FREE OF DEBRIS BY USE OF WHEEL WASHING FACILITIES AND ROAD SWEEPERS TO THE COUNCIL'S SATISFACTION.
  - ALL SETTING OUT SHALL BE AGREED ON-SITE WITH THE ENGINEER, PRIOR TO THE COMMENCEMENT OF THE WORKS.
  - UPON COMPLETION OF THE WORKS, THE CONTRACTOR SHALL UNDERTAKE ALL NECESSARY MAINTENANCE REPAIRS TO RETURN THE HIGHWAY TO ITS FORMER CONDITION.
  - THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY APPROVALS FROM THE LOCAL AUTHORITY PRIOR TO COMMENCING WORKS ON THE HIGHWAY.

- KERB NOTES:
- ALL KERBS TO BE IN ACCORDANCE WITH BS EN 1340.
  - ALL INSTITU CONCRETE TO FOUNDATION AND HAUNCH TO BE CLASS ST2 TO CL. 2602 OF SHW.
  - KERB FOUNDATION TO BE LAID ON ROLLED SUB-BASE OF MINIMUM THICKNESS 100mm.
  - THE KERB BED AND BACKING SHALL NORMALLY BE LAID IN ONE OPERATION.
  - WHERE THE BED IS LAID IN ADVANCE OF THE KERBS A 200x20mm DIA. MILD STEEL DOWEL BARS WILL BE REQUIRED IN BACKING AT 600mm CENTRES AND KERBS WILL BE BEDDED ON 10mm THICK MORTAR TO DESIGNATION (I) OF CL. 2404 OF SHW.
  - KERBS SHALL BE LAID WITH DRY JOINTS AND CLOSELY BUTTED TO ADJACENT KERBS AND CHANNELS.
  - TRANSITION KERBS SHALL BE USED AT ALL CHANGES IN KERB FACE.
  - FOR RADII OF 12m OR LESS AND CHANNELS OF THE APPROPRIATE RADIUS SHALL BE USED.
  - FOR RADII OF BETWEEN 12m AND 18m STRAIGHT KERBS 600mm LONG SHALL BE USED.
  - CUTTING KERBS AND CHANNELS SHALL BE APPROVED MECHANICAL MEANS.
  - THE LENGTH OF ANY KERB OR CHANNEL SHALL NOT BE LESS THAN 300mm.

- CONSTRUCTION NOTES:
- ALL SOFT SPOTS AND VOIDS SHALL BE REMOVED BEFORE CONSTRUCTION AND REPLACED WITH SUITABLE FILL MATERIAL.
  - APPROVED RESIDUAL WEEDKILLER, WHICH DOES NOT CONTAIN ATRAZINE OR SIMAZINE, MUST BE APPLIED TO ALL FORMATIONS.
  - ALL CONCRETE AND CEMENT MORTAR MUST BE SULPHATE RESISTING TO BS4021.
  - ALL CARBIDEWAY MATERIALS SHALL BE SUPPLIED AND LAID IN ACCORDANCE WITH BS EN 13108 & BS 59487.
  - ALL MATERIALS IN CARBIDEWAYS TO BE LAID BY MACHINE.
  - MINIMUM PAVEMENT DEPTH OF 450mm IS REQUIRED FOR NON FROST SUSCEPTIBLE MATERIAL.
  - CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING THE CBR VALUES FOR EACH ACCESS ROAD AND SHALL SUBMIT DETAILS OF THE PROPOSED CONSTRUCTION TO THE ENGINEER IN WRITING FOR APPROVAL PRIOR TO COMMENCING THE WORKS.
  - A CAPPING LAYER, WITH A MINIMUM THICKNESS OF 600mm WILL BE REQUIRED WHEN THE CBR OF THE SUB-GRADE IS LESS THAN 2.5%.
  - THE CBR OF THE COMPACTED CAPPING LAYER SHALL BE AT LEAST 15%.
  - ALL EARTHWORKS TO BE IN ACCORDANCE WITH SERIES 600 OF SHW.
  - PROPOSED PAVEMENT CONSTRUCTION DETAILS BASED ON A DESIGN CBR VALUE OF 3.0%, TO BE CONFIRMED AS NOTED.

|          |             |     |     |         |                  |
|----------|-------------|-----|-----|---------|------------------|
| P1       | FIRST ISSUE | AMC | AMC | AD      | 18-11-25         |
| Rev      | Description | Drn | Chk | App     | Date             |
| Purpose: | PRELIMINARY |     |     | Status: | NOT YET APPROVED |

**ARDENT** CONSULTING ENGINEERS  
AN EMPLOYEE OWNED COMPANY

Third Floor  
The Hallmark Building  
52-56 Leadenhall Street  
London  
EC3M 5JE

Tel: 020 7680 4088  
Web: [www.ardent-ce.co.uk](http://www.ardent-ce.co.uk)  
E-mail: [enquiries@ardent-ce.co.uk](mailto:enquiries@ardent-ce.co.uk)

www.ardentce.com

SAFETY  
PROCEDURES

|                                              |            |             |                           |
|----------------------------------------------|------------|-------------|---------------------------|
| Client                                       |            |             |                           |
| ESQUIRE DEVELOPMENTS                         |            |             |                           |
| Project Title:                               |            |             |                           |
| ROSE FARM, ISTEAD RISE                       |            |             |                           |
| Drawing Title:                               |            |             |                           |
| SuDS PRIVATE CONSTRUCTION DETAILS<br>SHEET 2 |            |             |                           |
| Drawn by                                     | Checked by | Approved by | Revision<br><br><b>P1</b> |
| JSH                                          | AMC        | AD          |                           |
| Scale                                        | Date       |             |                           |
| 1:NTS@A1                                     |            | 18-11-25    |                           |
| Drawing Number                               |            |             |                           |
| 2500920-ACE-XX-XX-DR-C-0612                  |            |             |                           |

## Model: SSK1000M

### INTRODUCTION

The STORMSHARK is a cutting-edge hydrodynamic vortex separator that sets the standard in the industry with its unique patented design and exceptional performance. Engineered specifically for Sustainable Drainage Systems (SuDS) treatment trains, the STORMSHARK delivers outstanding water quality treatment while significantly enhancing amenity and bio diversity downstream. It serves as a powerful guardian, effectively protecting controlled waters from harmful sediment-bound pollutants.

Manufactured in Germany for the global stormwater management market, every model in the STORMSHARK range not only meets but exceeds the most stringent German Stormwater Treatment standards, including DWA M153 D24 and D25. Furthermore, the STORMSHARK has undergone rigorous testing in the United States, fully complying with the guidelines established by the New Jersey Department of Environmental Protection (NJDEP).

The STORMSHARK's remarkable flexibility allows it to operate both online and offline, seamlessly integrating with or without an external bypass unit. This adaptability positions it as the definitive solution for a wide range of multi-treatment water purification processes.

### DESIGN CERTIFICATION & TESTING

- NJDEP 2021
- NRW Trennerlass (Independent German Lab & field test)
- DIBt

### PERFORMANCE

The STORMSHARK removes sediment bound contaminants. Available in differing sizes to suit site flows and conditions. The STORMSHARK removes over 50% of fine TSS (0–200 microns, median size 75 microns) at design flows and up to 99% of TDS 0.1 to 0.4mm (coarse).

| MITIGATION                       | TSS<br>Total Suspended Solids | TOTAL<br>METALS | TOTAL<br>HYDROCARBONS |
|----------------------------------|-------------------------------|-----------------|-----------------------|
| TSS Coarse                       | 0.99                          | 0.75            | 0.79                  |
| NJDEP*1                          | 0.5                           | 0               | 0                     |
| Turtle Enviro*2                  | 0.5                           | 0.4             | 0.45                  |
| British Water Code of Practice*3 | 0.8                           | 0.6             | 0.96*3                |

\*1 NJDEP protocol

\*2 "Best advice" (in part as NJDEP only covers TSS)

\*3 The British Water Code of Practice (Assessment of Manufactured Treatment Devices. Designed to Treat Surface Water Runoff) using DIBt and EN858 data.

### PLASTICS

|            |              |             |
|------------|--------------|-------------|
| NRW Tested | Polyethylene | Polystyrene |
| % Retained | 0.6224       | 0.7541      |

The STORMSHARK hydraulic flow rates have larger pipe connection sizes, ideal for sites where higher peak flows are anticipated or required. The STORMSHARK also affords ease of connection to twinwall and other structural wall drainage pipes commonly used in the UK storm water drainage market.

**\*Adjustable feet are fitted to this model, so the levels can be adjusted, if fitted into pre cast concrete chamber.**

### INSTALLATION:


The installation design should consider traffic loadings, ground conditions and variable ground water elevations. If in any doubt consult your schemes' Designer/Engineer. A suitably qualified professional is required to sign off the installation.

**\*To view installation instructions click here.**




### FEATURES

- Supplied as a single piece unit with machine pre-fitted into a PE twinwall chamber
- Pipework connections pre installed
- Can also be installed into PCC chambers
- Patented design that has been tested
- No head loss; the level inverts remain stable
- Cannot become air locked
- Inlet deflector plate creates a vortex
- Retains floatable materials and liquids
- Prevents re-suspension of settled solids
- Upward flow provides a uniform flow pathway, even at high design flows
- Shark toothed weir ensures balanced, optimised flow
- Simple maintenance required
- 25 year warranty



### SPECIFICATION

|                                       |                    |
|---------------------------------------|--------------------|
| Overall Height <b>A</b> :             | 1950mm             |
| Minimum Ø chamber required <b>B</b> : | 1050mm             |
| Height to Inlet centre <b>C</b> :     | 1587mm             |
| Standard Pipework Connection:         | 225mm              |
| Sediment Storage Capacity:            | 0.46m <sup>3</sup> |
| Oil/Debris Storage Capacity:          | 200 litres         |
| Machine Weight:                       | 70kg               |
| (Chamber weight not included)         |                    |



## **Appendix D - SuDS Management Plan**

| SUDS Element                  | Soakaways                                                                                                                                |                                                |
|-------------------------------|------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------|
| Maintenance Period            | Maintenance Task                                                                                                                         | Frequency                                      |
| <b>Regular Maintenance</b>    | Inspect for sediment and debris in pre-treatment components and flood of inspection tube or chamber and inside of concrete manhole rings | Annually                                       |
|                               | Cleaning of gutters and any filters on downpipes                                                                                         | Annually (or as required based on inspections) |
|                               | Trimming any roots that may be causing blockages                                                                                         | Annually (or as required)                      |
| <b>Occasional Maintenance</b> | Remove sediment and debris from pre-treatment components and flood of inspection tube or chamber and inside concrete manhole rings       | As required, based on inspections              |
| <b>Remedial Actions</b>       | Reconstruct soakaway and/or replace or clean void fill if performance deteriorates or failure occurs                                     | As required                                    |
|                               | Replacement of clogged geotextile (will require reconstruction of soakaway)                                                              | As required                                    |
| <b>Monitoring</b>             | Inspect silt traps and note rate of sediment accumulation                                                                                | Monthly in the first year and then annually    |
|                               | Check soakaway to ensure emptying is occurring                                                                                           | Annually                                       |

| <b>SUDS Element</b>           | <b>Detention Basin</b>                                                                                    |                                                         |
|-------------------------------|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------|
| <b>Maintenance Period</b>     | <b>Maintenance Task</b>                                                                                   | <b>Frequency</b>                                        |
| <b>Regular Maintenance</b>    | Remove litter and debris                                                                                  | Monthly (or as required)                                |
|                               | Cut the grass – for spillways and access routes                                                           | Monthly (during growing season), or as required         |
|                               | Cut grass - meadow grass in and around basin                                                              | Half yearly (spring, before nesting season, and autumn) |
|                               | Manage other vegetation and remove nuisance plants                                                        | Monthly (at start, then as required)                    |
|                               | Inspect inlets, outlets, and overflows for blockages, and clear is required                               | Monthly                                                 |
|                               | Inspect banksides, structures, pipework etc. for evidence of physical damage                              | Monthly                                                 |
|                               | Inspect inlets and facility surface for silt accumulation. Establish appropriate silt removal frequencies | Monthly (for first year), then annually or as required  |
|                               | Check any penstocks and other mechanical devices                                                          | Annually                                                |
|                               | Tidy all dead growth before start of growing season                                                       | Annually                                                |
|                               | Remove sediment from inlets, outlets and forebays                                                         | Annually (or as required)                               |
|                               | Manage wetland plants in outlet pool- where provided                                                      | Annually                                                |
| <b>Occasional Maintenance</b> | Reseed areas of poor vegetation growth                                                                    | As required                                             |

**SuDS Management & Maintenance Strategy****November 2025**

|                         |                                                                            |                                                                                                                       |
|-------------------------|----------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|
|                         | Prune and trim any trees and remove cuttings                               | Every 2 years, or as required                                                                                         |
|                         | Remove sediment from inlets, outlets, forebay and main basin when required | Every 5 years, or as required (likely to be minimal requirements where effective upstream source control is provided) |
| <b>Remedial Actions</b> | Repair erosion or other damage by reseeding or returfing                   | As required                                                                                                           |
|                         | Realignment of rip-rap                                                     | As required                                                                                                           |
|                         | Repair/rehabilitation of inlets, outlets and overflows                     | As required                                                                                                           |
|                         | Relevel uneven levels and reinstate design levels                          | As required                                                                                                           |

## STORMSHARK Operating Manual & Installation Instructions

For PPIC : Poly-Propylene Inspection Chamber Installation



### ATTENTION

This document contains  
important notes, please  
read carefully before  
commencement of  
your STORMSHARK  
Installation



# Table of Contents

General Information

Product Description

Working Principles

Installation into poly-propylene inspection chamber (PPIC)


Operating and Maintenance Instructions

Example Record Sheets

Professional Approval Certificate Example

Commissioning and Audit Protocol

Maintenance Record Sheets



# General Information

This manual should be completed and a copy left with the owner of the STORMSHARK unit. The information below should be completed by the installer of the STORMSHARK, or from the construction company, or the management company, who will remain responsible for the plant

## Location of the plant

|                  |  |
|------------------|--|
| Name of the Site |  |
| Address          |  |
| Postcode         |  |
| Telephone        |  |
| Email            |  |

## Operator of the plant

|                        |  |
|------------------------|--|
| Company / Municipality |  |
| Address                |  |
| Postcode               |  |
| Responsible Person     |  |
| Telephone              |  |
| Email                  |  |

## Construction Company

|                        |  |
|------------------------|--|
| Company / Municipality |  |
| Address                |  |
| Postcode               |  |
| Responsible Person     |  |
| Telephone              |  |
| Email                  |  |

## Design Details

|                        |  |
|------------------------|--|
| Type of Connected Area |  |
| Installation Date      |  |
| Commissioning Date     |  |
| No. of STORMSHARKS     |  |

# Product Description

All available sizes of the STORMSHARK have the same operational components

1. Inlet

2. Deflector Plate

3. Flow Breakers

4. Sludge Trap

5. Balancing Weir

6. Outlet



The STORMSHARK must only be handled and lifted by competent persons. Avoid any concentrated point loading. The unloading, storage and transport at site are entirely the responsibility of the Purchaser.


Backfill and excavation works are by other, in accordance with site designs, site ground conditions and legal requirements.

If you are in any doubt as to the function, applicability or safety of the device as supplied at site, you must seek Professional Advice from your supplier and/or a Professional Engineer.

The water quality flow rates and hydraulic peak capacity for the site would have been fully designed.

# Working Principles

Applicable to all STORMSHARK models apart from SSK750\*




1. Incoming stormwater is deflected into a radial flow pattern.
2. Vortex flow ensures solids settle to the sludge chamber, floatable's are retained at the surface.
3. Solids pass down into the sludge chamber below the treatment chamber. Remobilisation of the retained solids is not possible, flow baffles prevent this.
4. Cleaned water flows up the outer chamber in an even flow distribution.
5. Water flows over the toothed balancing weir to the annular flow channel surrounding the treatment chamber.
6. Clean stormwater passes to the outlet to discharge to the water environment.
7. Retained solids are easily removed by vacuum hose, once the retention safety grill\* is lifted using the lifting chain supplied and fitted within the unit.

\* The SSK750 models do not have the retention grill

# Installation Instructions

## For STORMSHARK models SSK750M and SSK1000M into PPIC



# Installation Instructions (continued)

## For STORMSHARK models SSK750M and SSK1000M into PPIC

---

### Instructions

1. Excavate pit for chamber, whilst supporting the wall according to legal requirements and ground conditions.
2. Pour concrete blinding layer for base, typically 50mm thick.
3. Cast in-situ concrete base slab.
4. Using safe and approved lifting methods, manoeuvre the chamber onto base slab and check the horizontal positioning is correct.
5. Maintenance and lifting cable is the appropriate length, if inverts are deeper this can be sited on the wall of the chamber
6. Align the left opening to the correct position to suit the drainage layout. The inlet end is identified by the deflector positioned in front of the inlet pipe.
7. Connect pipework to the chamber. We recommend rocker pipes to inlet and outlet, particularly where ground settlement might arise.
8. Backfill as detailed.
9. Position precast concrete cover slab.
10. Install Class B engineering brickwork or PCC seating rings.
11. Lay ductile iron cover & frame (appropriate load rating)

### Please Note:

- If in doubt regarding any of the above, we suggest you consult a professional engineer for further advice.
- At all times, the STORMSHARK must be protected against contamination & construction debris & physical damage during installation

# Operating and Maintenance Instructions

Due to the solids and pollutants in stormwater runoff, treatment systems must be checked and cleaned regularly. The following notes provide guidance for the typical work necessary for associated with the effective operation of a STORMSHARK.

## Annual Maintenance:

At intervals between 6 months and 3 years, the sludge trap must be emptied as the site conditions, local regulations, or site-specific conditions require. The amount of sludge depends on the local stormwater conditions and will vary between sites.

For Stormwater runoff with untypically low or high solids loads, these periods may vary. This can be observed and determined for a Programmed Maintenance Schedule, after the first few years of operation.

The STORMSHARK chamber is a confined space. It is not necessary to enter a STORMSHARK for routine maintenance. Local regulations must be fully observed in the event of planned or unplanned man entry.

**\*If in doubt you MUST consult a professional engineer who can advise you.**

## Equipment and materials typically required:

1. Suction and flushing vehicle, or submersible sludge pump with hoses.
2. Generator when there is no power connection nearby.
3. High-pressure cleaner or flushing lance for connection to the pump.

## Important pollution prevention notes:

The water pumped out of the chamber and the sludge trap may only be discharged into a foul or a combined sewer where local regulations allow. In no case may the foul water be discharged into a surface watercourse, a stormwater sewer, or a groundwater infiltration system.

If there is no possibility to discharge the water, a mobile water treatment system may be used.

The treated water can be discharged into a receiving water or storm sewer in accordance with local permits and regulations.

## Maintenance Instructions

1. Remove the layer of floatables and oils on the water surface. Lower the water level down to the level of the retention safety grill\* by means of suction hose.
2. Remove any coarse debris from the retention safety grill and then pull the grill up using the maintenance lifting cable.
3. Using a suction hose, remove the sludge and the solids from the sludge trap chamber. Make sure each section of the trap is cleared. Use water to rinse if necessary.
4. Close the grate, check the lock, and firmly secure the cover of the system.

\*For SSK1200 models it is preferable to use a 2" or a 3" suction hose.

**If you are in any doubt, you MUST consult a professional engineer or competent person to advise you. Your supplier will be able to direct you if they do not provide such a service themselves.**

# Example Record Sheets

Professional Approved Certificate Example  
For the construction or modifications of stormwater treatment systems.

## Project Details

|                                    |  |
|------------------------------------|--|
| Project Name                       |  |
| Designation of Sedimentation Plant |  |
| Professional / Expert (Name)       |  |
| Address                            |  |
| Postcode                           |  |
| Telephone                          |  |
| Email                              |  |

## Contractor

|                |  |
|----------------|--|
| Company (Name) |  |
| Address        |  |
| Postcode       |  |

## Location of the Stormshark

|          |  |
|----------|--|
| Address  |  |
| Postcode |  |

- I have installed the :
  - Piping System
  - Sedimentation Plant
  - New System
  - Modified the installation
  - Checked the install as a professional expert.
- The treated stormwater is / will be discharged into (tick as appropriate)

☐ a groundwater infiltration system

☐ receiving surface water

☐ stormwater sewer

☐ combined sewer
- The drainage system complies with the requirements of the valid standards.
- The pipes and components used for the system comply with the relevant product standards.
- I have received the installation instructions of the manufacturer and installed the system according to these instructions.
- The installation has been checked as complying with the valid standards and the general accepted rules of technology. The design corresponds to the planning documents including the proper execution of the preliminary work.

Date / Signature of Builder or Expert



# Commissioning and Audit Protocol for STORMSHARK

Please use this as an example template. Modify to suit local conditions.

Building Project Owner represented by

Specialist Company represented by

| No. | Feature                                                                     | Remarks |
|-----|-----------------------------------------------------------------------------|---------|
| 1.  | The STORMSHARK insert was fixed in the chamber by means of fixing anchors.  |         |
| 2.  | The STORMSHARK insert was aligned.                                          |         |
| 3.  | The uniform distance of the balancing weir to the chamber wall was checked. |         |
| 4.  | The bottom of the chamber was filled with 100mm of concrete.                |         |
| 5.  | The maintenance lifting cable is accessible and appropriately secured.      |         |

The instruction for the operation of the plant has been given. The required operating documents and existing operating and maintenance instructions according to the installation were handed over completely.

Signature of Contractor / Date

Signature of Owner / Date

# Maintenance Record Sheets

Please use this as an example template. Modify to suit local conditions.

Building Project Owner represented by

Specialist Company represented by

| Maintenance Interval | State Remark | Maintenance Work                                                                                                                                                                                                                                        | Name & Signature |
|----------------------|--------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|
| Date:                |              | <ul style="list-style-type: none"><li>◦ Inspection of the system for visable damage.</li><li>◦ Emptying and cleaning of the sludge trap.</li><li>◦ Grate is closed and locked.</li><li>◦ Maintenance lifting cable is accessible and secured.</li></ul> |                  |

|       |  |                                                                                                                                                                                                                                                         |  |
|-------|--|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| Date: |  | <ul style="list-style-type: none"><li>◦ Inspection of the system for visable damage.</li><li>◦ Emptying and cleaning of the sludge trap.</li><li>◦ Grate is closed and locked.</li><li>◦ Maintenance lifting cable is accessible and secured.</li></ul> |  |
|-------|--|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|

|       |  |                                                                                                                                                                                                                                                         |  |
|-------|--|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| Date: |  | <ul style="list-style-type: none"><li>◦ Inspection of the system for visable damage.</li><li>◦ Emptying and cleaning of the sludge trap.</li><li>◦ Grate is closed and locked.</li><li>◦ Maintenance lifting cable is accessible and secured.</li></ul> |  |
|-------|--|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|

# STORMSHARK Warranty

## Important Notes – Warranty Void if following conditions are not met



The installed product **MUST** be absolutely horizontal in its final position.

---

The STORMSHARK unit may be delivered on 30mm high adjustable feet; if so, the inlet and outlet openings must be 30mm higher to allow any adjustments to be made.

---

Please note that the STORMSHARK unit must be filled at the base with 10cm of concrete after installation within a concrete chamber to stabilise flow breaker plates.

If using other chamber materials, please consult your supplier.

---

This Manual should be completed and a copy left with the owner of the STORMSHARK unit.


---

A properly installed and commissioned STORMSHARK unit will be given a 25-year warranty in respect to both the PE materials and to the machine performance, subject to carrying out of adequate planned maintenance.



**turtle**

## **Appendix E – Exceedance Flood Routing Plan**




Reproduced from/based upon Ordnance Survey material.  
© Crown copyright and database rights 2024 OS AC0000851381

- NOTES:
1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE RELEVANT SPECIFICATION, INC. RISK ASSESSMENTS AND ALL OTHER RELATED DRAWINGS ISSUED BY THE ENGINEER.
  2. DO NOT SCALE FROM THIS DRAWING. WORK FROM FIGURED DIMENSIONS ONLY.
  3. ALL DIMENSIONS SHOWN ON THIS DRAWING ARE IN METRES UNLESS OTHERWISE STATED.
  4. ALL DIMENSIONS, LEVELS AND SURVEY GRID CO-ORDINATES ARE TO BE CHECKED ON SITE AND THE ENGINEER NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF THE WORKS.
  5. NO DEVIATION FROM THE DETAILS SHOWN ON THIS DRAWING IS PERMITTED WITHOUT PRIOR PERMISSION FROM THE ENGINEER.
  6. ANY WORKS OUTSIDE RED SITE BOUNDARY ARE FOR INFORMATION PURPOSES ONLY. UNLESS SPECIFICALLY NOTED, ALL WORKS OUTSIDE THE SITE BOUNDARY WILL BE UNDERTAKEN BY OTHERS UNDER A SEPARATE CONTRACT.

FLOOD ROUTING KEY

- SITE BOUNDARY  
▶ EXCEEDANCE ROUTING



|     |             |     |     |     |          |
|-----|-------------|-----|-----|-----|----------|
| P1  | FIRST ISSUE | JSH | AMC | AD  | 18-11-25 |
| Rev | Description | Drn | Chk | App | Date     |

|          |             |         |                  |
|----------|-------------|---------|------------------|
| Purpose: | PRELIMINARY | Status: | NOT YET APPROVED |
|----------|-------------|---------|------------------|

**ARDENT** CONSULTING ENGINEERS  
AN EMPLOYEE OWNED COMPANY

Third Floor  
The Hallmark Building  
52-56 Leadenhall Street  
London  
EC3M 5JE

Tel: 020 7680 4088  
Web: [www.ardent-ce.co.uk](http://www.ardent-ce.co.uk)  
E-mail: [enquiries@ardent-ce.co.uk](mailto:enquiries@ardent-ce.co.uk)

SSIP  
SAFETY  
SCHEDULED  
INSPECTION  
PROCEDURE


Client

ESQUIRE DEVELOPMENTS

Project Title:  
**ROSE FARM, ISTEAD RISE**

Drawing Title:  
**EXCEEDANCE ROUTING PLAN  
SHEET 1**

|                          |                          |                                                      |                       |
|--------------------------|--------------------------|------------------------------------------------------|-----------------------|
| Drawn by<br><b>JSH</b>   | Checked by<br><b>AMC</b> | Approved by<br><b>AD</b>                             | Revision<br><b>P1</b> |
| Scale<br><b>1:500@A1</b> | Date<br><b>18-11-25</b>  | Drawing Number<br><b>2500920-ACE-XX-XX-DR-C-0721</b> |                       |




Reproduced from/based upon Ordnance Survey material.  
© Crown copyright and database rights 2024 OS AC0000851381

- NOTES:
1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE RELEVANT SPECIFICATION, INC. RISK ASSESSMENTS AND ALL OTHER RELATED DRAWINGS ISSUED BY THE ENGINEER.
  2. DO NOT SCALE FROM THIS DRAWING. WORK FROM FIGURED DIMENSIONS ONLY.
  3. ALL DIMENSIONS SHOWN ON THIS DRAWING ARE IN METRES UNLESS OTHERWISE STATED.
  4. ALL DIMENSIONS, LEVELS AND SURVEY GRID CO-ORDINATES ARE TO BE CHECKED ON SITE AND THE ENGINEER NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF THE WORKS.
  5. NO DEVIATION FROM THE DETAILS SHOWN ON THIS DRAWING IS PERMITTED WITHOUT PRIOR PERMISSION FROM THE ENGINEER.
  6. ANY WORKS OUTSIDE RED SITE BOUNDARY ARE FOR INFORMATION PURPOSES ONLY. UNLESS SPECIFICALLY NOTED, ALL WORKS OUTSIDE THE SITE BOUNDARY WILL BE UNDERTAKEN BY OTHERS UNDER A SEPARATE CONTRACT.

FLOOD ROUTING KEY

- SITE BOUNDARY  
▶ EXCEEDANCE ROUTING



|    |             |     |     |    |          |
|----|-------------|-----|-----|----|----------|
| P1 | FIRST ISSUE | AMC | AMC | AD | 18-11-25 |
|----|-------------|-----|-----|----|----------|

|     |             |     |     |     |      |
|-----|-------------|-----|-----|-----|------|
| Rev | Description | Drn | Chk | App | Date |
|-----|-------------|-----|-----|-----|------|

|          |             |         |                  |
|----------|-------------|---------|------------------|
| Purpose: | PRELIMINARY | Status: | NOT YET APPROVED |
|----------|-------------|---------|------------------|

**ARDENT** CONSULTING ENGINEERS  
AN EMPLOYEE OWNED COMPANY

Third Floor  
The Hallmark Building  
52-56 Leadenhall Street  
London  
EC3M 5JE

Tel: 020 7680 4088  
Web: [www.ardent-ce.co.uk](http://www.ardent-ce.co.uk)  
E-mail: [enquiries@ardent-ce.co.uk](mailto:enquiries@ardent-ce.co.uk)

**worksafe**  
consultant  
[www.ardentce.com](http://www.ardentce.com)

**SSIP**  
SOCIETY OF  
SURVEYING  
INSTITUTIONS



Client

ESQUIRE DEVELOPMENTS

Project Title:

ROSE FARM, ISTEAD RISE

Drawing Title:  
**EXCEEDANCE ROUTING PLAN  
SHEET 2**

|                 |                   |                   |                       |
|-----------------|-------------------|-------------------|-----------------------|
| Drawn by<br>AMC | Checked by<br>AMC | Approved by<br>AD | Revision<br><b>P1</b> |
|-----------------|-------------------|-------------------|-----------------------|

|                   |                  |
|-------------------|------------------|
| Scale<br>1:500@A1 | Date<br>18-11-25 |
|-------------------|------------------|

Drawing Number  
**2500920-ACE-XX-XX-DR-C-0722**

## **Appendix F – Infiltration Test Results**